

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	96-00094-01-WR	KANE	187	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 83737				

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY STU I000-2A	SPRING TRAF SIGNAL STU Y031-1F	BOWES TRAF SIGNAL STU Y031-1F	LIGHT SPRING STU Y030-1E	LIGHT BOWES STU Y030-1E	INTER-CONNECT CMAQ Y031-1F	STATE 100% 1000-2A	VILLAGE NON-PART SPRING Y031-1F	VILLAGE NON-PART BOWES Y031-1F
* 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	129				78	51				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	8,113		255	189	2138	2441	3090			
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	24				12	12				
* 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	2				1	1				
* 83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	24				12	12				
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	260	20			120	120				
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	24				12	12				
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2				1	1				
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	4	2			1			1		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2	2								
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		1	1						
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		1	1						
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		1	1						
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1833		1395	438						
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2674		1866	808						
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	823		486	337						
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4675		2462	2213						
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1864			1864						
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	130		71	59						
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6		4	2						
* 87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2		1	1						
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1						
* 87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2		2							
* 87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1							
* 87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	2			2						
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24		16	8						
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	8		4	4						
* 87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	120		60	60						
* 87900200	DRILL EXISTING HANDHOLE	EACH	1						1			
* 88030020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		2	2						
* 88030100	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6		4	2						
* 88030110	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	12		6	6						
* 88030220	SIGNAL HEAD, L.E.D., 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		1	2						
* 88102710	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	6		4	2						
* 88102740	PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED	EACH	1			1						
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	16		8	8						
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	4			4						
* 88700200	LIGHT DETECTOR	EACH	4							2	2	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2							1	1	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	7		4	3						

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

URS 100 SOUTH WACKER DR. STE 500 TEL (312) 939-1000
CHICAGO, IL 60606 FAX (312) 939-4198

MCLEAN BOULEVARD
SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: ARM
DATE: 4/6/2007 CHECKED BY: DDL