

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	96-00094-01-WR	KANE	187	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**EARTHWORK SCHEDULE**

LOCATION	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	(1)	(2)	(3)	(4)
		CUT (CU YD)	FILL (CU YD)	ADJUSTED CUT (CU YD)	EXCESS (+) SHRINKAGE (-) (CU YD)
McLEAN BLVD.					
STA. 33+90 TO 37+00	122	68	101	58	-43
STA. 37+00 TO 45+00		1029	35	875	840
STA. 45+00 TO 49+00		2169	96	1844	1748
STA. 49+00 TO 55+00	381	2588	898	2200	1302
STA. 55+00 TO 61+00	936	3604	204	3063	2859
STA. 61+00 TO 67+00	1913	2720	26	2312	2286
STA. 67+00 TO 73+00	78	3844	99	3267	3168
STA. 73+00 TO 79+00	643	1705	131	1449	1318
STA. 79+00 TO 85+00	557	2601	79	2211	2132
STA. 85+00 TO 90+00	187	1954	259	1661	1402
SIDE STREETS					
SUNBURY RD.		-	-	-	-
HOPPS RD./SPRING ST.		4551	13	3868	3855
KANE ST.		-	-	-	-
SANDHURST LANE		-	-	-	-
JENNA DR.		-	-	-	-
SUNDOWN DR.		-	-	-	-
BOWES RD.		2342	501	1991	1490
TOTALS	4817	29175	2442	24799	22357

GENERAL NOTE: THE VOLUME FOR THE REMOVAL & DISPOSAL OF UNSUITABLE MATERIALS IS SEPARATE FROM THE CUT VOLUME. (SEE CROSS-SECTION SHEETS)

EXCESS/SHORTAGE NOTES:

SHRINKAGE FACTOR FOR COLUMNS (1) = 0.85  
 COLUMN (3) = COLUMN (1) x 0.85  
 COLUMN (4) = COLUMN (3) - COLUMN (2)

**TEMPORARY EARTHWORK SCHEDULE**

LOCATION	PRESTAGE		STAGE 1		(3) ADJUSTED CUT		(4) EXCESS (+) SHRINKAGE (-)	
	(1) CUT (CU YD)	(2) FILL (CU YD)	(1) CUT (CU YD)	(2) FILL (CU YD)	PRESTAGE	STAGE 1	PRESTAGE	STAGE 1
	STA 30+00 TO 37+00	68	101	176	194	58	150	-43
STA 37+00 TO 45+00	1029	36	139	37	875	118	839	81
STA 45+00 TO 49+00	2169	96	0	0	1844	0	1748	0
STA 49+00 TO 55+00	2588	899	0	0	2200	0	1301	0
STA 55+00 TO 61+00	3604	204	0	0	3063	0	2859	0
STA 61+00 TO 67+00	2719	26	0	0	2312	0	2285	0
STA 67+00 TO 73+00	3841	99	0	0	3265	0	3167	0
STA 73+00 TO 79+00	1705	131	0	0	1449	0	1318	0
STA 79+00 TO 85+00	2601	79	0	0	2211	0	2132	0
STA 85+00 TO 90+00	1953	259	0	0	1660	0	1401	0
HOPPS TOTAL	4586	13	0	0	3898	0	3885	0
BOWES TOTAL	2573	501	0	0	2187	0	1686	0
GRAND TOTAL	29439	2445	315	231	25023	268	22578	36

EXCESS/SHORTAGE NOTES:

SHRINKAGE FACTOR FOR COLUMNS (1) = 0.85  
 COLUMN (3) = COLUMN (1) x 0.85  
 COLUMN (4) = COLUMN (3) - COLUMN (2)

**PAVEMENT MARKING**

LOCATION	POLYUREA PAVEMENT MARKING LINE 4"	POLYUREA PAVEMENT MARKING LINE 6"	POLYUREA PAVEMENT MARKING LINE 12"	POLYUREA PAVEMENT MARKING LINE 24"	POLYUREA PAVEMENT MARKING LETTERS & SYMB.	(78100100) RAISED REFLECTIVE PAVEMENT MARKERS, ONE-WAY CRYSTAL	(78100100) RAISED REFLECTIVE PAVEMENT MARKERS, ONE-WAY AMBER
	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(EACH)	(EACH)
McLEAN BLVD.							
STA. 31+96 TO 45+00	4708	1332	590	36	168	27	49
STA. 45+00 TO 62+00	5305	301	370	36	123	37	50
STA. 62+00 TO 77+00	5206	693	444	96	109	39	50
STA. 77+00 TO 94+00	5498	768	220	96	218	51	50
HOPPS RD./SPRING ST.	3574	1596	485	88	328	31	48
BOWES RD.	1440	783	60	88	218	16	18
TOTALS	25731	5473	2169	344	1165	201	265

**URS** 100 SOUTH WACKER DRIVE  
 SUITE 500 CHICAGO, IL 60606 TEL (312) 939-1000  
 FAX (312) 939-4198

REVISIONS	
NAME	DATE

McLEAN BOULEVARD  
 SCHEDULE OF QUANTITIES III

SCALE: DATE 04/06/2007 DRAWN BY: KLM CHECKED BY: