CONTRACT NO. 83737

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	96-00094-01-WR	KANE	187	76
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PLAN — SURVEYED / A.D.I.DEPT. CHECKED / PLT. OF W.M.V. CHECKED / CAD FILE NAME / NOTE BOOK / NO. / BY / DATE

SEE SHEET NO. 75
MATCH LINE STA 61+00

EXIST. R.O.W.

30' 50'

61+00 61+50 62+00 62+50 63+00 63+50 64+00 64+50 65+00 65+50 66+00 66+50 67+

MATCH LINE STA 67+00
SEE SHEET NO. 77

1 2 3 7 4

NOTE:
NOT ALL TREES ARE SHOWN. CONTRACTOR SHALL VERIFY THE ACTUAL NUMBER AND SIZE OF THE EXISTING TREES IN THE FIELD.

FOR ITEM DESCRIPTION & LEGEND SEE SHEET NO. 47.

SEE ALIGNMENT & TIES SHEETS FOR BENCHMARK INFORMATION

PROFILE — SURVEYED / PLOTTED CHECKED / B.M. NOTED / SYMBOLITIZE NOTATNG CHKD / NOTE BOOK / NO. / BY / DATE

RETURN RADIUS FOR ALL STREETS ARE DIMENSIONED FROM THE EDGE OF PAVEMENT. RETURN RADIUS FOR THE ALL PRIVATE ENTRANCES ARE DIMENSIONED FROM THE BACK OF CURB.

825 820 815 810 805 800 795 790 785

ex = 0.35'
200.00' V.C.

+00.00 EL. 805.90

+00.00 EL. 805.82

EXISTING GRADE LINE

PROPOSED GRADE LINE.

-0.75% +0.67%

VPI STA. 63+00.00
ELEVATION 805.15

	61+00	61+50	62+00	62+50	63+00	63+50	64+00	64+50	65+00	65+50	66+00	66+50	67+00
EXISTING ℄ ELEV.	807.71	807.68	807.65	807.59	807.53	807.54	807.56	807.71	807.85	808.09	808.33	808.72	809.10
PROPOSED ℄ ELEV.	806.65	806.28	805.90	805.61	805.50	805.57	805.82	806.15	806.49	806.82	807.16	807.49	807.83

REVISIONS

NAME	DATE

URS
1701 GOLF ROAD, SUITE 1000
ROLLING MEADOWS, IL 60008
TEL (847) 228-0707
FAX (847) 228-1115

McLEAN BOULEVARD
PLAN AND PROFILE
STA. 61+00 TO STA. 67+00

SCALE: VERT. 1"= 5'
HORIZ. 1"= 20'
DATE: 04/06/2007

DRAWN BY: KLM
CHECKED BY: