

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2545	98-00036-19-PP	WILL	147	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83896


CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1	RETAINING WALLS	TRAFFIC SIGNALS 1	TRAFFIC SIGNALS 2	NON-PARTICIPATING			
				CONSTRUCTION TYPE CODE						BOLINGBROOK	
				1000-2A	Y007	BOUGHTON RD Y031-1F	104TH ST Y031-1F	BIKE TRAIL Y046			
35501308	HMA BASE COURSE, 6"	SQ YD	669	669							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32650	32650							
40600300	AGGREGATE (PRIME COAT)	TON	100	100							
40603080	HMA BINDER COURSE, IL-19.0, N50	TON	31	31							
40603085	HMA BINDER COURSE, IL-19, N70	TON	51816	51029				787			
40603310	HMA SURFACE COURSE, MIX "C", N50	TON	124	124							
40603340	HMA SURFACE COURSE, MIX D, N70	TON	8328	7646				682			
42001300	PROTECTIVE COAT	SQ YD	6059	6058.634							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1544	1544							
42400800	DETECTABLE WARNING	SQ FT	180	180							
44000100	PAVEMENT REMOVAL	SQ YD	35032	35032							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1318	1318							
44000300	CURB REMOVAL	FOOT	552	552							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2018	2018							
44000600	SIDEWALK REMOVAL	SQ FT	2450	2450							
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	538	538							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1635	1635							
48203021	HMA SHOULDERS 6"	SQ YD	175	175							
50105220	PIPE CULVERT REMOVAL	FOOT	1608	1608							
50200100	STRUCTURE EXCAVATION	CU YD	2310		2310						
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	100		100						
50300225	CONCRETE STRUCTURES	CU YD	917		917.3						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	96050		96050						
50900105	ALUMINUM RAILING, TYPE L	FOOT	853		853						
51201400	FURNISHING STEEL PILES HP10X42	FOOT	7183		7183						
51203400	TEST PILE STEEL HP10X42	EACH	4		4						

- DENOTES SPECIALTY ITEM
- ROADWAY - 80% FEDERAL 20% LOCAL
- RETAINING WALLS - 80% FEDERAL 20% LOCAL
- NON-PARTICIPATING - 100% LOCAL

NO.	DATE	REVISION	BY

WILL COUNTY DEPARTMENT OF HIGHWAYS

PLAINFIELD-NAPERVILLE ROAD (C.H. 14)
ROADWAY RECONSTRUCTION
SUMMARY OF QUANTITIES


 McDonough Associates Inc.
 Engineers/Architects

DESIGNED BY: N.J.L.
 CHECKED BY: N.J.L.
 DRAWN BY: R.E.

SCALE: N.T.S.