

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2545	98-00036-19-FP	WILL	147	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83896


CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1	RETAINING WALLS	TRAFFIC SIGNALS 1	TRAFFIC SIGNALS 2	CONSTRUCTION TYPE CODE			NON-PARTICIPATING
								BOUGHTON RD	104TH ST	BIKE TRAIL	BOLINGBROOK
				1000-2A	Y007	Y031-1F	Y031-1F	Y046			
51204650	Pile SHOES	EACH	457		457						
51205200	TEMPORARY SHEET PILING	SQ FT	2673		2673						
54200463	PIPE CULVERTS, TYPE 1 RCCP 48"	FOOT	76	76							
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	84	84							
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	20	20							
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	14	14							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1							
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1							
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1							
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1							
54214533	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 48"	EACH	1	1							
54215550	METAL END SECTIONS 15"	EACH	5	5							
54215553	METAL END SECTIONS 18"	EACH	2	2							
54215559	METAL END SECTIONS 24"	EACH	1	1							
54223447	REMOVE AND RELAY PIPE CULVERTS 12"	FOOT	50	50							
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	1	1							
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1	1							
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1							
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1							
54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"	EACH	1	1							
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	2073	2073							
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	58	58							
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	263	263							
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	190	190							
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	315	315							

- * DENOTES SPECIALTY ITEM
- ** ROADWAY - 80% FEDERAL 20% LOCAL
- RETAINING WALLS - 80% FEDERAL 20% LOCAL
- NON-PARTICIPATING - 100% LOCAL

NO.	DATE	REVISION	BY

WILL COUNTY DEPARTMENT OF HIGHWAYS

PLAINFIELD-NAPERVILLE ROAD (C.H. 14)
ROADWAY RECONSTRUCTION
SUMMARY OF QUANTITIES


 McDonough Associates Inc.
 Engineers/Architects

DESIGNED BY: N.J.L.
 CHECKED BY: R.E.
 DRAWN BY: R.E.

SCALE: N.T.S.