

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83906				

NOTE:
GORE AREA STRIPING ADJACENT TO FREE-FLOW ISLAND (SOUTH OF STA 129+00) SHALL BE THERMOPLASTIC.

LOCATION	STANDARD NUMBER	SIGN PANEL	SIGN PANEL	METAL POST	METAL POST	RELOCATE	SIGN PLACEMENT	
		TYPE 1 (SQ FT)	TYPE 2 (SQ FT)	TYPE A (FOOT)	TYPE B (FOOT)	SIGN PANEL ASSEMBLY TYPE A (EACH)	HEIGHT ABOVE EDGE OF PAVEMENT	CENTERLINE OFFSET
ILLINOIS ROUTE 56								
220+00 LT	R2-1-3036	7.50			18.5		6'-0"	64'
221+00 LT	M3-4-2412	2.00		18.5			8'-0"	64'
221+00 LT	MI-1100-2424	4.00					6'-0"	64'
221+20 LT	R3-5LL-3030	6.25				13.0	6'-0"	9'
221+52 RT	R1-1-3030	6.25				13.0	6'-0"	84'
221+59 RT	R3-5-2430	5.00		12.5			6'-0"	90'
222+70 LT	R3-5LL-3030	6.25				13.0	6'-0"	9'
222+72 LT	R4-7-2430	5.00				13.0	6'-0"	9'
224+70 RT	R4-7-2430	5.00				13.0	6'-0"	15'
224+72 RT	R3-5LL-3030	6.25				13.0	6'-0"	15'
226+00 RT	R3-7-3030	6.25				12.5	6'-0"	70'
226+20 RT	R3-5LL-3030	6.25				13.0	6'-0"	15'
226+75 RT	M3-2-2412	2.00		17.5			8'-0"	70'
226+75 RT	MI-1100-2424	4.00					6'-0"	70'
226+93 LT	R3-5-2430	5.00		13.0			6'-0"	78'
227+00 LT	R1-1-3030	6.25				13.0	6'-0"	71'
227+91 RT	R1-1-3030	6.25				13.0	6'-0"	68'
227+97 RT	R3-5-2430	5.00		15.5			6'-0"	75'
228+40 RT	R3-7-3030	6.25				17.5	6'-0"	70'
229+50 LT	FERMILAB*					13.0	6'-0"	75'
230+15 RT	R3-5-2430	5.00		17.5			6'-0"	67'
232+50 RT	R3-5-2430	5.00		17.5			6'-0"	62'
232+88 LT	R1-1-3030	6.25				12.0	6'-0"	62'
233+57 RT	R1-1-3030	6.25				13.0	6'-0"	56'
235+00 RT	R2-1-3036	7.50				16.0	6'-0"	45'
235+00 LT	R2-1-3036	7.50				16.0	6'-0"	64'
SUBTOTAL - ROUTE 56		138.25		112.00	235.50	1		
FARNSWORTH AVENUE								
115+50 LT	TREE CITY USA*			14.0		1	8'-0"	44'
115+50 LT	AURORA CRIME STOPPERS*					1	6'-0"	44'
118+05 LT	R5-1-3030	6.25				11.5	6'-0"	61'
118+07 LT	R3-5-2430	5.00		11.0			6'-0"	65'
118+15 LT	R1-1-3030	6.25				12.0	6'-0"	60'
121+25 RT	MARMION SIGN*					13.0	6'-0"	75'
121+61 LT	W4-2-3636	9.00				11.0	6'-0"	63'
123+10 LT	R3-5-2430	5.00		10.0			6'-0"	62'
123+19 LT	R1-1-3030	6.25				10.5	6'-0"	65'
123+70 LT	R3-5LL-3030	6.25				13.0	6'-0"	11'
124+76 LT	R2-1-3036	7.50				11.5	6'-0"	63'
125+00 RT	MI-1100-2424	4.00		14.0			7'-3"	70'
125+00 RT	M6-4-2115	2.19					6'-0"	70'
125+44 LT	R3-5LL-3030	6.25				13.0	6'-0"	11'
125+46 LT	R4-7-2430	5.00				13.0	6'-0"	11'
SUBTOTAL - FARN.	W4-2-3636	68.94		49.00	108.50	3		
KIRK ROAD								
127+44 RT	R4-7-2430	5.00				13.0	6'-0"	12'
127+46 RT	R3-5LL-3030	6.25				13.0	6'-0"	12'
128+00 LT	MI-1100-2424	4.00		16.0			7'-3"	75'
128+00 LT	M6-4-2115	3.00					6'-0"	75'
129+00 RT	R3-5LL-3030	6.25				13.0	6'-0"	12'
129+00 LT	R5-1101-2430	5.00		14.5			6'-0"	77'
130+00 RT	NORRIS CULTURAL ARTS**					27.0	9'-0"	77'
130+00 RT	PHEASANT RUN RESORT**							

- NOTE:
ALL SIGNS ALONG KIRK ROAD WILL BE INSTALLED BY KANE COUNTY DIVISION OF TRANSPORTATION MAINTENANCE PERSONNEL.
THE CONTRACTOR SHALL PROVIDE A 10" X 10" BLOCKOUT FOR SIGN PLACEMENT WITHIN THE BARRIER MEDIAN. THE BLOCKOUT
SHALL EXTEND THE FULL DEPTH OF THE MEDIAN.

SCALE: VERT.
HORIZ.
DATE APR 06 2007

DRAWN BY BAH
CHECKED BY APS