

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	114
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 83906				

SUMMARY OF QUANTITIES					
IDOT PAY ITEM NO.	DESIGNATION	UNIT	CONTRACT TOTAL	RECORD TOTAL	
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	954		
80700140	GROUND ROD, 5/8" X 10 FT.	EACH	56		
81800400	AERIAL CABLE, 4-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4770		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4561		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	64		
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	24		
83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	1		
83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	28		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	240		
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	24		
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	9		
84200700	LIGHTING FOUNDATION REMOVAL	EACH	9		
X0321994	UNIT DUCT, WITH 4-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	5680		
X0322696	MAST ARM, STEEL, STREET LIGHTING, 15 FT	EACH	7		
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	13		
X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	28		

I:\projects\046\046116\046116.dwg 4/2/2021



GANDHI AND ASSOCIATES, INC.
ENGINEERS AND PLANNERS
8035 N. NORTHWEST HIGHWAY
SUITE 306
CHICAGO, ILLINOIS 60631 TEL: (773) 774-5900

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH

SCHEDULE OF
ELECTRICAL QUANTITIES

SCALE: NONE
DATE: 04/06/07

DRAWN BY: RDP
CHECKED BY: MAE