

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3869	06-00030-00-FF	MCHENRY	56	6
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-80036411				

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				1000-2A	Y031-1F	Y06 100% VILLAGE
• 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	225	225		
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	381	381		
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24345	24345		
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2589	2589		
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1242	1242		
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	178	178		
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	27	27		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1586	1586		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	26	26		
• 81018500	CONDUIT PUSHED, 2" DIAMETER, GALVANIZED STEEL	FOOT	15		15	
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1	1		
• 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1
• 87200400	SPAN WIRE	FOOT	618		618	
• 87200500	TETHER WIRE	FOOT	589		589	
• 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	34		34	
• 87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	346		346	
• 87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	985		985	
• 87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 7C	FOOT	1970		1970	
• 88000180	SIGNAL HEAD, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	4		4	
• 88000300	SIGNAL HEAD, 1-FACE, 5-SECTION, SPAN WIRE MOUNTED	EACH	8		8	
• 88700200	LIGHT DETECTOR	EACH	2			2
• 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	15578	15578		
△ Z0076600	TRAINEES	HOURS	500	500		
• X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	78	78		
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	42	42		
• X8050010	SERVICE INSTALLATION, GROUND MOUNTED	EACH	1		1	
• X8730350	ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED	FOOT	346			346
XX004801	BITUMINOUS BIKE PATH REMOVAL	SQ YD	231	231		
* XX005107	CONNECTION TO EXISTING WATER MAIN (NON-PRESSURE) - 12"	EACH	1			1
• XX005723	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	EACH	1			1
XX005770	STRUCTURE TO BE ABANDONED	EACH	1	1		
• XX006963	TRAFFIC SIGNAL, WOOD POLE, 45 FT, CLASS 5	EACH	4		4	
• XX006964	ELECTRIC CABLE AERIAL SUSPENDED, COMMUNICATION, NO. 16 5 1/2 PAIR	FOOT	763		763	

• INDICATES SPECIALTY ITEMS

△ Y080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

DRAWN BY DJK  
CHECKED BY JRV  
DATE 3/7/07