

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3869	06-00030-00-FF	MCHENRY	56	8
SCHEDULE OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003641				

SCHEDULE OF RELOCATE SIGN PANEL ASSEMBLY - TYPE A	
PROPOSED LOCATION	TELESCOPING STEEL SIGN SUPPORT (FT)
398+60, LT	14.5
326+97, LT	14.5
327+11, LT	16.0
401+43, RT	14.5
400+61, LT	0

SCHEDULE OF SIGN PANEL - TYPE 1				
PROPOSED LOCATION	SIGN NUMBER	DIMENSIONS	AREA (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)
301+50, RT	R2-1	24"X30"	5.0	14.5
302+53, LT	R3-8	30"X30"	6.25	14.5
308+21, LT	W11-1	30"X30"	6.25	14.5
	W16-7	24"X18"	3.0	16.0
308+30, LT	R1-1	36"X36"	9.0	16.5
	R1-1100	24"X18"	3.0	16.5
308+99, LT	W11-1	30"X30"	6.25	14.5
325+00, LT	R2-1	24"X30"	5.0	14.5
325+78, RT	R1-1	36"X36"	9.0	16.5
	R1-1100	24"X18"	3.0	16.5
327+11, LT	R1-1100	24"X18"	3.0	0
392+70, RT	W2-1	30"X30"	6.25	0
399+15.5, RT	W11-1	30"X30"	6.25	14.5
400+70, LT	W11-1	30"X30"	6.25	14.5
404+71, LT	W2-1	30"X30"	6.25	0
SCHEDULE OF SIGN PANEL - TYPE 2				
299+71, LT	R3-8B	48"X30"	10.0	29.0

EARTHWORK SCHEDULE			
ITEM	UNIT	HALIGUS ROAD	REED ROAD
EARTH EXCAVATION	C.Y.	2566	490
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	2182	417
EMBANKMENT REQUIRED	C.Y.	2296	531
EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	C.Y.	-114	-114
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL			
TOPSOIL STRIPPING	C.Y.	9883	493
UNDERCUT	C.Y.	785	0
TOTAL	C.Y.	11161	

NOTE: SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR

UNDERCUT DEPTH SCHEDULE		
FROM	TO	DEPTH
STA. 303+50	STA. 306+00	10"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DATE 3/7/07

DRAWN BY DJK  
CHECKED BY JRV