

C.H.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
15	96-00044-00-BR	KENDALL	55	9
STA. 30+00.00		TO STA. 45+00.00		
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 87325	

WILLIAM WARREN NESSON  
NESSON TRUSTEES  
NW/4, SEC 34, T. 37 N., R. 6 E., 3RD P.M.

WILLIAM WARREN NESSON  
NESSON TRUSTEES  
NW/4, SEC 34, T. 37 N., R. 6 E., 3RD P.M.

CURVE ORC202  
PI Sta. 35+44.10  
 $\Delta = 10^\circ 43' 04''$  (LT)  
 $D = 1^\circ 57' 32''$   
 $T = 274.38'$   
 $R = 2,924.99'$   
 $L = 547.15'$   
 $E = 12.84'$   
PC Sta. 32+69.73  
PRC Sta. 38+16.88  
SE = 4.5%  
SE TRANSITION  
Sta. 37+98.38 TO Sta. 38+35.38

A.R. STA. 39+00.00  
ABANDON EXISTING  
7'x3' BOX CULVERT  
CLSM 53.1 CU YD

A.R. STA. 39+20.00  
USFL 584.65 @ 38+60 LT  
DSFL 581.00 @ 39+53 RT.  
PRECAST CONC. BOX CULV  
8' X 3' (M273) = 107 FOOT  
END SEC. 8' X 3' W/GRATING = 1 EACH  
PRECAST CONC. DROP BOX  
8' X 3' X 10' W/GRATING = 1 EACH  
CLASS D PATCHES TYPE IV 15 INCH = 83 SY YD


CURVE ORC203  
PI Sta. 41+26.28  
 $\Delta = 19^\circ 16' 46''$  (LT)  
 $D = 3^\circ 08' 43''$   
 $T = 309.40'$   
 $R = 1,821.61'$   
 $L = 612.96'$   
 $E = 26.09'$   
PRC Sta. 38+16.88  
PT Sta. 44+29.83  
SE = 6.0%  
SE TRANSITION  
Sta. 37+98.38 TO Sta. 38+35.38  
Sta. 43+79.83 TO Sta. 45+79.83

LEGEND

- EXISTING ROW
- - - PROPOSED ROW
- ▨ PAVEMENT REMOVAL

DATE	BY

DATE	BY



KENDALL COUNTY FOREST PRESERVE DISTRICT  
NW/4, SEC 34, T. 37 N., R. 6 E., 3RD P.M.

