

# SUMMARY OF QUANTITIES

ITEM CODE	ITEM DESCRIPTION	UNIT	PROJECT QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	73
20800150	TRENCH BACKFILL	CU YD	100
* 21101600	TOPSOIL, FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	452
25000100	SEEDING, CLASS 1	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2
25100115	MULCH, METHOD 2	ACRE	0.1
35101400	AGGREGATE BASE COURSE, TYPE B	TON	130
35400100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	SQ YD	124
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	136
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,863
40600300	AGGREGATE (PRIME COAT)	TON	58
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	447
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,116
40600990	TEMPORARY RAMP	SQ YD	126
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3,405
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	2,431
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	351
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	690
42400800	DETECTABLE WARNINGS	SQ FT	96
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	512
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	384
44000400	GUTTER REMOVAL	FOOT	326
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	591
44000600	SIDEWALK REMOVAL	SQ FT	600
44200069	PAVEMENT PATCHING, TYPE III, 6 INCH	SQ YD	108
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,389
50105220	PIPE CULVERT REMOVAL	FOOT	89
55080050	STORM SEWERS, CLASS B, TYPE 1, 12'	FOOT	483
55100500	STORM SEWER REMOVAL, 12'	FOOT	288
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	11
60107600	PIPE UNDERDRAINS, 4'	FOOT	5,800
60108100	PIPE UNDERDRAINS, 4' (SPECIAL)	FOOT	132
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60260100	INLETS TO BE ADJUSTED	EACH	1
60500060	REMOVING INLETS	EACH	1
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1.7
60602800	CONCRETE GUTTER, TYPE B	FOOT	50
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	819

\* SEE SPECIAL PROVISIONS CONSTRUCTION TYPE CODE: I000

ITEM CODE	ITEM DESCRIPTION	UNIT	PROJECT QUANTITY
△ 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	800
63200310	GUARDRAIL REMOVAL	FOOT	200
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,300
70300220	TEMPORARY PAVEMENT MARKING - LINE 4'	FOOT	34,034
70300280	TEMPORARY PAVEMENT MARKING - LINE 24'	FOOT	151
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11,894
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	7
△ 78001110	PAINT PAVEMENT MARKING - LINE 4'	FOOT	34,034
△ 78001180	PAINT PAVEMENT MARKING - LINE 24'	FOOT	151
△ LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	12
△ * XX006932	COLD IN-PLACE RECYCLING, BITUMINOUS CONCRETE PAVEMENT, 5-1/2"	SQ YD	27,704
△ * XX006933	BITUMINOUS MATERIALS (COLD IN-PLACE RECYCLING)	TON	256

\* SEE SPECIAL PROVISIONS CONSTRUCTION TYPE CODE: I000

### △ SPECIALTY ITEMS