TABULATIONS

STORM SEWER CONSTRUCTION

STRUCTURE NO.	PIPE NO.	LOCATION STATION	LOCATION OFFSET	INLET AND GRATE TYPE * TA T3F&G	TA T8G	TB T8G	RIM ELEV.	BOTTOM WELL	PIPE SIZE 12"		FLOW ELEV. IN	OUT	SLOPE %	TRENCH BACKFILL (CY)	PAVEMENT PATCH (SY)
S-1		2+43.66	25.41 R	1			576.30	574.80							
	P-1								113.5		574.80	574.52	0.25	11.2	
S-2		3+60.00	26.00 R		1		576.30	574.42							
	P-2								77.7		574.42	574.22	0.26	6.4	
S-6		4+39.77	26.31 R			1	576.30	573.71							
S-3		4+36.29	26.03 L		1		576.20	574.20							
	P-3								6.1		574.20	574.15	0.82	0.4	
S-4		4+40.20	20.29 L	1			576.40	574.05							
	P-4								36.5		574.05	573.96	0.25	7.1	19.5
S-5		4+39.83	20.20 R	1			576.40	573.86							
	P-5								5.1		573.86	573.81	0.98	0.4	
S-6		4+39.77	26.31 R			(1)	576.30	573.71							
	P-6								107.7		573.71	573.44	0.25		
S-7		5+49.90	26.00 R		1		576.30	573.34							
	P-7								25.2		573.34	573.27	0.28	0.7	
S-8		5+74.23	35.00 R	1			576.20	573.17							
	P-8								38.3		573.17	573.06	0.29	14.7	21.5
S-9		6+16.29	35.00 R	1			576.34	572.96							
	P-9								72.3		572.96	572.78	0.25	27.6	
S-10		6+87.74	20.89 R		1		576.00	572.49							
								FROM DRAINAGE ITEM REMOVAL TABULATION:						30.7	66.4
PROJECT TOTAL:				5	4	1			482.4					99.2	107.4
USE:				5	4	1			483					100	108

* TA T3F&G: TYPE A INLET WITH TYPE 3 FRAME AND GRATE (STANDARDS 602301 & 604006)
TA T8G: TYPE A INLET WITH TYPE 8 GRATE (STANDARDS 602301 & 604036)
TB T8G: TYPE A INLET WITH TYPE 8 GRATE (STANDARDS 602306 & 604036)

ADJUST INLETS AND MANHOLES

LOCATION STATION	LOCATION OFFSET	ADJUST MANHOLES (EA)	ADJUST INLETS (EA)
2+21.60	0.00 L	1	
83+87.25	15.26 L		1
PROJECT TOTAL:		1	1
USE:		1	1

SIDEWALK REMOVAL AND REPLACEMENT

LOCATION START STATION	START SIDE	END STATION	END SIDE	SIDEWALK 4" P.C.C. (SF)	DETECTABLE WARNINGS TYPE A (SF)	SIDEWALK REMOVAL (SF)	TEMPORARY ACCESS (TON)
1+98.99	R	2+10.22	R	70.6	16	22.9	1.63
2+43.00	R	2+63.33	R	108.5	16	123.7	2.51
2+97.40	R	3+15.77	R	75.8		58.3	1.70
3+51.02	R	3+68.59	R	69.3		55.6	1.62
3+94.49	R	3+99.50	R	20.2		18.6	0.46
4+32.61	L	4+40.60	L	32.3		32.3	0.74
5+61.29	R	5+74.04	R	80.8	16	30.0	1.87
5+61.60	L	5+74.32	L	77.2	16	73.9	1.78
6+16.37	L	6+28.94	L	75.4	16	94.0	1.74
6+16.48	R	6+28.95	R	79.3	16	89.8	1.83
PROJECT TOTAL:				689.4	96	599.1	16
USE:				690	96	600	SEE ENTR. TAB

REMOVAL OF EXISTING DRAINAGE ITEMS

LOCATION START STATION	START OFFSET	END STATION	END OFFSET	STORM SEWER REM (FT)	CULVERT REMOVAL (FT)	INLET REMOVAL (EA)	TRENCH BACKFILL (CY)	PAVEMENT PATCHING (SY)
2+01.29	18.93 R	2+41.63	18.15 R		40.5		7.0	23.2
4+00.16	24.43 R	6+87.74	20.89 R	287.5			16.9	21.6
5+61.77	17.95 L	5+65.25	19.48 L		4.4			
5+74.01	27.61 L	5+75.94	33.17 L		5.9			
5+78.54	20.14 R	6+16.09	19.41 R		37.5		6.8	21.6
6+87.74	20.89 R					1.0		
PROJECT TOTAL:				287.5	88.3	1.0	30.7	66.4
USE:				288	89	1.0	SEE STORM SEWER TAB	