

# TABULATIONS

RELOCATE SIGN			
LOCATION		TYPE A	DESCRIPTION
STATION	OFFSET	(EA)	
2+44.23	33.89 R	1	STOP
2+50.79	22.36 R	1	CLAY STREET
4+65.04	21.23 R	1	SPEED LIMIT 30 MPH, NO PARKING
5+74.61	37.17 L	1	STOP
6+17.24	24.53 R	1	STOP
6+20.47	25.80 R	1	JACKSON STREET
6+45.14	24.47 R	1	NO PARKING
PROJECT TOTAL:		7	

GUARDRAIL						
LOCATION				GUARDRAIL REMOVAL (FT)	SPBGR TYPE A (FT)	TYPE 1 END SECTION (EA)
START		END				
STATION	OFFSET	STATION	OFFSET			
9+16.56	24.03 R	9+41.56	20.03 R	25.0		1
10+09.83	25.97 L	10+34.83	21.97 L	25.0		1
12+42.64	20.56 R	12+67.64	24.56 R	25.0		1
13.88.60	22.00 L	14+13.60	26.00 L	25.0		1
83+59.43	20.51 L	83+84.43	16.51 L	25.0		1
88+09.69	15.80 L	88+34.69	19.80 L	25.0		1
89+63.30	23.47 L	89+88.30	19.47 L	25.0		1
95+14.47	20.24 L	95+39.47	24.24 L	25.0		1
82+50.00	23.00 R	82+75.00	19.00 R			1
82+75.00	19.00 R	86+50.00	19.00 R		375	
86+50.00	19.00 R	86+75.00	23.00 R			1
88+95.00	23.00 R	89+20.00	19.00 R			1
89+20.00	19.00 R	93+45.00	19.00 R		425	
93+45.00	19.00 R	93+70.00	23.00 R			1
PROJECT TOTAL:				200.0	800	12

PAINT PAVEMENT STRIPING							
LOCATION				WHITE	YELLOW	YELLOW 4'	WHITE 24'
BEGIN		END		4' EDGE STRIPE	4' NO PASSING	10-30 SKIP DASH	STOP BAR STRIPE
STATION	SIDE	STATION	SIDE	(FT)	(FT)	(FT)	(FT)
6+31	R	12+71	R	640			
13+61	R	109+48	R	9587			
6+31	L	21+67	L	1536			
22+44	L	31+83	L	939			
32+38	L	60+63	L	2825			
61+07	L	109+48	L	4841			
0+45	L	17+50	L		1705		
30+00	L	48+50	L		1850		
75+00	L	88+50	L		1350		
103+50	L	109+48	L		598		
0+45	R	9+00	R		855		
20+00	R	37+50	R		1750		
65+00	R	85+00	R		2000		
93+50	R	109+48	R		1598		
9+00	L	17+50	R			220	
17+50	CL	20+00	CL			70	
20+00	L	30+00	L			250	
37+50	R	48+50	R			280	
48+50	CL	65+00	CL			420	
65+00	L	75+00	L			250	
85+00	R	88+50	R			90	
88+50	CL	93+50	CL			130	
93+50	L	103+50	L			250	
0+43	L	0+45	L				21
2+04	L	2+23	L				19
2+23	R	2+41	R				18
5+76	L	5+94	L				18
5+94	R	6+13	R				19
13+18	R	13+40	R				22
2+86	L	22+06	L				20
60+71	L	60+85	L				14
PROJECT TOTAL:				20,368	11,706	1,960	151

SUBSURFACE DRAIN							
LOCATION			SIDE	4' UNDERDRAIN (FT)	4' SPECIAL (FT)	HEADWALL (EA)	REMARKS
STATION	TO	STATION					
15+00		18+27	L	327	12.0	1.0	SAG LOCATION
18+27		23+00	L	473			
32+00		37+00	R	500	12.0	1.0	
37+00		42+00	R	500	12.0	1.0	
42+00		47+00	R	500	12.0	1.0	
47+00		52+00	R	500	12.0	1.0	
52+00		57+00	R	500	12.0	1.0	
57+00		62+00	R	500	12.0	1.0	
62+00		63+00	R	100	12.0	1.0	SAG LOCATION
63+00		67+00	R	400			
67+00		72+00	R	500	12.0	1.0	
72+00		77+00	R	500	12.0	1.0	
77+00		82+00	R	500	12.0	1.0	
PROJECT TOTAL:				5,800	132.0	11.0	
USE:				5,800	132	11	
* NOTE: SAG LOCATIONS REQUIRE DOUBLE HEADWALLS							