

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	F		BRF		F			
				80% FEDERAL 20% STATE CONSTRUCTION TYPE		BIG SALT FEDERAL 20% STATE CONSTRUCTION TYPE		LITTLE SALT CREEK			
				URBAN	RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	RURAL
				1000-2A	X071-2A	X081-2A	X081-2A	X081-2A	X081-2A	X081-2A	X081-2A
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	784		784						
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1366		1366						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	313		313						
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	43157	3179	39978						
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	368	368							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	15067	1423	13644						
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1								
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1								
50102400	CONCRETE REMOVAL	CU YD	31.3						31.3		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1								
50105200	REMOVE EXISTING CULVERTS	EACH	61	4	47						
50200100	STRUCTURE EXCAVATION	CU YD	428		348	80					
50300100	FLOOR DRAINS	EACH	6			6					
50300225	CONCRETE STRUCTURES	CU YD	309.9	147.4	125.6	36.9					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	376.7		249.9	95.6			31.2		
50300260	BRIDGE DECK GROOVING	SQ YD	1599		748	228			623		
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	318			318					
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1								
50500505	STUD SHEAR CONNECTORS	EACH	3384		3384						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	145638	207	46481	72400	22,230		4320		
50800515	BAR SPLICERS	EACH	1078		760	294			24		
51201400	FURNISHING STEEL PILES HPI0X42	FOOT	540			540					
51201500	FURNISHING STEEL PILES HPI0X57	FOOT	416		416						
51201700	FURNISHING STEEL PILES HPI2X74	FOOT	248		248						
51202305	DRIVING PILES	FOOT	956		416	540					
51203400	TEST PILE STEEL HPI0X42	EACH	1			1					
51203500	TEST PILE STEEL HPI0X57	EACH	2			2					
51205200	TEMPORARY SHEET PILING	SQ FT	954		954						
51500100	NAME PLATES	EACH	2								
52100520	ANCHOR BOLTS, 1"	EACH	48		48						
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	1								
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	1								
54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH	2	2							
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	2		2						
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	2		2						
54001007	BOX CULVERT END SECTION, CULVERT NO.7	EACH	2		2						

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	EFFINGHAM	409	5
STA. TO STA.				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				
* (6.7)Y, RS-1, 6B-1, 7B-1 & 7BR-2				
CONTRACT NO. 94356				
F			BRF	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	80% FEDERAL 20% STATE CONSTRUCTION TYPE		BIG SALT FEDERAL 20% STATE CONSTRUCTION TYPE		LITTLE SALT CREEK	
				URBAN	RURAL	URBAN	RURAL	URBAN	RURAL
				1000-2A	X071-2A	X081-2A	X081-2A	X081-2A	X081-2A
				URBAN	RURAL	URBAN	RURAL	URBAN	RURAL
54001008	BOX CULVERT END SECTION, CULVERT NO.8	EACH	2		2				
54001009	BOX CULVERT END SECTION, CULVERT NO.9	EACH	1		1				
54001010	BOX CULVERT END SECTION, CULVERT NO.10	EACH	1		1				
54001011	BOX CULVERT END SECTION, CULVERT NO.11	EACH	2		2				
54001012	BOX CULVERT END SECTION, CULVERT NO.12	EACH	4		4				
54001013	BOX CULVERT END SECTION, CULVERT NO.13	EACH	2		2				
54001014	BOX CULVERT END SECTION, CULVERT NO.14	EACH	2		2				
54001015	BOX CULVERT END SECTION, CULVERT NO.15	EACH	1		1				
54001016	BOX CULVERT END SECTION, CULVERT NO.16	EACH	1		1				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	408	48	360				
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	111	62	49				
54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	42		42				
54010303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT	33	33					
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	23		23				
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	43		43				
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	69		69				
54010703	PRECAST CONCRETE BOX CULVERT 7' X 3'	FOOT	140		140				
54010802	PRECAST CONCRETE BOX CULVERT 8' X 2'	FOOT	10		10				
54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'	FOOT	26		26				
542A0220	PIPE CULVERTS, CLASS A, TYPE 115"	FOOT	98	98					
542A0228	PIPE CULVERTS, CLASS A, TYPE 118"	FOOT	5	5					
542A0229	PIPE CULVERTS, CLASS A, TYPE 124"	FOOT	79	2	77				
542A0235	PIPE CULVERTS, CLASS A, TYPE 130"	FOOT	45	31	14				
542A0247	PIPE CULVERTS, CLASS A, TYPE 142"	FOOT	13	13					
542D0217	PIPE CULVERTS, CLASS D, TYPE 112"	FOOT	94		94				
542D0220	PIPE CULVERTS, CLASS D, TYPE 115"	FOOT	1446	403	1043				
542D0223	PIPE CULVERTS, CLASS D, TYPE 118"	FOOT	309		309				
542D0226	PIPE CULVERTS, CLASS D, TYPE 121"	FOOT	194		194				
542D0229	PIPE CULVERTS, CLASS D, TYPE 124"	FOOT	432	45	387				

URBAN SECTION STA. 142+00.00 TO STA. 180+60.00
RURAL SECTION STA. 180+60.00 TO STA. 689+81.63
* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 2 OF 4
DATE 6/02
DRAWN BY ASB
CHECKED BY SJK