CONTRACT NO. 94660

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	*	CRAWFORD	37	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

RESURFACING SCHEDULE

STATION TO STATION			LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NTO	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, (VARIABLE DEPTH)	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
			LIN FT	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD
179+36.0	TO	186+18.0	682.0	26.00	17732.0	197	3.9	165.5		1970.2			12.2
186+18.0	=	5+53.0	STATION EQUATION	26.00									
5+53.0	TO	8+25.0	272.0	26.00	7072.0	79	1.6	66.0		785.8			
8+25.0	TO	10+23.0	198.0	25.00	4950.0	55	1.1	46.2		550.0			
10+23.0	TO	40+92.0	3069.0	24.00	73656.0	818	16.4	687.5		8184.0			12.2
0+00	TO	18+32.7	1832.7	18.00	32988.6	367	7.3	307.9		3665.4			
18+32.7	TO	20+42.0	209.3	22.00	4604.6	51	1.0	43.0		511.6			
20+42.0	TO	22+50.0	208.0	22.00	4576.0	51	1.0	42.7		508.4		26	
22+50.0	TO	27+29.0	479.0	22.00	10538.0	117	2.3	98.4		1170.9			
27+29.0	TO	27+59.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
27+59.0	TO	27+82.6	23.6	22.00	519.2	6	0.1	4.8			57.7	2	
27+82.6	=	28+36.9	STATION EQUATION	22.00									
28+36.9	TO	34+27.0	590.1	22.00	12982.2	144	2.9	121.2			1442.5	45	
34+27.0	TO	34+48.3	21.3	22.00	468.6	5	0.1	4.4			52.1	2	
34+48.3	TO	34+78.3	30.0	22.00	660.0	7	0.1	6.2	73.3			2	12.2
34+78.3	TO	35+21.7	BRIDGE OMISSION	22.00	954.8								
35+21.7	TO	35+51.7	30.0	22.00	660.0	7	0.1	6.2	73.3			2	12.2
35+51.7	TO	35+73.0	21.3	22.00	468.6	5	0.1	4.4			52.1	2	
35+73.0	TO	43+53.0	780.0	22.00	17160.0	191	3.8	160.2			1906.7	59	
43+53.0	TO	43+83.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
43+83.0	TO	54+94.0	1111.0	22.00	24442.0	272	5.4	228.1		2715.8			
54+94.0	TO	61+59.0	665.0	22.00	14630.0	163	3.3	136.5		1625.6			
61+59.0	TO	63+44.2	185.2	22.00	4074.4	45	0.9	38.0		452.7			
63+44.2	=	64+21.7	STATION EQUATION	22.00									
64+21.7	TO	84+13.0	1991.3	22.00	43808.6	487	9.7	408.9		4867.6			
84+13.0	TO	88+98.4	485.4	22.00	10678.8	119	2.4	99.7		1186.5			
88+98.4	=	89+08.2	STATION EQUATION	22.00									
89+08.2	TO	89+84.0	75.8	22.00	1667.6	19	0.4	15.6		185.3			
89+84.0	TO	90+76.0	92.0	22.00	2024.0	23	0.4	18.9		224.9			
90+76.0	TO	100+01.4	925.4	22.00	20358.8	226	4.5	190.0		2262.1			
100+01.4	=	100+22.7	STATION EQUATION	22.00									
100+22.7	TO	101+99.0	176.3	22.00	3878.6	43	0.9	36.2		431.0			
101+99.0	TO	102+29.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
102+29.0	TO	118+70.0	1641.0	22.00	36102.0	401	8.0	337.0			4011.3	125	
118+60.0	TO	118+90.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
118+90.0	TO	134+75.0	1585.0	22.00	34870.0	387	7.7	325.5		3874.4			
134+75.0	TO	135+05.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
135+05.0	TO	157+54.3	2249.3	22.00	49484.6	550	11.0	461.9			5498.3	171	
157+54.3	=	157+57.7	STATION EQUATION	22.00									
157+57.7	TO	163+06.0	548.3	22.00	12062.6	134	2.7	112.6			1340.3	42	
163+06.0	TO	163+36.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
163+36.0	TO	174+91.0	1155.0	22.00	25410.0	282	5.6	237.2		2823.3			
174+91.0	TO	175+21.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
175+21.0	TO	177+70.0	249.0	22.00	5478.0	61	1.2	51.1			608.7	19	
177+70.0	TO	178+00.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
178+00.0	TO	182+78.3	478.3	22.00	10522.6	117	2.3	98.2		1169.2			
182+78.3	=	182+85.5	STATION EQUATION	22.00									
182+85.5	TO	184+75.0	189.5	22.00	4169.0	46	0.9	38.9		463.2			
184+75.0	TO	185+05.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
185+05.0	TO	221+42.3	3637.3	22.00	80020.6	889	17.8	746.9			8891.2	276	
221+42.3	=	221+60.6	STATION EQUATION	22.00									
221+60.6	TO	236+32.1	1471.5	22.00	32373.0	360	7.2	302.1			3597.0	112	
236+32.1	=	236+39.4	STATION EQUATION	22.00									
236+39.4	TO	252+73.2	1633.8	22.00	35943.6	399	8.0	335.5			3993.7	124	
252+73.2	=	254+11.8	STATION EQUATION	22.00									
254+11.8	TO	283+10.5	2898.7	22.00	63771.4	709	14.2	595.2			7085.7	220	
283+10.5	=	281+22.8	STATION EQUATION	22.00									
281+22.8	TO	305+41.0	2418.2	22.00	53200.4	591	11.8	496.5			5911.2	184	
305+41.0	TO	305+71.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
305+71.0	TO	309+17.2	346.2	22.00	7616.4	85	1.7	71.1		846.3			
309+17.2	=	309+26.0	STATION EQUATION	22.00									
309+26.0	TO	337+65.0	2839.0	22.00	62458.0	694	13.9	582.9		6939.8			
337+65.0	TO	337+95.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	
337+95.0	TO	364+06.0	2611.0	22.00	57442.0	638	12.8	536.1			6382.4	198	
364+06.0	=	364+11.4	STATION EQUATION	22.00									
364+11.4	TO	367+79.0	367.6	22.00	8087.2	90	1.8	75.5			898.6	28	
367+79.0	TO	368+09.0	30.0	22.00	660.0	7	0.1	6.2			73.3	2	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$