

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 782 | * | CRAWFORD | 37 | 10 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

PAVEMENT MARKING SCHEDULE

| STATION TO STATION | LENGTH | SHORT-TERM PAVEMENT MARKING | WORK ZONE PAVEMENT MARKING REMOVAL | PAINT PAVEMENT MARKING - LINE 4" | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | RAISED REFLECTIVE PAVEMENT MARKER | TEMPORARY PAVEMENT MARKING LINE 4" | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | THERMOPLASTIC PAVEMENT MARKING - LINE 24" |
|------------------------|--------|-----------------------------|------------------------------------|----------------------------------|--|-----------------------------------|------------------------------------|--|---|
| | | | | | | | | | |
| 179+36.00 TO 185+26.00 | 590 | 177 | 642.2 | | 1868 | 7 | 1868 | 58 | 33 |
| 185+26.00 TO 186+18.00 | 92 | 28 | 38.8 | | 107 | 5 | 107 | | |
| 5+53.00 TO 40+92.00 | 3539 | 1062 | 2538.9 | | 7263 | 63 | 7263 | | |
| 0+00.00 TO 27+82.60 | 2783 | 835 | 2013.1 | | 5761 | 149 | 5761 | | |
| 28+36.90 TO 33+73.00 | 536 | 161 | 420.0 | | 1206 | 7 | 1206 | | |
| 33+73.00 TO 42+93.00 | 920 | 276 | 999.0 | | 2905 | 12 | 2905 | | |
| 42+93.00 TO 57+13.00 | 1420 | 426 | 1940.6 | 5680 | 18 | 18 | 5680 | | |
| 57+13.00 TO 63+44.00 | 631 | 189 | 862.3 | 2524 | 8 | 8 | 2524 | | |
| 64+22.00 TO 68+26.00 | 404 | 121 | 451.2 | 1313 | 5 | 5 | 1313 | | |
| 68+26.00 TO 71+61.00 | 335 | 101 | 262.5 | 754 | 4 | 4 | 754 | | |
| 71+61.00 TO 81+81.00 | 1020 | 306 | 1139.0 | 3315 | 13 | 13 | 3315 | | |
| 81+81.00 TO 88+98.40 | 717 | 215 | 801.1 | 2332 | 9 | 9 | 2332 | | |
| 89+08.20 TO 95+11.00 | 603 | 181 | 823.8 | 2411 | 8 | 8 | 2411 | | |
| 95+11.00 TO 100+01.00 | 490 | 147 | 669.6 | 1960 | 6 | 6 | 1960 | | |
| 100+22.70 TO 114+73.00 | 1450 | 435 | 1619.5 | 4714 | 18 | 18 | 4714 | | |
| 114+73.00 TO 118+03.00 | 330 | 99 | 451.0 | 1320 | 4 | 4 | 1320 | | |
| 118+03.00 TO 128+83.00 | 1080 | 324 | 1206.0 | 3510 | 14 | 14 | 3510 | | |
| 128+83.00 TO 143+53.00 | 1470 | 441 | 1151.5 | 3308 | 18 | 18 | 3308 | | |
| 143+53.00 TO 153+68.00 | 1015 | 305 | 1133.4 | 3299 | 13 | 13 | 3299 | | |
| 153+68.00 TO 157+54.30 | 386 | 116 | 528.0 | 1545 | 5 | 5 | 1545 | | |
| 157+57.70 TO 158+36.00 | 78 | 24 | 71.3 | 206 | 1 | 1 | 206 | | |
| 158+36.00 TO 177+16.00 | 1880 | 564 | 2099.4 | 6110 | 24 | 24 | 6110 | | |
| 177+16.00 TO 181+41.00 | 425 | 128 | 580.9 | 1700 | 5 | 5 | 1700 | | |
| 181+41.00 TO 182+78.00 | 137 | 41 | 153.0 | 445 | 2 | 2 | 445 | | |
| 182+86.00 TO 191+34.00 | 848 | 254 | 880.3 | 2556 | 11 | 11 | 2556 | | |
| 191+34.00 TO 194+70.50 | 337 | 101 | 263.6 | 757 | 4 | 4 | 757 | | |
| 194+70.50 TO 221+42.33 | 2672 | 802 | 2093.0 | 6012 | 33 | 33 | 6012 | | |
| 221+60.60 TO 236+32.10 | 1472 | 442 | 1152.7 | 3311 | 18 | 18 | 3311 | | |
| 236+39.40 TO 252+60.00 | 1621 | 486 | 1189.8 | 3407 | 20 | 20 | 3407 | | |
| 252+60.00 TO 252+73.20 | 13 | 4 | 14.7 | 43 | 0 | 0 | 43 | | |
| 254+11.80 TO 265+09.00 | 1097 | 329 | 1225.2 | 3566 | 14 | 14 | 3566 | | |
| 265+09.00 TO 279+19.00 | 1410 | 423 | 1927.0 | 5640 | 18 | 18 | 5640 | | |
| 279+19.00 TO 283+10.50 | 392 | 118 | 437.2 | 1272 | 5 | 5 | 1272 | | |
| 281+22.80 TO 286+21.00 | 498 | 150 | 530.7 | 1542 | 6 | 6 | 1542 | | |
| 286+21.00 TO 305+31.00 | 1910 | 573 | 1496.2 | 4298 | 24 | 24 | 4298 | | |
| 305+31.00 TO 309+17.20 | 386 | 116 | 431.3 | 1255 | 5 | 5 | 1255 | | |
| 309+26.00 TO 315+65.00 | 639 | 192 | 693.6 | 2017 | 8 | 8 | 2017 | | |
| 315+65.00 TO 317+00.00 | 135 | 41 | 184.5 | 540 | 2 | 2 | 540 | | |
| 317+00.00 TO 327+90.00 | 1090 | 327 | 1197.1 | 3483 | 14 | 14 | 3483 | | |
| 327+90.00 TO 348+90.00 | 2100 | 630 | 1645.0 | 4725 | 26 | 26 | 4725 | | |
| 348+90.00 TO 358+90.00 | 1000 | 300 | 1095.6 | 3187 | 13 | 13 | 3187 | | |
| 358+90.00 TO 364+06.00 | 516 | 155 | 705.2 | 2064 | 7 | 7 | 2064 | | |
| 364+11.40 TO 378+58.20 | 1447 | 434 | 1977.3 | 5787 | 18 | 18 | 5787 | | |
| 378+69.00 TO 408+50.80 | 2982 | 895 | 4025.1 | 11777 | 37 | 37 | 11777 | | |
| 409+66.90 TO 423+72.00 | 1405 | 422 | 1920.3 | 5620 | 18 | 18 | 5620 | | |
| 423+72.00 TO 424+83.20 | 111 | 33 | 124.2 | 361 | 1 | 1 | 361 | | |
| 424+85.90 TO 427+49.00 | 263 | 79 | 293.8 | 855 | 3 | 3 | 855 | | |
| 427+49.00 TO 431+55.00 | 406 | 122 | 453.3 | 1320 | 5 | 5 | 1320 | | |
| 431+55.00 TO 443+53.90 | 1199 | 360 | 939.2 | 2698 | 15 | 15 | 2698 | | |
| 443+56.30 TO 451+72.50 | 816 | 245 | 614.3 | 1761 | 10 | 10 | 1761 | | |
| 451+89.80 TO 464+25.00 | 1235 | 371 | 945.9 | 2714 | 15 | 15 | 2714 | | |
| 464+25.00 TO 473+25.00 | 900 | 270 | 1005.0 | 2925 | 11 | 11 | 2925 | | |
| 473+25.00 TO 475+42.40 | 217 | 65 | 297.1 | 870 | 3 | 3 | 870 | | |
| 475+48.70 TO 476+95.00 | 146 | 44 | 200.0 | 585 | 2 | 2 | 585 | | |
| 476+95.00 TO 497+30.00 | 2035 | 611 | 2781.1 | 8140 | 25 | 25 | 8140 | | |
| 497+41.60 TO 498+83.00 | 141 | 42 | 193.2 | 566 | 2 | 2 | 566 | | |
| 498+83.00 TO 508+03.00 | 920 | 276 | 1007.4 | 2930 | 12 | 12 | 2930 | | |
| 508+03.00 TO 514+53.00 | 650 | 195 | 509.2 | 1463 | 8 | 8 | 1463 | | |
| 514+53.00 TO 535+13.00 | 2060 | 618 | 2287.0 | 6655 | 26 | 26 | 6655 | | |
| 535+13.00 TO 541+03.00 | 590 | 177 | 462.2 | 1328 | 7 | 7 | 1328 | | |
| 541+03.00 TO 552+43.00 | 1140 | 342 | 1273.0 | 3705 | 14 | 14 | 3705 | | |
| 552+48.00 TO 559+48.00 | 700 | 210 | 781.6 | 2275 | 9 | 9 | 2275 | | |
| 559+48.00 TO 574+68.00 | 1520 | 456 | 1190.7 | 3420 | 19 | 19 | 3420 | | |
| 574+68.00 TO 584+98.00 | 1030 | 309 | 1128.5 | 3283 | 13 | 13 | 3283 | | |
| 584+98.00 TO 592+08.00 | 710 | 213 | 970.4 | 2840 | 9 | 9 | 2840 | | |
| 592+08.00 TO 596+69.80 | 462 | 139 | 515.7 | 1501 | 6 | 6 | 1501 | | |
| 597+46.50 TO 604+24.50 | 678 | 203 | 757.1 | 2204 | 9 | 9 | 2204 | | |
| 604+24.50 TO 623+14.00 | 1890 | 567 | 1480.1 | 4251 | 24 | 24 | 4251 | | |
| TOTALS | | 19836 | 67892 | 177952 | 19109 | 964 | 197062 | 58 | 33 |

PAVEMENT PATCHING, 12 IN

| STATION | TY I | TY II | TY III | TY IV |
|---------|-------|--------|--------|-------|
| | SQ YD | SQ YD | SQ YD | SQ YD |
| TOTAL | 555.8 | 1274.0 | 215.7 | 201.6 |

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING AND PATCHING SCHEDULES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE