

F.A. ILL. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 95500				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN - FAYETTE COUNTY				
				FEDERAL 80% CITY 20% TEA-21	FEDERAL 80% CITY 20% STU	CITY 100%	STATE 50% CITY 50%	STATE 100%
Δ 88600100	DETECTOR LOOP, TYPE I	FOOT	867					867
Δ B2001366	TREE, CORNUS FLORIDA (FLOWERING DOG-WOOD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	36	36				
• LR430040	PAVING BRICK SIDEWALK	SQ. YD.	780	780				
• Z0012450	CONCRETE STEPS	CU. YD.	5	5				
• Z0050900	REMOVE CONCRETE FOUNDATION	EACH	2			2		
• Z0067500	STEEL CASINGS 16"	FOOT	84			84		
• XX000739	CURB STOP & BOX 1 INCH	EACH	83			83		
• XX000868	SELECT GRANULAR BACKFILL	CU. YD.	5487			5487		
Δ XX000959	TRASH RECEPTACLES	EACH	36			36		
Δ XX001051	WATER SERVICE LINE RECONNECTION	EACH	83			83		
• XX001386	SANITARY SEWERS, PVC, 8"	FOOT	419			419		
• X0322024	TRENCH DRAIN	EACH	1			1		
• XX004101	ORNAMENTAL METAL FENCE	FOOT	78	78				
• XX004242	ORNAMENTAL HANDRAIL	FOOT	52	52				
Δ XX004602	BENCH WITH BACK	EACH	36			36		
• XX004735	RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1			1		
Δ XX004887	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	40	40				
Δ XX004998	PVC WATER MAIN 6"	FOOT	671			671		
Δ XX004999	PVC WATER MAIN 8"	FOOT	3249			3249		
• XX005884	GROUT ABANDONED SEWERS	FOOT	1749			1749		
• XX005790	RECONNECT SANITARY SERVICE LATERAL 6"	EACH	50			50		
• XX006179	SANITARY MANHOLE REMOVAL AND REPLACEMENT	EACH	4			4		
• X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	1599			1599		
• XX000690	SANITARY SEWER REMOVAL AND REPLACEMENT 10"	FOOT	28			28		
• XX006887	CAP AND BLOCK 1"	EACH	1			1		
• XX006888	CAP AND BLOCK 2"	EACH	1			1		
• XX006889	CAP AND BLOCK 3"	EACH	3			3		
• X0301708	CAP AND BLOCK 6"	EACH	4			4		
• X0301709	CAP AND BLOCK 8"	EACH	1			1		
• X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3			3		
• X0322719	TEMPORARY DRAINAGE CONNECTION	EACH	20			20		
• X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	29	20		9		
• X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	10	5		5		
• X6020125	RESTRICTED DEPTH INLET TYPE B, TYPE 3V FRAME AND GRATE	EACH	7	1		6		
• X6020127	RESTRICTED DEPTH INLET TYPE B, TYPE 3V FRAME AND GRATE	EACH	12	8		4		
• XX006890	CIPP LINER FOR SANITARY SEWER MAIN 6"	FOOT	187			187		
• XX006891	CIPP LINER FOR SANITARY SEWER MAIN 8"	FOOT	1162			1162		
• XX006892	CIPP LINER FOR SANITARY SEWER MAIN 10"	FOOT	280			280		
• XX006893	CIPP LINER FOR SANITARY SEWER MAIN 12"	FOOT	391			391		
• XX006894	CIPP LINER FOR SANITARY SEWER MAIN 15"	FOOT	265			265		
• XX006895	RESTRICTED DEPTH MANHOLE, 4'-DIAMETER, WITH SALVAGE FRAME AND GRATE	EACH	1			1		
Δ XX006896	STEEL CASING BORED AND JACKED 42"	FOOT	110			110		
Δ XX005488	STEEL CASING BORED AND JACKED 48"	FOOT	119			119		
• XX006897	5' BRICK CIRCULAR PATTERN	EACH	36	36				
• XX006898	STAMPED COLORED PORTLAND CEMENT CONCRETE	SO. FT.	856	712		144		
Δ XX006899	SERIES A OUTDOOR INTERPRETIVES SIGN TYPE A3	EACH	7	5		2		
Δ XX006900	SERIES A OUTDOOR INTERPRETIVES SIGN TYPE A4	EACH	3	3				
Δ XX006901	TREE GRATE ASSEMBLY, COMPLETE	EACH	36	36				
• XX006902	HANDICAP RAMP AND HANDRAIL, COMPLETE	EACH	1	1				
Δ XX006903	ORNAMENTAL STREET SIGN POST, COMPLETE	EACH	30	30				
Δ XX006213	METAL POST, SPECIAL	EACH	7	7				
Δ XX006961	ORNAMENTAL STREET SIGN	EACH	12	12				
Δ XX006962	ORNAMENTAL SIGN FRAME	EACH	65	65				
Z0048665	Railroad Protective Liability Insurance	L.SUM	1	1				

- SPECIAL PROVISIONS
- Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE
LWJ	4-13-07
LWJ	5-09-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY KOJ
CHECKED BY BWC

CADD FILE: /4812/84-4812.dgn
PLOTTED: 5/9/2007