F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	20
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	CLASS B JACKED IN PLACE		STEEL CASING BORED & JACKED		DRAINS (SPECIAL)	UNDER-DRAINS (SPECIAL)	PIPE TEE						INLETS										MANHOLES					
																			RESTRICTED DEPTH					RESTRICTED DEPTH					
	30"	36"	42"	48"	6"	6"	12" PIPE 12" RISER	15" PIPE 12" RISER	18" PIPE 12" RISER	24" PIPE 12" RISER	30" PIPE 12" RISER	36" PIPE 12" RISER	TYPE A TYPE 3 F & G	TYPE A TYPE 3V F & G	TYPE A SALVAGED F & G	TYPE B TYPE 3 F & G	TYPE B TYPE 3V F & G	TYPE B TYPE 4 F & G	TYPE B TYPE 1 F & CL	TYPE B TYPE 3 F & G	TYPE B TYPE 3V F & G	TRENCH DRAIN (2' x 8')	4' - DIA. TYPE 1 F & CL	4' - DIA. TYPE 1 F & CL	4' - DIA. SALVAGED F & G	5' - DIA. TYPE 1 F & CL	6' - DIA. TYPE 1 F & CL	7' - DIA. TYPE 1 F & CL
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
LT. STA. 609+84, 24.00'																											1	
LT. STA. 609+84 TO LT. STA. 610+30																												
LT. STA. 610+30, 24.00'																											1	
LT. STA. 610+30 TO LT. STA. 610+76																												
LT. STA. 610+76, 24.00'																											1	
LT. STA. 610+76 TO LT. STA. 612+31																												
FIFTH STREET																												
RT. STA. 502+51 TO RT. STA. 502+65																												
LT. STA. 502+60, 29.17'														1														
LT. STA. 502+60 TO LT. STA. 502+75																												
RT. STA. 502+65, 27.12'																	1											
RT. STA. 502+65 TO RT. STA. 502+75																												
LT. STA. 502+75, 29.17'																					1							
LT. STA. 502+75 TO RT. STA. 502+75																												
RT. STA. 502+75, 22.00'																							1					
RT. STA. 502+75 TO RT. STA. 504+64.41																												
RT. STA. 502+83.26																												
LT. STA. 503+75, 29.38'														1														
LT. STA. 503+75 TO LT. STA. 503+90																												
RT. STA. 503+81, 27.12'										1							1											
LT. STA. 503+90, 29.38'																				1								
LT. STA. 503+90 TO RT. STA. 503+90																												
RT. STA. 503+90, 22.00'										1																		
RT. STA. 503+96, 27.12'										1						1												
RT. STA. 504+13.08, 22.00'										1																		
RT. STA. 504+64.41 TO RT. STA. 506+34																												
RT. STA. 506+34, 22.00'																										1		
RT. STA. 506+34, 27.56'																	1											
RT. STA. 506+34 TO RT. STA. 507+65																												
LT. STA. 506+99 TO LT. STA. 507+68																												
RT. STA. 507+02, 27.63'											1						1											
LT. STA. 507+02, 27.69'														1														
LT. STA. 507+02 TO LT. STA. 507+17																												
LT. STA. 507+17, 27.66'																					1							
LT. STA. 507+17 TO LT. STA. 507+50																												
RT. STA. 507+17, 27.55'											1						1											
RT. STA. 507+40, 27.42'											1									1								
LT. STA. 507+50, 27.58'																				1								
LT. STA. 507+50 TO LT. STA. 507+65																												
LT. STA. 507+65, 27.55'																				1								
RT. STA. 507+65, 22.00'																											1	
LT. STA. 507+65 TO RT. STA. 507+65																												
RT. STA. 507+65 TO RT. STA. 508+80	110		110																									
RT. STA. 508+80, 22.00'																											1	
RT. STA. 508+80 TO RT. STA. 509+41																												
RT. STA. 509+41, 22.00'																										1		
RT. STA. 509+41 TO RT. STA. 510+10																												
RT. STA. 510+10, 22.00'																										1		
RT. STA. 510+10 TO RT. STA. 512+07																												
RT. STA. 512+07, 22.00'																										1		
RT. STA. 512+07 TO RT. STA. 513+72																												
RT. STA. 513+72, 23.82'																										1		
RT. STA. 513+72 TO RT. STA. 515+70																												
TOTAL	110	119	110	119	54	2606	1	1	7	18	3	6	8	29	2	1	10	1	1	7	12	1	3	6	1	9	7	2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY BWC

H.M. & G. NO. 4812

CADD FILE: /4812/sch_4812.dgn
PLOTTED: 01/23/2007

HENRY, MEISENHEIMER & GENDE, INC. 1075 LAKE ROAD CARLYLE, ILLINOIS 62231 (618) 594-3711 WWW.HMGENGINEERS.COM