

SIGN SCHEDULE

LOCATION	SIGN	SIZE	ORNAMENTAL SIGN OR FRAME	SIGN PANEL			ORNAMENTALS TREET SIGN	ORNAMENTAL FRAME	ORNAMENTAL STREET SIGN POST, COMPLETE	METAL POST, SPECIAL	CONCRETE FOUNDATION	COMMENTS
				TYPE 1	TYPE 1	TYPE 2						
STATION	LT / R	CODE	IN X IN	MODEL	SO. FT.	SO. FT.	SO. FT.	EACH	EACH	EACH	CU. YD.	
GALLATIN STREET												
98+78.0	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
98+78.0	RT	RI-1100	30x18	RV3018	3.75			1				CROSS TRAFFIC DOES NOT STOP
98+98.0	LT			S214				1	1		0.485	W GALLATIN ST
98+98.0	LT			S214				1				S EIGHTH ST
99+29.0	LT	R7-X	12x18	RV1218	1.50			1		1		NO PARKING HERE TO CORNER
99+29.0	LT	R7-8	12x18	RV1218	1.50			1		1		HANDICAP RESERVED
99+71.0	LT	R7-8	12x18	RV1218	1.50			1		1		HANDICAP RESERVED
101+91.0	RT	R7-X	12x18	RV1218	1.50			1		1		NO PARKING HERE TO CORNER
101+99.0	LT	R7-X	12x18	RV1218	1.50			1		1		NO PARKING HERE TO CORNER
102+15.0	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
2+27.0	LT			S214				1	1		0.485	W GALLATIN ST
2+27.0	LT			S214				1				S SEVENTH ST
2+39.0	LT	RI-1	30x30	030	6.25			1	1		0.485	STOP
2+75.0	RT	D6-X	24x30	RV2430		5.00		1	1		0.485	HISTORIC NATIONAL ROAD (RELOCATE)
2+75.0	RT	M6-1	21x15	RV2115	2.19			1				RIGHT ARROW
2+82.0	LT	D6-X	24x30	RV2430		5.00		1	1		0.485	HISTORIC NATIONAL ROAD (RELOCATE)
2+82.0	LT	M6-1	21x15	RV2115	2.19			1				LEFT ARROW
4+21.7	LT	R7-X	12x18	RV1218	1.50			1				NO PARKING ANYTIME
4+96.3	RT	R7-8	12x18	RV1218	1.50			1				HANDICAP RESERVED
5+61.5	RT	R7-X	12x18	RV1218	1.50			1				NO PARKING HERE TO CORNER
5+80.0	LT	R7-X	12x18	RV1218	1.50			1				NO PARKING ANYTIME
6+21.5	RT			S214				1	1		0.485	W GALLATIN ST
6+21.5	RT			S214				1				S SIXTH ST
6+23.5	LT	RI-1	30x30	030	6.25			1	1		0.485	STOP
6+81.5	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
7+04.0	RT	W3-1	36x36	D36	9.00			1	1		0.485	STOP AHEAD
7+36.0	RT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
8+16.0	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
8+16.0	RT	R7-8	12x18	RV1218	1.50			1				HANDICAP RESERVED (LT ARROW)
8+96.0	RT	R7108	12x18	RV1218	1.50			1				2 HOUR PARKING
9+75.5	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
10+10.8	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
10+10.8	RT	RI-4	18x06		0.75			1	1		0.485	ALL WAY
10+13.0	LT			S214				1	1		0.485	W GALLATIN ST
10+13.0	LT			S214				1				S FIFTH ST
10+26.0	LT	RI-1	30x30	030	6.25			1	1		0.485	STOP
10+26.0	LT	RI-4	18x06		0.75			1				ALL WAY
10+88.0	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
10+88.0	RT	RI-4	18x06		0.75			1				ALL WAY
11+01.0	RT	R3-4	24x24	S24	4.00			1	1		0.485	NO U TURN
11+04.0	LT	RI-1	30x30	030	6.25			1	1		0.485	STOP
11+04.0	LT	RI-4	18x06		0.75			1				ALL WAY
11+37.0	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING (RT ARROW)
11+37.0	LT	R7-108	12x18	RV1218	1.50			1				15 MINUTE PARKING (LT ARROW)
11+37.0	RT	R7-108	12x18	RV1218	1.50			1				15 MINUTE PARKING (RT ARROW)
11+37.0	RT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING (LT ARROW)
11+88.0	LT	I-8	24x24	S24	4.00			1	1		0.485	LIBRARY (SYMBOL)
11+88.0	LT	I-8P	24x12	RV2412	2.00			1				LIBRARY (WORD)
11+88.0	LT	M7-1	21x15	RV2115	2.19			1				LEFT ARROW
12+37.0	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
13+35.0	LT	R3-4	24x24	S24	4.00			1	1		0.485	NO U TURN
13+37.0	RT	W3-3	36x36	D36	9.00			1	1		0.485	SIGNAL AHEAD
13+37.0	RT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
13+77.0	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
13+92.0	LT	R7-X	12x18	RV1218	1.50			1	1		0.485	NO PARKING HERE TO CORNER
13+92.0	LT	W3-1	36x36	D36	9.00			1				STOP AHEAD
14+23.0	LT	RI-1	30x30	030	6.25			1	1		0.485	STOP
14+77.0	RT	RI-1	30x30	030	6.25			1	1		0.485	STOP
15+01.0	LT			S214				1	1		0.485	W GALLATIN ST
15+01.0	LT			S214				1				S FOURTH ST
15+12.0	RT	R7-108	12x18	RV1218	1.50			1		1		2 HOUR PARKING
15+12.0	RT	R7-X	12x18	RV1218	1.50			1				NO PARKING HERE TO CORNER
15+21.0	LT	R7-108	12x18	RV1218	1.50			1		1		2 HOUR PARKING
15+21.0	LT	R7-X	12x18	RV1218	1.50			1				NO PARKING HERE TO CORNER
15+28.0	RT	M2-1	21x15	RV2115	2.19			1	1		0.485	JCT
15+28.0	RT	M1-4	24x24	S24	4.00			1				40
15+28.0	RT	M1-4	24x24	S24	4.00			1				51
15+28.0	RT	M1-5	30x24	RV3024	5.00			1				185
16+16.7	LT	R7-108	12x18	RV1218	1.50			1				2 HOUR PARKING
17+27.5	RT	D1-3	48x30	RV4830		10.00		1	1		0.485	DIRECTIONAL
17+95.5	RT	D6-X	24x30	RV2430	5.00			1	1		0.485	HISTORIC NATIONAL ROAD (RELOCATE)
17+95.5	RT	M4-X	24x12	RV2412	2.00			1				SPUR
17+95.5	RT	M6-1	21x15	RV2115	2.19			1				ARROW RIGHT
17+95.5	LT	D6-X	24x30	RV2430		5.00		1	1		0.485	HISTORIC NATIONAL ROAD (RELOCATE)
17+96.5	LT	R7-108	12x18	RV1218	1.50			1	1		0.485	2 HOUR PARKING
18+10.5	LT			S214				1	1		0.485	W GALLATIN ST
18+11.5	LT			S214				1				KENNEDY BLVD
TOTAL					189	15.00	10.00	12	65	30	7	14.6

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	23
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 95500				

PAVEMENT MARKINGS

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING				
		YELLOW		WHITE		
		LINE 4"	LINE 6"	LINE 6"	LINE 24"	LETTERS AND SYMBOLS
		FOOT	FOOT	FOOT	FOOT	SQ. FT.
GALLATIN STREET						
STA. 98+96 TO STA. 102+15	YELLOW - CENTERLINE - SKIP DASH	80.0				
	YELLOW - NO PARKING		300.0			
	WHITE - PARKING STALLS			180.0		
	WHITE - STOP BAR				20.0	
STA. 2+55 (STA 703+70 SEVENTH STREET) TO STA. 3+90	YELLOW - CENTERLINE - NO PASSING	366.0				
STA. 3+90 TO STA. 6+29	YELLOW - CENTERLINE - SKIP DASH	60.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - CROSSWALK			118.0		
STA. 6+92.5 TO STA. 10+23.5	YELLOW - CENTERLINE - NO PASSING	614.0				
	WHITE - PARKING STALLS			176.0		
	WHITE - TURN LANE			100.0		
	WHITE - LARGE LEFT TURN ARROW				31.2	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 10+90.5 TO STA. 14+22	YELLOW - CENTERLINE - NO PASSING	616.0				
	WHITE - PARKING STALLS			160.0		
	WHITE - TURN LANE			127.5		
	WHITE - LEFT TURN ARROW				62.4	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 14+83 TO STA. 18+02.5	YELLOW - CENTERLINE - NO PASSING	620.0				
	WHITE - PARKING STALLS			176.0		
	YELLOW - NO PARKING		450.0			
	WHITE - TURN LANE			127.0		
	WHITE - LEFT TURN ARROW				62.4	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			233.0		
SIXTH STREET						
STA. 603+15 TO STA. 604+10	YELLOW - CENTERLINE - NO PASSING	162.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - STOP BAR				21.0	
	WHITE - CROSSWALK			102.0		
STA. 604+71 TO STA. 605+32	YELLOW - CENTERLINE - NO PASSING	94.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - TURN LANE			47.0		
	WHITE - LEFT TURN ARROW				15.6	
	WHITE - STOP BAR				35.0	
	WHITE - CROSSWALK			129.0		
FIFTH STREET						
STA. 503+72 TO STA. 504+09	YELLOW - CENTERLINE - NO PASSING	46.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			23.0		
	WHITE - LEFT TURN ARROW				15.6	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			120.0		
STA. 504+72 TO STA. 504+98	YELLOW - CENTERLINE - NO PASSING	24.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			12.0		
	WHITE - STOP BAR				34.0	
	WHITE - CROSSWALK			122.0		
FOURTH STREET						
STA. 403+84.5 TO STA. 404+08	YELLOW - CENTERLINE - NO PASSING	19.0				
	WHITE - STOP BAR				23.0	
	WHITE - CROSSWALK			103.0		
STA. 404+71.5 TO STA. 404+98	YELLOW - CENTERLINE - NO PASSING	25.0				
	WHITE - STOP BAR				29.0	
	WHITE - CROSSWALK			129.0		
TOTALS		2726	750	2753	294	188
			3503			

REVISIONS	
NAME	DATE
LWJ	5-09-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY KOJ CHECKED BY BWC

CADD FILE: 4812/10th_4812.dgn
PLOTTED: 5/9/2007

H.M. & G. NO. 4812