

SCHEDULE OF QUANTITIES

F.A.U. 7695 / S. 14TH STREET

CITY OF MATTOON

SECTION 06-00144-00-RS

ROUTE: F.A.U. 7695

S. 14TH STREET

JOB#: C-97-043-07

PROJ#: M-5042(16)

CONTRACT#: 95501

COLES COUNTY

SHEET 7 OF 35

40600100 BITUMINOUS MATERIALS (PRIME COAT)
 Lt. ~ Rt., 0+00 ~ 33+82 =882.0 GALLON
 TOTAL =882.0 GALLON

40600300 AGGREGATE (PRIME COAT)
 Lt. ~ Rt., 0+00 ~ 33+82 =4 TON
 TOTAL =4 TON

40600982 HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT
 12' Lt. ~ Rt., 17+30 ~ 17+45 =40.0 SQ. YD.
 12' Lt. ~ Rt., 17+51 ~ 17+66 =40.0 SQ. YD.
 11' Lt. ~ Rt., 33+57 ~ 37' Lt. ~ 31' Rt. 33+82 =98.0 SQ. YD.
 TOTAL =178.0 SQ. YD.

60300350 MANHOLE FRAMES TO ADJUST
 3' Lt., 1+38 =1 EACH
 14' Lt., 2+51 =1 EACH
 11' Rt., 17+20 =1 EACH
 4' Rt., 17+80 =1 EACH
 3' Lt., 19+03 =1 EACH
 3' Lt., 22+64 =1 EACH
 3' Lt., 25+76 =1 EACH
 4' Lt., 28+86 =1 EACH
 4' Lt., 29+03 =1 EACH
 3' Lt., 32+07 =1 EACH
 5' Lt., 33+63 =1 EACH
 TOTAL =11 EACH

7800200 THERMOPLASTIC PVT. MK. LINE 4"
DASHED 10' YELLOW 4"
 C-L., 0+25 ~ 33+50 = 830.0 FOOT
SOLID WHITE 4"
 10' Lt. & Rt., 0+25 ~ 33+50 = 5850.0 FOOT
 TOTAL = 6680.0 FOOT

78000400 THERMOPLASTIC PVT MK LINE 6"
 23.5' Lt. ~ Rt., 0+00 =47.0 FOOT
 19' Lt. ~ Rt., 0+16 =38.0 FOOT
 18' Lt. ~ 11' Rt., 33+58 =29.0 FOOT
 18' Lt. ~ 11' Rt., 33+64 =29.0 FOOT
 TOTAL =143.0 FOOT

78000100 THPL PVT MK LTR & SYM
 ~17+78 = 122.4 SQ. FT.

78000650 THERMOPLASTIC PVT MK-LINE 24"
SOLID WHITE 24" STOP BAR
 CL. ~ 17' Lt., 0+24 =17.0 FOOT
 CL. ~ 11' Rt., 33+50 =11.0 FOOT
 ~ 17+48 =72.0 FOOT
 TOTAL =100 FOOT

40603335 HOT-MIX ASPHALT SURFACE COURSE MIX "D" N50
 12' Lt. ~ Rt., 0+00 ~ 19+47 =365 TON
 12' ~ 42.5' Lt., 0+00 ~ 12' ~ 18' Lt., 0+36 =3 TON
 12' ~ 42.5' Rt., 0+00 ~ 12' ~ 18' Rt., 0+36 =3 TON
 12' Lt. ~ Rt., 19+47 ~ 33+82 =246 TON
 11' ~ 37.4' Lt., 33+53 ~ 11' ~ 37.4' Lt., 33+82 =2 TON
 11' Rt. ~ 33+63 ~ 11' ~ 31 Rt., 33+82 =1 TON
 TOTAL =620 TON