

### SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK 4" (SQ FT)
STRATFORD LANE	
STA. 52+03.74 - 44.76' RT TO STA. 53+52.78 - 22.05' RT	608.3
STA. 53+87.79 - 21.58' RT TO STA. 55+08.53 - 21.58' RT	452.8
STA. 55+34.53 - 21.58' RT TO STA. 56+18.59 - 21.58' RT	312.2
STA. 56+34.59 - 21.58' RT TO STA. 56+84.94 - 19.62' RT	189.9
STA. 57+23.49 - 19.62' RT TO STA. 58+30.11 - 21.58' RT	397.2
STA. 58+42.11 - 21.58' RT TO STA. 59+08.27 - 21.58' RT	247.3
STA. 59+22.27 - 21.58' RT TO STA. 59+84.81 - 21.58' RT	227.2
STA. 59+98.81 - 21.58' RT TO STA. 60+98.93 - 21.58' RT	377.5
STA. 61+12.93 - 21.58' RT TO STA. 61+28.94 - 21.58' RT	46.7
STA. 61+46.94 - 21.58' RT TO STA. 62+49.01 - 21.58' RT	390.9
STA. 62+73.01 - 21.58' RT TO STA. 63+32.74 - 21.58' RT	215.9
STA. 63+54.74 - 21.58' RT TO STA. 63+58.67 - 21.58' RT	3.6
STA. 63+82.67 - 21.58' RT TO STA. 64+43.37 - 21.58' RT	219.8
STA. 64+67.37 - 21.58' RT TO STA. 65+71.87 - 21.58' RT	389.3
STA. 65+91.87 - 21.58' RT TO STA. 66+51.38 - 21.58' RT	196.5
STA. 66+75.38 - 21.58' RT TO STA. 66+87.23 - 21.58' RT	23.4
STA. 67+09.23 - 21.58' RT TO STA. 68+08.30 - 21.58' RT	379.0
STA. 68+26.30 - 21.58' RT TO STA. 68+88.48 - 21.58' RT	219.3
STA. 69+08.48 - 21.58' RT TO STA. 69+70.37 - 21.58' RT	189.2
STA. 69+88.37 - 21.58' RT TO STA. 70+80.55 - 22.08' RT	354.7
STA. 71+30.99 - 22.08' RT TO STA. 72+27.28 - 21.58' RT	371.2
STA. 72+45.28 - 21.58' RT TO STA. 73+02.02 - 21.58' RT	189.1
STA. 73+26.02 - 21.58' RT TO STA. 74+35.73 - 21.58' RT	359.9
STA. 74+53.73 - 21.58' RT TO STA. 75+21.78 - 21.58' RT	254.9
STA. 75+39.78 - 21.58' RT TO STA. 76+04.01 - 21.58' RT	239.6
STA. 76+22.01 - 21.58' RT TO STA. 76+89.96 - 21.58' RT	213.4
STA. 77+07.96 - 21.58' RT TO STA. 78+05.73 - 23.00' RT	385.3
STA. 78+48.64 - 44.21' RT TO STA. 78+60.41 - 20.47' RT	132.5
STA. 51+96.90 - 61.32' LT TO STA. 53+55.40 - 22.09' LT	711.3
STA. 53+82.30 - 21.58' LT TO STA. 55+58.52 - 22.08' LT	666.1
STA. 56+04.40 - 27.54' LT TO STA. 56+14.47 - 27.02' LT	38.9
STA. 56+91.39 - 26.85' LT TO STA. 56+98.79 - 26.84' LT	27.6
STA. 57+10.83 - 26.45' LT TO STA. 57+18.65 - 26.44' LT	24.9
STA. 58+53.61 - 26.29' LT TO STA. 58+63.56 - 26.77' LT	35.7
STA. 59+01.76 - 30.86' LT TO STA. 59+22.57 - 30.23' LT	81.4
STA. 59+63.28 - 29.90' LT TO STA. 59+64.28 - 29.90' LT	4.0
STA. 59+86.28 - 29.19' LT TO STA. 59+87.28 - 29.19' LT	3.5
STA. 60+43.48 - 28.88' LT TO STA. 60+44.48 - 28.88' LT	3.5
STA. 60+56.48 - 28.88' LT TO STA. 60+57.48 - 28.88' LT	3.5
STA. 61+41.52 - 28.65' LT TO STA. 61+42.90 - 28.65' LT	4.7
STA. 61+57.90 - 28.76' LT TO STA. 61+59.28 - 28.76' LT	5.0
STA. 62+04.67 - 28.89' LT TO STA. 62+09.35 - 28.88' LT	18.4
STA. 62+23.35 - 28.86' LT TO STA. 62+28.49 - 28.85' LT	20.1
STA. 62+40.49 - 28.75' LT TO STA. 62+45.17 - 28.74' LT	17.9
STA. 63+22.86 - 28.72' LT TO STA. 63+23.86 - 28.73' LT	3.8
STA. 63+35.86 - 28.85' LT TO STA. 63+36.86 - 28.85' LT	3.9
STA. 63+83.72 - 28.86' LT TO STA. 63+87.92 - 28.86' LT	16.5
STA. 63+99.92 - 28.79' LT TO STA. 64+04.12 - 28.78' LT	16.1
STA. 64+53.99 - 28.70' LT TO STA. 64+58.43 - 28.69' LT	16.3
STA. 64+76.43 - 28.75' LT TO STA. 64+80.87 - 28.75' LT	16.8
STA. 65+21.73 - 29.06' LT TO STA. 65+31.33 - 29.05' LT	38.4
STA. 65+49.33 - 29.02' LT TO STA. 65+58.93 - 29.00' LT	37.9
STA. 65+90.61 - 28.92' LT TO STA. 66+00.03 - 28.91' LT	36.3
STA. 66+16.03 - 28.73' LT TO STA. 66+25.45 - 28.72' LT	33.1
STA. 66+84.88 - 29.15' LT TO STA. 66+94.04 - 29.13' LT	31.9
STA. 67+42.87 - 50.76' LT TO STA. 67+55.12 - 28.98' LT	106.7
STA. 67+78.52 - 28.97' LT TO STA. 67+82.02 - 28.96' LT	13.6
STA. 68+17.02 - 28.97' LT TO STA. 68+20.52 - 28.97' LT	13.5
STA. 68+30.59 - 28.95' LT TO STA. 68+34.37 - 28.94' LT	14.3
STA. 68+46.37 - 28.92' LT TO STA. 68+50.15 - 28.91' LT	14.3
STA. 68+99.21 - 28.94' LT TO STA. 69+04.91 - 28.93' LT	22.1
STA. 69+16.91 - 28.95' LT TO STA. 69+22.61 - 28.94' LT	22.3
SUBTOTAL	9710.9

### SIDEWALK SCHEDULE (CONT.)

LOCATION	PCC SIDEWALK 4" (SQ FT)
STA. 69+54.76 - 28.94' LT TO STA. 69+62.14 - 28.93' LT	29.2
STA. 69+74.14 - 28.91' LT TO STA. 69+75.55 - 28.90' LT	5.6
STA. 69+87.55 - 28.83' LT TO STA. 69+94.63 - 28.82' LT	27.2
STA. 70+27.03 - 28.66' LT TO STA. 70+32.43 - 28.65' LT	19.4
STA. 70+44.43 - 28.68' LT TO STA. 70+49.83 - 28.67' LT	19.7
STA. 70+89.98 - 28.78' LT TO STA. 70+94.78 - 28.77' LT	18.4
STA. 71+06.78 - 28.78' LT TO STA. 71+11.58 - 28.77' LT	18.7
STA. 71+65.26 - 28.74' LT TO STA. 71+66.58 - 28.74' LT	5.2
STA. 71+78.58 - 28.74' LT TO STA. 71+79.90 - 28.74' LT	5.2
STA. 72+28.07 - 28.81' LT TO STA. 72+30.07 - 28.81' LT	7.9
STA. 72+42.07 - 28.79' LT TO STA. 72+44.07 - 28.79' LT	7.9
STA. 72+85.92 - 28.77' LT TO STA. 72+89.58 - 28.76' LT	14.3
STA. 73+01.58 - 28.77' LT TO STA. 73+05.24 - 28.76' LT	14.3
STA. 73+48.24 - 28.80' LT TO STA. 73+52.86 - 28.80' LT	17.8
STA. 73+69.36 - 28.81' LT TO STA. 73+73.98 - 28.80' LT	17.7
STA. 74+14.86 - 28.94' LT TO STA. 74+21.94 - 28.93' LT	26.8
STA. 74+39.94 - 28.99' LT TO STA. 74+47.02 - 28.98' LT	26.7
STA. 74+88.22 - 29.14' LT TO STA. 74+93.72 - 29.16' LT	21.0
STA. 75+05.72 - 29.23' LT TO STA. 75+11.22 - 29.26' LT	21.5
STA. 75+54.54 - 29.26' LT TO STA. 75+61.04 - 29.25' LT	25.5
STA. 75+73.04 - 29.23' LT TO STA. 75+88.36 - 29.18' LT	59.8
STA. 76+00.36 - 29.14' LT TO STA. 76+08.46 - 29.12' LT	31.9
STA. 76+30.20 - 29.01' LT TO STA. 76+39.38 - 28.99' LT	36.2
STA. 76+51.38 - 28.94' LT TO STA. 76+60.56 - 28.93' LT	36.0
STA. 76+91.22 - 28.82' LT TO STA. 76+99.14 - 28.80' LT	31.8
STA. 77+11.14 - 28.77' LT TO STA. 77+19.06 - 28.76' LT	32.2
STA. 77+94.04 - 15.92' LT TO STA. 77+99.04 - 17.22' LT	38.9
STA. 78+04.14 - 28.87' LT TO STA. 78+13.20 - 28.86' LT	34.6
STA. 78+50.35 - 44.92' LT TO STA. 78+75.70 - 21.58' LT	173.7
SUBTOTAL (PREVIOUS SCHEDULE)	9710.9
SUBTOTAL (THIS SCHEDULE)	825.1
TOTAL	10536

### PROTECTIVE COAT SCHEDULE

LOCATION	VOLUME (SQ YD)
STRATFORD LANE	
COMBINATION CURB AND GUTTER, B-6.24	1854
DRIVEWAY PAVEMENT	2311
4" PCC SIDEWALK	1171
TOTAL	5336

### PAVING SCHEDULE

LOCATION	PROCESSING MODIFIED SOIL 12 IN (SQ YD)	LIME (TON)	BIT MATL PR CT (GALLON)	AGGREGATE BASE COURSE, TYPE A 8" (SQ YD)	SUB-BASE GRANULAR MATERIAL, TYPE A (TON)	HOT-MIX ASPHALT, SURFACE COURSE MIX C, N70, 2" (TON)	HOT-MIX ASPHALT, BINDER COURSE, IL-19, N70, 4" (TON)	INCIDENTAL HOT-MIX ASPHALT SURFACING, N70, 3" (TON)
STRATFORD LANE								
STA. 52+33.30 TO STA. 79+57.94	11093.0	274.6	2229.0		2278.6	998.4	1996.8	
MOCKINGBIRD LANE								
STA. 148+02.53 TO STA. 148+42.53				7.6				18.3
TOTAL	11093	275	2229	8	2279	998	1997	18

DATE	BY
SURVEYED	
REPLATED	
NOTE BOOK	
TEMPLATE	
AREAS	
CHECKED	
NO.	

DATE	BY
ORIGINAL SURVEYED	
REPLATED	
NOTE BOOK	
TEMPLATE	
AREAS	
CHECKED	
NO.	

Juneau Associates, Inc. P.C.  
CONSULTING ENGINEERS AND LAND SURVEYORS  
2100 State Street, P.O. Box 320  
Granite City, Illinois 60040  
Phone: (618) 257-1400 / FAX: (618) 257-1400  
FAC: (618) 257-1400

QUANTITY SCHEDULES  
F.A.U. ROUTE 9024  
STRATFORD LANE  
GRANITE CITY, ILLINOIS  
SECTION No. 05-00187-01-RP

REVISIONS		SCALE: NOT TO SCALE
NO.	DATE BY REMARKS	DSN. BY: BFK DATE: 1/12/07 SHEET 9
		DWN. BY: DAN DATE: 1/12/07
		CHKD: BFK DATE: 1/12/07
DWG. NO.	JOB NO. E050210 DSN. NAME: STRATSCH OF 79 SHTS	