

### MANHOLE AND INLET SCHEDULE


STRUCTURE ID	LOCATION	INLET						MANHOLE TYPE A, 5' DIAMETER TY 1 F&CL (EACH)
		TYPE A	TYPE B	SPECIAL	SPECIAL	SPECIAL	SPECIAL	
		TY 3 F&G (EACH)	TY 3 F&G (EACH)	TYPE 1 (EACH)	TYPE 2 (EACH)	TYPE 3 (EACH)	TYPE 4 (EACH)	
S-18	STRATFORD LANE							
S-16	STA. 52+40.00 - 19.88' RT		1					
S-14	STA. 54+20.00 - 17.00' RT			1				
S-12	STA. 56+84.70 - 22.95' RT				1			
S-11	STA. 57+23.73 - 22.95' RT				1			
S-06	STA. 57+60.70 - 17.50' RT				1			
S-04	STA. 58+20.00 - 17.00' RT			1				
S-01	STA. 59+42.00 - 17.00' RT			1				
I-49	STA. 60+65.00 - 17.00' RT			1				
I-47	STA. 62+89.00 - 17.00' RT			1				
I-45	STA. 64+32.00 - 17.00' RT			1				
I-44	STA. 65+02.00 - 17.00' RT			1				
I-41	STA. 65+63.00 - 17.00' RT			1				
I-37	STA. 66+01.00 - 17.50' RT				1			
I-35	STA. 66+32.00 - 17.50' RT				1			
I-55	STA. 67+72.12 - 17.50' RT				1			
I-33	STA. 68+80.00 - 17.50' RT				1			
I-32	STA. 68+00.00 - 18.00' RT					1		
I-29	STA. 69+17.00 - 18.00' RT					1		
I-27	STA. 69+50.00 - 18.00' RT					1		
I-27	STA. 70+81.83 - 27.01' RT					1		
I-51	STA. 71+29.70 - 27.01' RT					1		
I-26	STA. 71+29.70 - 27.01' RT					1		
I-22	STA. 72+93.30 - 18.00' RT					1		
I-22	STA. 73+68.31 - 18.00' RT					1		
I-21	STA. 73+78.31 - 18.00' RT					1		
I-19	STA. 74+27.00 - 18.00' RT					1		
I-17	STA. 74+27.00 - 18.00' RT					1		
I-13	STA. 76+30.00 - 18.00' RT					1		
I-13	STA. 76+81.00 - 18.00' RT					1		
I-10	STA. 77+40.00 - 18.00' RT					1		
I-61	STA. 78+02.56 - 38.05' RT					1		
I-53	STA. 78+07.57 - 25.40' RT					1		
J-02	STA. 78+32.90 - 6.49' RT					1		
S-17A	STA. 51+98.78 - 32.56' LT						1	
S-19	STA. 51+98.88 - 56.85' LT						1	
S-17	STA. 52+40.00 - 23.78' LT				1			
S-15	STA. 54+20.00 - 17.50' LT				1			
S-21	STA. 55+35.00 - 17.50' LT				1			
S-23	STA. 56+04.33 - 30.50' LT			1				
S-13	STA. 56+70.00 - 14.22' LT							
S-08	STA. 57+60.70 - 14.21' LT		1					
S-05	STA. 58+20.00 - 14.21' LT		1					
S-22	STA. 59+02.06 - 33.90' LT			1				
S-03	STA. 59+42.00 - 14.22' LT			1				
S-02	STA. 60+65.00 - 14.21' LT			1				
I-50	STA. 62+89.00 - 14.21' LT			1				
I-48	STA. 64+32.00 - 14.22' LT			1				
I-46	STA. 65+02.00 - 14.71' LT			1				
I-43	STA. 65+91.00 - 14.72' LT			1				
I-39	STA. 66+32.00 - 14.72' LT			1				
I-56	STA. 67+72.14 - 14.72' LT			1				
I-36	STA. 68+55.00 - 14.22' LT			1				
I-35	STA. 68+96.00 - 14.21' LT			1				
I-31	STA. 69+50.00 - 14.21' LT			1				
I-28	STA. 70+60.00 - 14.22' LT			1				
I-24	STA. 73+44.00 - 14.22' LT			1				
I-25	STA. 73+78.31 - 14.22' LT			1				
I-20	STA. 74+49.00 - 14.22' LT			1				
I-18	STA. 76+30.00 - 14.22' LT			1				
I-15	STA. 76+85.13 - 14.22' LT			1				
I-12	STA. 77+40.00 - 14.22' LT			1				
I-54	STA. 78+05.73 - 19.09' LT			1				
I-52	STA. 78+52.38 - 31.70' LT			1				
TOTAL		4	19	11	11	12	1	2

### CURB AND GUTTER SCHEDULE

LOCATION	COMBINATION CONCRETE C & G TYPE B-6.24 (FOOT)
STRATFORD LANE	
STA. 52+26.86-21.28' RT TO STA. 56+75.78-15.00' RT	449.1
STA. 56+75.78-15.00' RT TO STA. 56+90.80-29.72' RT	22.7
STA. 57+17.69-30.20' RT TO STA. 57+32.67-15.00' RT	23.1
STA. 57+32.67-15.00' RT TO STA. 70+62.83-15.00' RT	1330.2
STA. 70+62.83-15.00' RT TO STA. 70+92.83-45.06' RT	46.5
STA. 71+18.73-44.94' RT TO STA. 71+48.70-15.00' RT	46.3
STA. 71+48.70-15.00' RT TO STA. 77+90.05-15.00' RT	641.4
STA. 77+90.05-15.00' RT TO STA. 78+18.04-42.89' RT	43.9
STA. 78+18.04-42.89' RT TO STA. 78+76.04-15.00' RT	44.1
STA. 78+76.04-15.00' RT TO STA. 79+57.43-15.00' RT	81.4
STA. 51+96.31-61.32' LT TO STA. 55+70.80-47.69' LT	420.8
STA. 55+70.80-47.69' LT TO STA. 56+27.05-15.00' LT	49.0
STA. 56+27.05-15.00' LT TO STA. 58+41.45-15.00' LT	214.4
STA. 58+41.45-15.00' LT TO STA. 58+71.37-56.84' LT	57.9
STA. 58+71.37-56.84' LT TO STA. 59+26.34-15.00' LT	57.9
STA. 59+26.34-15.00' LT TO STA. 66+67.69-15.00' LT	741.4
STA. 66+67.69-15.00' LT TO STA. 67+02.69-50.14' LT	54.4
STA. 67+02.69-50.14' LT TO STA. 67+71.15-15.00' LT	54.3
STA. 67+71.15-15.00' LT TO STA. 77+89.70-15.00' LT	1018.5
STA. 77+89.70-15.00' LT TO STA. 78+19.70-45.11' LT	46.5
STA. 78+19.70-45.11' LT TO STA. 78+75.70-15.00' LT	46.3
STA. 78+75.70-15.00' LT TO STA. 79+48.36-15.00' LT	72.7
TOTAL	5563

DATE	
BY	
FINAL SURVEY	
SURVEY	
BOOK	
NO. DATE	
AREAS	
CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEY	
SURVEY	
BOOK	
NO. DATE	
AREAS	
CHECKED	
NO.	

 <b>Juneau Associates, Inc. P.C.</b> CONSULTING ENGINEERS AND LAND SURVEYORS 2100 State Street, P.O. Box 1000 Granite City, Illinois 62401 Phone: (618) 937-1400 / (618) 937-0335 Fax: (618) 937-0341	<b>QUANTITY SCHEDULES</b> F.A.U. ROUTE 9024 STRATFORD LANE GRANITE CITY, ILLINOIS SECTION No. 05-00187-01-RP																
	REVISIONS <table border="1"> <tr><th>NO.</th><th>DATE</th><th>BY</th><th>REMARKS</th></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </table>		NO.	DATE	BY	REMARKS											
NO.	DATE	BY	REMARKS														
SCALE: NOT TO SCALE DSN. BY: BFK DATE: 1/12/07 DWN. BY: DAN DATE: 1/12/07 CHKD: BFK DATE: 1/12/07 JOB NO. E050210 DGN. NAME: STRATSCH OF 79 SHTS		SHEET <b>10</b>															