SUMMARY OF QUANTITIES

CONTRACT NO. 97305

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	466		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	162		
20100500	TREE REMOVAL, ACRES	ACRE	0.3		
20200100	EARTH EXCAVATION	CU YD	1,162		
20400800	FURNISHED EXCAVATION	CU YD	2,005		
20800150	TRENCH BACKFILL	CU YD	263		
25000200	SEEDING, CLASS 2	ACRE	1.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	99		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	99		
25100115	MULCH, METHOD 2	ACRE	1.1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	251		
28000300	TEMPORARY DITCH CHECKS	EACH	2		
28000400	PERIMETER EROSION BARRIER	FOOT	85		
28000500	INLET AND PIPE PROTECTION	EACH	13		
28100107	STONE RIPRAP, CLASS A4	SQ YD	34		
28200200	FILTER FABRIC	SQ YD	34		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3,566		
30201500	LIME	TON	69		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,244		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	321		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		
50105220	PIPE CULVERT REMOVAL	FOOT	115		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	812		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	81		
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	84		
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	36		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4		
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	3		
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	4		
60240390	INLETS, TYPE B, WITH SPECIAL GRATE	EACH	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,807		
63200310	GUARDRAIL REMOVAL	FOOT	163		
67100100	MOBILIZATION	L SUM	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	600		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	34		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,407		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10		
XX006471	STORM SEWERS, TYPE 1, WATERMAIN QUALITY PIPE, SDR-21 12"	FOOT	70		
Z0022800	FENCE REMOVAL	FOOT	90		

* SPECIALTY ITEMS

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS ◆ SURVEYORS ◆ PLANNERS

☒ CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

☐ WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

☐ ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 336-5052
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-000886
PROFESSIONAL ENGINEERING CORP.	184-000886
PROFESSIONAL STRUCTURAL ENGR. CORP.	184-000886
ILLINOIS PROF. LAND SURVEYING CORP.	184-000886
MISSOURI PROFESSIONAL ENGR. CORP.	MO 000886
MISSOURI LAND SURVEYING CORP.	MO 000886

SEAL

Signature: _____
Signature Date: _____
Expiration Date: _____

STATEMENT OF RESPONSIBILITY

I hereby confirm that the document herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

TITLE: SUMMARY OF QUANTITIES

PROJECT: SEIBERT ROAD RECONSTRUCTION - PHASE IV
VILLAGE OF SHILOH
ST. CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY:	MJJ	SHEET 3
DESIGNED BY:	MJJ	
CHECKED BY:	XXX	
APPROVED BY:	XXX	
PROJECT NUMBER	D20010479	OF 36 SHEETS

☐ ISSUED FOR REVIEW ☐ ISSUED FOR BIDDING
☐ ISSUED FOR CONSTR. ☐ RECORD DRAWING

LOT DATE = 3/21/2007
FILE NAME = P:\010479\dgn\Phase IV Plans-REVISED 2-16-07\010479SUM4.dgn
PLOT SCALE = 112.0000 ' / IN.
USER NAME = dbiggs
..\010479SUMM 4.dgn 3/21/2007 3:25:34 PM