



CORPORATE OFFICE
4840 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6888
corp@twm-inc.com

WATERLOO OFFICE
118 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5060
FAX (618) 939-3998
waterloo@twm-inc.com

ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 360
ST. LOUIS, MISSOURI 63146
TEL (314) 296-6062
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	104-00289
PROFESSIONAL ENGINEERING CORP.	61-00079
PROFESSIONAL STRUCTURAL ENGR. CORP.	61-00022
ILLINOIS PROF. LAND SURVEYING CORP.	606-00020
MISSOURI PROFESSIONAL ENGR. CORP.	NC 00046
MISSOURI LAND SURVEYING CORP.	NC 00046

SEAL:

Signature: _____
Expiration Date: _____
STATEMENT OF RESPONSIBILITY
I hereby certify that the documents herein to be authorized by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

PAVING SCHEDULE						
LOCATION STATION TO STATION	HOT MIX ASPHALT BINDER COURSE, IL 19.0, N70 (TON)	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70 (TON)	PROCESSING MODIFIED SOILS, 12" (SQ. YD.)	LIME (TON)	COMBINATION CURB & GUTTER TYPE B 6.24 (FEET)	
SEIBERT ROAD						
33+39.32 TO 35+00.00	55.5	14.3	179	3.5		
35+00.00 TO 44+03.40	1132.7	292.3	3228	62	1807	
44+03.40 TO 44+53.40	55.5	14.3	179	3.5		
TOTAL:	1244	321	3586	69	1807	

EARTHWORK SCHEDULE				
LOCATION STATION TO STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE FACTOR (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
SEIBERT ROAD				
33+75.50 TO 44+03.40	1162	872	2877	-2005
TOTAL:	1162	872	2877	-2005

SEEDING SCHEDULE					
LOCATION STATION TO STATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD, 2 (ACRE)
SEIBERT ROAD					
33+75.50 TO 44+03.40	1.1	99	99	99	1.1
TOTAL:	1.1	99	99	99	1.1

THERMOPLASTIC PAVEMENT MARKING SCHEDULE	
STATION TO STATION	4" MARKINGS SOLID YELLOW (FOOT)
SEIBERT ROAD	
36+00.00 TO 43+03.40	1407
TOTAL:	1407

TEMPORARY PAVEMENT MARKING SCHEDULE			
STATION TO STATION	4" MARKINGS SOLID YELLOW (FOOT)	4" MARKINGS SOLID WHITE (FOOT)	8" MARKINGS SOLID WHITE (FOOT)
SEIBERT ROAD			
35+00.00 TO 36+00.00	200		
35+00.00 TO 36+00.00		100	17
43+03.04 TO 44+03.04	200	100	17
SUB-TOTAL:	400	200	34
TOTAL:	600	300	34

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE	
STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKERS TWO-WAY AMBER (EACH)
SEIBERT ROAD	
36+00.00 TO 43+03.40	10
TOTAL:	10

TREE REMOVAL			
LOCATION	OFFSET (FT)	TREE REM. 6 TO 15 UNIT	TREE REM. OVER 15 UNIT
37+42.90	26.37	RT	6
37+46.86	23.48	RT	6
37+48.20	26.87	RT	6
37+48.99	26.59	RT	6
37+57.08	27.20	RT	6
37+61.83	21.53	RT	6
37+62.49	21.75	RT	6
37+64.24	23.89	RT	6
37+69.70	26.08	RT	6
37+80.20	22.49	RT	6
37+81.06	20.48	RT	7
37+92.03	27.54	RT	6
37+97.10	22.78	RT	6
38+06.77	22.38	RT	8
38+14.32	18.09	RT	6
38+32.06	24.45	RT	7
38+40.81	25.09	RT	8
38+46.86	25.29	RT	8
38+47.73	32.54	RT	10
38+57.60	26.17	RT	6
38+63.35	23.56	RT	6
38+66.39	22.28	RT	6
38+67.67	33.56	RT	8
38+70.37	32.29	RT	6
38+71.29	32.42	RT	6
38+75.81	32.31	RT	6
38+77.80	21.81	RT	8
38+81.11	29.89	RT	6
38+87.34	25.22	RT	10
38+88.29	21.17	RT	6
38+97.41	26.44	RT	12
38+99.88	25.31	RT	8
39+01.43	22.66	RT	8
39+11.00	27.37	RT	18
39+11.25	23.33	RT	10
39+13.62	23.29	RT	12
39+17.38	24.12	RT	12
39+23.50	25.60	RT	12
39+24.23	22.14	RT	15
39+27.40	24.68	RT	12
39+42.09	19.96	RT	10
39+43.42	28.54	RT	6
39+47.07	21.79	RT	10
39+47.58	23.85	RT	15
39+52.52	23.20	RT	6
39+60.86	24.36	RT	18
39+68.09	26.47	RT	18
40+18.92	23.03	RT	12
40+21.35	21.09	RT	6
40+26.80	22.03	RT	12
40+27.73	20.97	RT	10
40+44.33	23.53	RT	12
40+47.03	23.14	RT	24
40+62.87	21.74	RT	16
40+76.10	22.43	RT	6
40+77.79	22.34	RT	6
40+79.45	20.67	RT	24
40+81.60	23.39	RT	18
41+07.75	22.01	RT	12
41+14.40	19.71	RT	10
43+78.71	21.42	LT	12
43+87.52	20.18	LT	24
43+95.73	16.03	LT	6
43+96.59	21.74	LT	8
44+05.65	17.79	LT	6
TOTAL:		466	162

TREE REMOVAL	
STATION TO STATION	TREE REMOVAL (ACRES)
33+39.32 RT TO 36+00.00 RT	0.07
33+45.11 LT TO 35+86.03 LT	0.25
TOTAL:	0.3

SCHEDULE OF QUANTITIES

SEIBERT ROAD RECONSTRUCTION - PHASE IV VILLAGE OF SHILOH ST. CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: MJJ
DESIGNED BY: MJJ
CHECKED BY: XXX
APPROVED BY: XXX

PROJECT NUMBER: D20010479 OF 96 SHEETS

ISSUED FOR REVIEW ISSUED FOR BIDDING ISSUED FOR CONSTR. RECORD DRAWING

5