CONTRACT NO. 98782

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 885 | * | HARDIN | 26 | 3 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

* 5 RS-3 (13, 11, 8) RS

# SUMMARY OF QUANTITIES

| | |
|---|---|
| FUNDING: | 80% FEDERAL 20% STATE |
| COUNTY: | HARDIN |
| LOCATION: | RURAL |
| ROUTE: | FAP 885 (IL 146) |

| CODE NUMBER | ITEM DESCRIPTION | UNIT | PROJECT TOTAL QUANTITY | ROADWAY | CULVERT |
|---|---|---|---|---|---|
| | | | WORK TYPE: | ROADWAY | CULVERT |
| | | | CONST TYPE CODE: | I000 | SFTY-2A |
| | | | | | S. N. 035-2002 |
| X0300203 | CLEAN AND FILL EXPANSION JOINTS | EACH | 408.0 | 408.0 | |
| X0322729 | MATERIAL TRANSFER DEVICE | TON | 26,915.0 | 26,915.0 | |
| Z0017202 | DOWEL BARS 1 1/2" | EACH | 3,020.0 | 3,020.0 | |
| Z0075310 | TIE BARS 3/4" | EACH | 26.0 | 26.0 | |
| ~~Z0076600~~ | ~~TRAINEES~~ | ~~HOUR~~ | ~~500.0~~ | ~~500.0~~ | |
| 20200600 | EXCAVATING AND GRADING EXISTING SHOULDER | UNIT | 620.0 | 619.8 | 0.2 |
| 20201006 | GRADING AND SHAPING SHOULDERS | UNIT | 277.0 | 277.0 | |
| 21400100 | GRADING AND SHAPING DITCHES | FOOT | 300.0 | 300.0 | |
| 25000350 | SEEDING, CLASS 7 | ACRE | 6.5 | 6.5 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 1,040.0 | 1,040.0 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 780.0 | 780.0 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 780.0 | 780.0 | |
| 25000700 | AGRICULTURAL GROUND LIMESTONE | TON | 13.0 | 13.0 | |
| 25001010 | SEEDING, CLASS 2 (MODIFIED) | ACRE | 6.5 | 6.5 | |
| 25100115 | MULCH, METHOD 2 | ACRE | 13.0 | 13.0 | |
| 28100207 | STONE RIPRAP, CLASS A4 | TON | 348.0 | | 348.0 |
| 35101400 | AGGREGATE BASE COURSE, TYPE B | TON | 1,201.0 | 1,201.0 | |
| 40600100 | BITUMINOUS MATERIAL (PRIME COAT) | GALLON | 20,921.0 | 20,916.6 | 4.4 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 334.0 | 333.9 | 0.1 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 45.0 | 45.0 | |
| 40600645 | LEVELING BINDER (MACHINE METHOD), N90 | TON | 8,583.0 | 8,579.7 | 3.3 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2.0 | 2.0 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 2,139.0 | 2,139.0 | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 68.0 | 68.0 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 600.0 | 600.0 | |
| 40603090 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 | TON | 2,140.0 | 2,139.5 | 0.5 |
| 40603320 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90 | TON | 18,332.0 | 18,327.9 | 4.1 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 728.0 | 728.0 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 285.0 | 285.0 | |
| 44000151 | HOT-MIX ASPHALT SURFACE REMOVAL, 1/2" | SQ YD | 90,836.0 | 90,836.0 | |
| 44000198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 498.0 | 498.0 | |



| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 3/5/2007
FILE NAME = c:\pw_acts\cf980103\d980103ch_sh32
PLOT SCALE = 5.0000 ' / IN.
USER NAME = krontz,jp