

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	*	HARDIN	26	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* 5 RS-3 (13, 11, 8) RS

# SUMMARY OF QUANTITIES

FUNDING:	80% FEDERAL 20% STATE
COUNTY:	HARDIN
LOCATION:	RURAL
ROUTE:	FAP 885 (IL 146)

WORK TYPE:	ROADWAY	CULVERT
CONST TYPE CODE:	I000	SFTY-2A
		S. N. 035-2002

CODE NUMBER	ITEM DESCRIPTION	UNIT	PROJECT TOTAL QUANTITY		
44002710	GUTTER REMOVAL (PARTIAL)	FOOT	26,712.0	26,712.0	
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	40.0	40.0	
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	2,017.0	2,017.0	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	65.0	65.0	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	57.0	57.0	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	1,115.0	1,115.0	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	19.0	19.0	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	60.0	60.0	
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	44.0	44.0	
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	40.0	40.0	
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	1,198.0	1,198.0	
44213100	PAVEMENT FABRIC	SQ YD	79.0	79.0	
44213200	SAW CUTS	FOOT	6,840.0	6,840.0	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	112,044.0	112,026.0	18.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,977.0	2,976.5	0.5
50105220	PIPE CULVERT REMOVAL	FOOT	81.0	81.0	
60255500	MANHOLES TO BE ADJUSTED	EACH	18.0	18.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	1.0	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.0	2.0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	25,206.0	25,206.0	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	249,247.0	249,247.0	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	103.0	103.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,801.0	2,801.0	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	103.0	103.0	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	249,247.0	249,247.0	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,040.0	1,040.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,030.0	1,030.0	

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. DATE  
HORIZ.

DRAWN BY JCK  
CHECKED BY