

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	*	HARDIN	26	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 5 RS-3 (13, 11, 8) RS

SURFACE REMOVAL SCHEDULE

LOCATION: STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
	SQ YD	SQ YD	SQ YD	SQ YD
IL 146				
FAP 885				
STA 2+00			57.8	14.4
STA 2+00 TO STA 9+41.56 BK	2,142.3			
STA 9+39.43 AH TO STA 37+65.31 BK	8,163.7			
STA 37+72.76 AH TO STA 73+65	10,377.6			
STA 73+65 TO STA 76+48	817.6			
STA 76+48			57.8	14.4
STA 77+12			57.8	14.4
STA 77+12 TO STA 92+88.84 BK	4,555.3			
STA 92+97.83 AH TO STA 94+29	378.9			
STA 94+29 TO STA 139+63.19 BK	13,098.8			
STA 139+61.40 AH TO STA 159+30.00	5,687.1			
STA 159+30 TO STA 213+56	15,675.1			
STA 213+56 TO STA 263+82.56 BK	14,521.2			
STA 263+84.98 AH TO STA 278+19	4,142.7			
STA 278+19			57.8	14.4
STA 283+41			57.8	14.4
STA 283+41 TO STA 295+03	3,356.9			
STA 295+03 TO STA 308+28	4,269.4			
STA 308+28 TO STA 308+73	145.0			
STA 308+73 TO STA 317+49 BK	3,504.4			
STA 317+49 BK TO STA 0+00 AH				4.1
STA 0+00 TO STA 2+12		339.5		
STA 2+12 TO STA 3+90		158.5		
STA 84+86.75			93.5	35.5
STA 86+16			93.5	35.5
STA 227+67			80.0	13.3
STA 228+89			80.0	13.3
STA 481+00			80.0	13.3
SCHEDULE TOTALS:	90,836.0	498.0	716.0	187.0
FROM ENTRANCE AND SIDEROAD SCHEDULE:			1423.0	413.0
IMPROVEMENT TOTALS:	90,836.0	498.0	2,139.0	600.0

PLOT DATE = 2/6/2007
 FILE NAME = c:\prowork\980703\980703.sch\2
 USER NAME = kranjs

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION <h3 style="margin: 0;">SCHEDULE</h3>
NAME	DATE	
SCALE: VERT. _____		DRAWN BY JCK CHECKED BY _____
DATE _____		