

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-03, 4-1, 4-2R5-2	PULASKI	52	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 2 OF 3

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	90% FEDERAL / 10% STATE PULASKI COUNTY		
			TOTAL QUANTITY	I-57	MOUNDS RD FAS 939
				I 000	I 000
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	11760	11760	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	190	171	25
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	127817	127817	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	667	667	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	760	760	
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	346	346	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	690	690	
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	65	65	
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	819	819	
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	321	133	188
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	58		58
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	39		39
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	112	112	
44213000	PATCHING REINFORCEMENT	SQ YD	1860	1860	
44213100	PAVEMENT FABRIC	SQ YD	97		97
44213200	SAW CUTS	FOOT	12,005	11006	999
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3279	3133	146
48203100	HOT-MIX ASPHALT SHOULDERS	TON	15,573	15173	400
50300255	CONCRETE SUPERSTRUCTURE	CU YD	6.6	5.4	1.2
50300300	PROTECTIVE COAT	SQ YD	50	40	10
50800105	REINFORCEMENT BARS	POUND	3939	3939	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	935	775	160
54002020	EXPANSION BOLTS 3/4 INCH	EACH	68	68	
54003000	CONCRETE BOX CULVERTS	CU YD	27	27	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	5	5	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
54248510	CONCRETE COLLAR	CU YD	0.3	0.3	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	10	10	
60100072	SHOULDER REMOVAL AND REPLACEMENT 5"	FOOT	76	76	
60108100	PIPE DRAINS 4" (SPECIAL)	FOOT	164	164	
60406500	FRAMES AND LIDS, SPECIAL	EACH	1	1	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	6680	6680	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	131	131	
* 63001105	FURNISHING AND INSTALLING GUARD RAIL BLOCKS	EACH	542	418	124
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	5	2
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	8	6	2
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	12	

* SPECIALTY ITEM

PLOT DATE = 3/21/2007
 FILE NAME = c:\pvs\extra\9884603\9884603.sch2.m32
 PLOT SCALE = 80.0000 / IN.
 USER NAME = thomashf

Rev.