CONTRACT NO. 98829

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-13, 4-1, 4-2)RS-2	PULASKI	52	14
STA.		TO STA.		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

RESURFACING AND SHOULDER SCHEDULE (INTERCHANGE RAMPS/MOUNDS ROAD)

LOCATION STATION TO STATION	LENGTH / AREA (FOR INFORMATION ONLY)	POLYMERIZED HMA BINDER COURSE	POLYMERIZED HMA SURFACE COURSE	HMA SURFACE COURSE	PRIME COAT			SHOULDERS		TEMPORARY RAMP	HMA SURFACE REMOVAL 1 1/2"	HMA SURFACE REMOVAL BUTT JOINT	PCC SURFACE REMOVAL BUTT JOINT
					BITUMINOUS MATERIALS	BIT MATERIALS	AGGREGATE	AGGREGATE TYPE B	HOT-MIX ASPHALT				
	FEET / SQ FEET	TONS	TONS	TONS	GAL	GAL	TONS	TONS	TONS	SQ YD	SQ YD	SQ YD	SQ YD
RAMP A													
STA 0+24.50 TO STA 1+13.83	3505.55 SQ FT		32.72			35	0.6	8.48	19.46	29.63			
STA 1+13.83 TO STA 1+38.83	25.00	4.07	3.76			7	0.1	3.56	8.25				
STA 1+38.83 TO STA 10+56	917.17	206.52	138.03			257	4.3	130.61	302.67				
STA 10+56 TO STA 11+11	55.00	14.56	8.28			15	0.3	7.83	18.15	11.85			
TRANSITION FROM MAINLINE TO RAMP	12952.39 SQ FT	181.33	120.89			130	2.2	11.86	54.45		1439.2		
MATERIAL FOR SHOULDER DROP OFF									79.70				
RAMP B													
TRANSITION FROM MAINLINE TO RAMP	7986.84 SQ FT	111.82	74.54			80	1.3	30.84	141.57		887.4		
STA 0+00 TO STA 0+55	55.00	14.56	8.28			15	0.3	7.83	18.15	11.85			
STA 0+55 TO STA 12+99.18	1244.18	280.15	187.25			348	5.8	177.17	410.58				
STA 12+99.18 TO STA 13+24.18	25.00	4.07	3.76			7	0.1	3.56	8.25				
STA 13+24.18 TO STA 14+23.53	4569.9 SQ FT		42.65			46	0.8	9.49	21.78	29.63			
MATERIAL FOR SHOULDER DROP OFF									117.60				
RAMP C													
STA 0+24.62 TO STA 1+15.20	3506.92 SQ FT		32.73			35	0.6	8.60	19.73	29.63			
STA 1+15.20 TO STA 1+40.20	25.00	4.07	3.76			7	0.1	3.56	8.25				
STA 1+40.20 TO STA 10+55	914.80	205.98	137.68			256	4.3	130.27	301.88				
STA 10+55 TO STA 11+10	55.00	14.56	8.28			15	0.3	7.83	18.15	11.85			
TRANSITION FROM MAINLINE TO RAMP	11923.19 SQ FT	166.92	111.28			119	2.0	10.44	47.92		1324.8		
MATERIAL FOR SHOULDER DROP OFF									67.70				
RAMP D													
TRANSITION FROM MAINLINE TO RAMP	8089.44 SQ FT	113.25	75.50			81	1.3	12.81	58.81		898.8		
STA 0+00 TO STA 0+55	55.00	14.56	8.28			15	0.3	7.83	18.15	11.85			
STA 0+55 TO STA 15+53.32	1498.32	337.37	225.50			420	7.0	213.36	494.45				
STA 15+53.32TO STA 15+78.32	25.00	4.07	3.76			7	0.1	3.56	8.25				
STA 15+78.32 TO STA 16+94.27	5203.94 SQ FT		48.57			52	0.9	11.00	25.25	29.63			
MATERIAL FOR SHOULDER DROP OFF									126.50				
MOUNDS ROAD													
92+00.00 TO 92+50.00	50.00			11.26	17.5		0.3	2.21	5.13	13.33		114.0	
92+50.00 TO 96+38.02	388.02			87.37	155.2		2.6	17.19	39.84				
96+38.02 TO 98+86.07	248.05			74.37	119.1		2.0	10.99	37.04				
98+86.07 TO 101+16.95	230.88			69.23	110.8		1.8	10.23	34.48				
101+16.95 TO 106+25.65	508.70			190.51	284.9		4.7	22.53	75.97				
106+25.65 TO 106+75.65	50.00			18.73	28.0		0.5	2.21	7.47	13.33			147.0
BRIDGE													
109+26.25 TO 109+76.25	50.00			17.79	27.0		0.5	2.21	7.47	13.33			147.0
109+76.25 TO 114+81.50	505.25			189.22	282.9		4.7	22.38	75.45				
114+81.50 TO 117+13.93	232.43			87.05	111.6		1.9	10.29	34.71				
117+13.93 TO 119+61.98	248.05			74.37	119.1		2.0	10.99	37.04				
119+61.98 TO 123+50.00	388.02			87.37	155.2		2.6	17.19	39.84				
123+50.00 TO 124+00.00	50.00			11.26	17.5		0.3	2.21	5.13	13.33		107.0	
TOTALS		1678	1276	919	1429	1948	56.3	932	2796	220	4550	221	294

NOTE: THE QUANTITIES REFLECT THE BINDER COURSE BEING TAPERED ACCORDINGLY

PLOT DATE = 5/4/2007
FILE NAME = c:\pw_work\hdr94683\d94683ch2.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = thomesh\f