

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-03, 4-1, 4-2RS-2	PULASKI	52	19
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE (I-57 MAINLINE)

LOCATION STATION TO STATION	PREFORMED LINE 4"	THERMOPLASTIC PAVEMENT MARKING				POLYUREA PAVEMENT MARKING TYPE I - LINE 4"			SHORT TERM PAVEMENT MARKING (WHITE)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS CRYSTAL	WORK ZONE PAVEMENT MARKING REMOVAL
	SKIP DASH WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE	AIR SPEED WHITE	SOLID WHITE	SKIP DASH WHITE	SOLID YELLOW	SKIP DASH	EDGE LINE	EACH	EACH	SQ FT
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			
SOUTHBOUND MAINLINE													
687+85 TO 688+75	23	90	90						25	11	1	1	12
688+75 TO 737+40	1216	4865	4865						1327	584	61	61	637
737+40 TO 742+75	134		535	755					146	64	7	7	70
742+75 TO 769+08	658	2633	2633						718	316	33	33	345
769+08 TO 778+45	234		937						256	112	12	12	123
778+45 TO 785+00	164	655	655		12				179	79	8	8	86
785+00 TO 852+62	1691	6762	6762		12				1844	1623	85	85	1156
861+04 TO 873+18	304	1214	1214						331	291	15	15	207
873+18 TO 874+90						172	43	172	47	41			29
874+90 TO 880+17	132	527	527						144	126	7	7	90
880+17 TO 890+98						1092	270	1070	295	259			185
890+98 TO 941+00	1251	5002	5002						1364	1200	63	63	855
SB SUBTOTALS	5805	21748	23220	755	24	1264	313	1242	6674	4708	290	290	3794
NORTHBOUND MAINLINE													
687+85 TO 688+75	23	90	90						25	11	1	1	12
688+75 TO 734+14	1135	4539	4539						1238	545	57	57	594
734+14 TO 743+84	243		970						265	116	12	12	127
743+84 TO 770+00	654	2616	2616	787					713	314	33	33	342
770+00 TO 773+40	85		340						93	41	4	4	45
773+40 TO 785+00	290	1160	1160		12				316	139	15	15	162
785+00 TO 852+60	1690	6760	6760		12				1844	1622	85	85	1155
861+04 TO 873+77	318	1273	1273						347	306	16	16	218
873+77 TO 875+47						170	43	170	46	41			29
875+47 TO 880+90	136	543	543						148	130	7	7	93
880+90 TO 890+98						997	252	1019	275	242			172
890+98 TO 941+62	1266	5064	5064						1381	1215	63	63	865
NB SUBTOTALS	5839	22045	23355	787	24	1167	295	1189	6691	4722	292	292	3804
MAINLINE TOTALS	11644	43793	46575	1542	48	2431	608	2431	13365	9430	582	582	7598
		90368					5470		22795				

NOTES:
 TEMPORARY PAVEMENT MARKING QUANTITIES ARE CALCULATED FROM THE PERMANENT PAVEMENT MARKING QUANTITIES.
 SHORT TERM PAVEMENT MARKING QUANTITIES ARE CALCULATED FOR THREE APPLICATIONS.

PLOT DATE = 3/21/2007
 PLOT SCALE = 500/603
 USER NAME = thomahf