CONTRACT NO. 98829

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-13, 4-1, 4-21RS-2	PULASKI	52	20
STA.		TO STA.		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE (INTERCHANGE RAMPS/MOUNDS ROAD)

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING						POLYUREA LINE 4"		SHORT TERM PAVEMENT MARKING (YELLOW)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL
	LETTERS AND SYMBOLS	LINE 4"			LINE 12"	LINE 24"								
		SKIP DASH YELLOW	SOLID WHITE	SOLID YELLOW	SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SKIP DASH	EDGE LINE		AMBER	CRYSTAL	
	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	SQ FT
MOUNDS ROAD/RAMPS														
92+00 TO 93+84		46	368	184					17			3		6
93+84 TO 96+38			508	1016	73				23			13		8
96+38 TO 100+77			878	878		70			40	18		22		19
RAMP 'D'			2364	1480						189	50	16	34	63
RAMP 'C'			2140	1208						171				57
101+74 TO 104+00	36.4		678	452					21	9		12		10
104+00 TO 106+77			554	554					25	11		14		12
106+77 TO 109+26							500	500	23	10				11
109+26 TO 112+03			555	555					25	11		14		12
112+03 TO 114+27	36.4		672	448					20	9		12		10
114+27 TO 114+51			72						2	1		2		1
RAMP 'A'			2184	1218						175				58
RAMP 'B'			2103	1375						168	65	25	40	56
115+30 TO 119+62			864	864	89	70			39	17		6		19
119+62 TO 122+00			476	952					22			3		7
122+00 TO 124+07		52	414	207					19			3		6
SUBTOTALS	73	98	14829	11390	162	140	500	500	276	789	115	145	74	355
		26317					1000		1065			219		

NOTES:
TEMPORARY PAVEMENT MARKING QUANTITIES ARE CALCULATED FROM THE PERMANENT PAVEMENT MARKING QUANTITIES.
SHORT TERM PAVEMENT MARKING QUANTITIES ARE CALCULATED FOR TWO APPLICATIONS ON THE RAMPS.

PLOT DATE = 5/7/2007
FILE NAME = c:\pw_work\ka\d9916803\d9916803sht2.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = bhomash

PAVEMENT MARKING SCHEDULE
(INTERCHANGE RAMPS / MOUNDS ROAD)