

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-B, 4-1, 4-2RS-2	PULASKI	52	21
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE

SHEET 1 OF 2

LOCATION STATION	CLEANING UNDERDRAIN OUTLET	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	SHOULDER REMOVAL & REPLACEMENT 5"	RODENT SHIELD	REMARKS
	EACH	FOOT	EACH	FOOT	EACH	
SOUTHBOUND						
EDGE OF PAVEMENT						
688+75	1					
694+98	1					
699+50	1					
704+85		20	1	10	1	REPLACE
709+75	1					
712+55		20	1	10	1	REPLACE
715+36			1		1	
719+85	1					
729+90	1					
734+90	1					
738+85	1					
747+70	1					
764+90	1					
769+45	1					
774+90		20	1	10	1	REPLACE
799+90	1					
805+00	1					
809+85	1					
814+80		40		12		REPLACE
820+20	1					
824+80	1					
830+00	1					
850+00	1					
853+80	1					
900+00			1		1	
905+00			1		1	
910+10	1					
925+15	1					
MEDIAN						
697+30	1					
702+40	1					
707+40	1		1		1	
717+80	1					
722+49	1					
727+65	1					
737+40	1					
752+20	1					
757+45	1					
762+50	1					
767+50	1					
772+24	1				1	
777+10	1					
787+30	1					
792+50	1					
797+50	1					
807+40	1					
812+40	1					
817+40	1					
822+40	1					
827+44	1					
832+65	1					
837+80	1					
842+50	1					
852+80	1					
856+65	1					
870+12	1					
878+90	1					
892+45	1					
902+60	1					
912+60	1					
917+60	1					
922+65	1					
927+45	1					
932+50	1					
937+65	1					
SB SUBTOTALS	57	100	7	42	8	

NOTE: TRENCH BACKFILL FOR PIPE UNDERDRAINS SHALL BE INCLUDED IN THE COST OF PIPE UNDERDRAINS.

PLOT DATE = 3/21/2007
 FILE NAME = c:\projects\98829\98829.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = thomasr