F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 98963

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY J000-2A (80% FED./20% STATE)	BRIDGE X271-2A	ROADWAY FAI 57/64 90% FEDERAL 10% STATE (J000)	LIGHTING 90% FEDERAL 10% STATE Y030-1E	TRUSS SIGN PANELS 100% STATE Y002-1C
51204650	PILE SHOES	EACH	24		24			
51500100	NAME PLATES	EACH	1		1			
*5160 9000	DRILLED SHAFT IN SOIL	CU YD	68.4		68.4			
*5160 4000	DRILLED SHAFT IN ROCK	CU YD	16.3		16.3			
54001000	BOX CULVERT END SECTIONS	EACH	3	3				
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	4	4				
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	53	53				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	12			12		
542A3379	PIPE CULVERTS, CLASS A, TYPE 5 24"	FOOT	156			156		
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	43			43		
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT	115	115				
54201303	PIPE CULVERTS, TYPE 2 RCCP 48"	FOOT	253	253				
54202143	PIPE CULVERTS, TYPE 3 RCCP 48"	FOOT	166	166				
54204219	PIPE CULVERTS, TYPE 6 RCCP 24"	FOOT	227	227				
54204231	PIPE CULVERTS, TYPE 6 RCCP 36"	FOOT	480	480				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8	8				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	11	8		3		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	6	6				
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	6	6				
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTION - ELLIPTICAL EQUIVALENT ROUND-SIZE 36"	EACH	2			2		
54215547	METAL END SECTIONS 12"	EACH	25	25				
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1				
54248510	CONCRETE COLLAR	CU YD	20.24	19.8		0.44		
542JA024	PIPE CULVERTS, CLASS A 24" (JACKED)	FOOT	230	230				
5421C012	PIPE CULVERTS, CLASS C, TYPE 1, 12" (TEMPORARY)	FOOT	140	140				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	853	853				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	69	69				
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	424	424				
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	378	378				
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	134	134				
55100500	STORM SEWER REMOVAL 12"	FOOT	261	261				

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK

SCALE: DRAWN BY RLT

DATE 3-22-07 CHECKED BY MTM

© Copyright Hanson Professional Services Inc. 2007

HANSON Hanson Professional Services Inc.

03/27/2007 10:35 AM
I:\98\bos\98x2019a\Road\Sheets\60ISS00.dgn

LAYOUT	RLT	02/26/04
DRAWN	JEO	04/12/04
REVIEWED	MTM	03/22/07