

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98963				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FED./20% STATE		100%		LIGHTING 90% FEDERAL 10% STATE <i>1030-1E</i>	TRUSS SIGN PANELS 100% STATE <i>1002-1C</i>
				ROADWAY J000-2A	BRIDGE X271-2A	ROADWAY FAI 57/64 90% FEDERAL 10% STATE			
66700095	PERMANENT SURVEY MARKERS	EACH	6			6			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	9		9			
67100100	MOBILIZATION	L SUM	1	0.5		0.5			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1			1			
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300725	TEMPORARY PAINT PAVEMENT MARKING, 4" WHITE	FOOT	26625			26625			
70300825	TEMPORARY PAINT PAVEMENT MARKING, 4" YELLOW	FOOT	11520			11520			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	14025			14025			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	337.5			337.5			
72000300	SIGN PANEL, TYPE 3	SQ FT	4272			3100		1172	
72400800	REMOVE SIGN COMPLETE	SQ FT	9			9			
72400900	REMOVE SIGN PANEL	EACH	2			2			
72700100	STRUCTURAL STEEL SIGN SUPPORT, BREAKAWAY	POUND	27508			27508			
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")	FOOT	173			173			
73400100	CONCRETE FOUNDATIONS	CU YD	74			74			
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	21			21			
78000200	THERMOPLASTIC PAVEMENT MARKING LINE 4"	FOOT	16498			16498			
78000400	THERMOPLASTIC PAVEMENT MARKING LINE 6"	FOOT	232			232			
78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12"	FOOT	132			132			
78000650	THERMOPLASTIC PAVEMENT MARKING LINE 24"	FOOT	105			105			
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	21828			21828			
78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	4006			4006			
78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	281			281			
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	619	619					
78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	9949	9949					
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2534	2534					
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	531	531					
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	371	371					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	731	174		557			

* SPECIALTY ITEMS

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/27/2007 10:35 AM
 A:\98\1065\98620199\Froad\SheetAc-60\S000.dgn

LAYOUT: RLT 02/26/04
 DRAWN: LEO 04/12/04
 REVIEWED: MTM 03/22/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK

 SCALE: DATE 3-22-07
 DRAWN BY RLT
 CHECKED BY MTM