

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	033
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

PAVING SCHEDULE - GRADE SEPARATION

LOCATION	PROCESSING MODIFIED SOIL 12"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A	AGGREGATE BASE COURSE, TYPE A	AGGREGATE SURFACE COURSE, TYPE A 8"	BITUMINOUS MATERIALS (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N50	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50	HOT-MIX ASPHALT SURFACE COURSE, MIX D N50	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 12 1/4"	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2" (JOINTED)	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	PAVEMENT FABRIC	AGGREGATE SHOULDERS, TYPE B 6"	HOT-MIX ASPHALT SHOULDERS 8"	BRIDGE APPROACH PAVEMENT (SPECIAL)
	SQ YD	TON	TON	TON	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
VETERANS MEMORIAL DRIVE																
STA. 34+00.00 TO STA. 48+12.27												8997.1	8997.1			
STA. 34+00.00 TO STA. 76+40.34	27789.3	687.8														
STA. 38+45.00 TO STA. 48+12.27			852.5													
STA. 48+12.27 TO STA. 51+32.27																592.5
STA. 51+32.27 TO STA. 58+81.00			565.9													
STA. 51+32.27 TO STA. 76+40.34												13988.7	13988.7			
STA. 64+42.00 TO STA. 69+05.05			552.9													
SUBTOTAL	27789.3	687.8	1971.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	22985.8	22985.8	0.0	0.0	592.5
45TH STREET																
STA. 101+50.00 TO STA. 102+60.00							37.0									
STA. 101+50.00 TO STA. 107+73.06						874.1			214.3						1063.0	
STA. 102+60.00 TO STA. 107+73.06				1077.6				268.9								
STA. 102+60.00 TO STA. 108+72.96	2794.3	69.2														
STA. 107+73.06 TO STA. 108+77.10											771.3					
STA. 109+47.73 TO STA. 110+88.47											1101.2					
STA. 109+51.82 TO STA. 111+20.00	1203.7	29.8		71.8												
SUBTOTAL	3998.0	99.0	0.0	1149.4	0.0	874.1	37.0	268.9	214.3	0.0	1872.5	0.0	0.0	0.0	1063.0	0.0
42ND STREET																
STA. 192+15.21 TO STA. 197+85.94				574.3		951.8					1897.0					
STA. 197+85.94 TO STA. 199+60.92	1247.2	30.9														
STA. 197+85.94 TO STA. 199+64.30											1128.6					
STA. 200+34.36 TO STA. 201+70.70																
STA. 200+39.12 TO STA. 207+32.15	3535.3	87.5									2959.6					
SUBTOTAL	4782.5	118.4	0.0	574.3	0.0	951.8	0.0	0.0	0.0	1897.0	4088.2	0.0	0.0	0.0	0.0	0.0
RELOCATED GRAHAM ROAD																
STA. 200+21.50 TO STA. 207+79.46				589.4												
SUBTOTAL	0.0	0.0	0.0	589.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
ACCESS ROAD #1																
STA. 9+69.67 TO STA. 15+38.00					1846.2											
STA. 15+38.00 TO STA. 16+82.96				83.4						366.8				72.1		
SUBTOTAL	0.0	0.0	0.0	83.4	1846.2	0.0	0.0	0.0	0.0	366.8	0.0	0.0	0.0	72.1	0.0	0.0
ACCESS ROAD #2																
STA. 20+00.00 TO STA. 22+12.77				185.5		308.3				659.9						
SUBTOTAL	0.0	0.0	0.0	185.5	0.0	308.3	0.0	0.0	0.0	659.9	0.0	0.0	0.0	0.0	0.0	0.0
TEMPORARY ACCESS ROAD																
STA. 15+02.79 TO STA. 17+40.65	0.0	0.0	0.0	201.1	0.0	0.0	0.0	94.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SUBTOTAL	0.0	0.0	0.0	201.1	0.0	0.0	0.0	94	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TOTAL	36569.8	905.2	1971.3	2783.1	1846.2	2134.2	37.0	363.0	214.3	2923.7	5960.7	22985.8	22985.8	72.1	1063.0	592.5
USE TOTAL	36570	905.2	1971	2783	1846	2134	37	363	214	2924	5961	22986	22986	72	1063	593

PROTECTIVE COAT SCHEDULE - GRADE SEPARATION

LOCATION	PROTECTIVE COAT
	SQ YD
PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2" (JOINTED)	5961
PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	22986
BRIDGE APPROACH PAVEMENT (SPECIAL)	593
COMBINATION CONCRETE CURB & GUTTER B-6.06	142
COMBINATION CONCRETE CURB & GUTTER B-6.12	608
COMBINATION CONCRETE CURB & GUTTER B-6.18	2923
COMBINATION CONCRETE CURB & GUTTER B-6.24	3430
CONCRETE MEDIAN SURFACE, 4 INCH	2774
CONCRETE MEDIAN, TYPE SB-6	1278
TOTAL	40695

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
SCALE: NO SCALE DRAWN BY RL
DATE 3-22-07 CHECKED BY MTM

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/22/2007 05:35 PM
 R:\98\Drawings\98s2019\road\sheet\ac-60-sched.rvt

LAYOUT	RLT	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MTM	03/22/07