

REMOVAL SCHEDULE - RAMPS

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	PAVEMENT REMOVAL	PAVED DITCH REMOVAL	TREE REMOVAL	CONCRETE HEADWALL REMOVAL	REMOVING INLETS	CHAIN LINK FENCE REMOVAL
	SQ YD	SQ YD	FOOT	ACRE	EACH	EACH	FOOT
I-57/I-64 NORTHBOUND							
696+50 TO 711+65 (LT)	1346.7						
697+60.6 TO 706+76.3 (RT)	1221.0						
706+50.00 (RT) TO 733+92.62 (RT)							2743
706+64.5		233					
707+00 (0' RT)						1	
707+00 (108' RT)					1		
731+35 TO 759+15 (LT)	2471.1						
734+80.4 TO 756+01.7 (RT)	2828.4						
753+98.5 71.5' (RT) TO 756+01.1 83.0' (RT)		146					
755+00.5 100' (RT) TO 756+71 115.7' (RT)			171				
761+36.5 TO 765+55 (RT)	558.0						
I-57/I-64 SOUTHBOUND							
693+85 TO 713+30 (RT)	1728.9						
696+87.3 TO 709+97.5 (LT)	1746.9						
709+00.00 (LT) TO 737+00.00 (LT)							2800
717+54.63, 569.17' LT TO 722+89.43, 380.12' LT		1173					
729+35 TO 768+15 (RT)	3448.9						
732+33.8 TO 758+51.5 (LT)	3490.3						
748+81.9 106.6 (LT) TO 755+91.7 130.9 (LT)			711				
749+00 (93.6' LT)					1		
753+00.6 (71.0' LT) TO 756+51.5 (83.0' LT)		367					
RAMP A				3			
RAMP B				5			
RAMP C				1			
RAMP D				1			
TOTALS	18840	1919	882	10	2	1	5543

STRUCTURE REMOVAL SCHEDULE - GRADE SEPARATION

LOCATION	REMOVING MANHOLES	REMOVING INLETS	HEADWALL REMOVAL
	EACH	EACH	EACH
VETERANS MEMORIAL DRIVE			
STA 62+52.68 25' RT.			
STA 49+57.53 55' LT.		1	
STA 62+54.13 14' LT.		1	
STA 65+66.32 14' LT. 5130		1	
STA 67+62.45 14' LT. 5133		1	
STA 68+63.59 14' LT. 5131		1	
STA 70+65.17 14' LT. 5136		1	
STA 72+65.38 14' LT.		1	
STA 48+43.71 61' LT.			1
STA 50+79.69 48' LT.			1
STA 62+00.77 37' LT.		1	
STA 69+65.42 14' LT.		1	
SUBTOTAL	1	9	2
42ND STREET			
STA 200+40.6 11' RT.	1		
STA 201+48.8 4' RT.	1		
STA 193+57.43 35' RT.		1	
STA 193+68.28 5' LT.		1	
STA 195+13.97 112' RT.		1	
STA 195+32.46 75' RT.		1	
STA 198+15.79 35' RT.		1	
STA 198+48.14 63, RT.		1	
STA 201+51.28 35' LT.		1	
STA 201+49.39 6' LT.		1	
STA 206+01.53 15' LT.		1	
STA 206+02.57 14' LT.		1	
STA 198+47.8 24' LT.			1
STA 200+43.2 22' RT.			1
STA 192+28.24 48' RT.		1	
STA 193+64.55 64' RT.		1	
SUBTOTAL	2	10	2
SUBTOTAL	3	21	4

PAVEMENT REMOVAL SCHEDULE-GRADE SEPARATION

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL VAR. DEPTH	PAVEMENT REMOVAL
	SQ YD	SQ YD
VETERANS MEMORIAL DRIVE		
STA. 62+43.00 TO STA. 76+40.34		4157.8
SUBTOTAL		4157.8
45TH STREET		
STA 101+50.00 TO STA 102+31.16	189.2	
STA 102+31.16 TO STA 111+20.20		2322.7
SUBTOTAL	189.2	2322.7
42ND STREET		
STA. 192+15.21 TO STA. 199+56.00		2592.9
STA. 200+65.00 TO STA. 201+80.00		407.7
STA. 201+80.00 TO STA. 207+32.22		1608.1
SUBTOTAL		4608.7
TEMPORARY ACCESS ROAD		
STA. 11+00.00 TO STA. 17+40.38		1473.1
SUBTOTAL		1473.1
SUBTOTAL	189.2	12562.3
USE TOTAL	189	12562

TREE REMOVAL SCHEDULE - GRADE SEPARATION

LOCATION	TREE REMOVAL 6-15 UNITS UNIT	TREE REMOVAL ACRES
VETERANS MEMORIAL DRIVE		
RT. STA. 44+23.00 TO RT. STA. 45+43.00		0.32
RT. STA. 51+48.00 TO RT. STA. 53+00.00		0.31
RT. STA. 53+00.00 TO RT. STA. 54+96.00		0.42
RT. STA. 56+18.00 TO RT. STA. 198+00.00		1.88
LT. STA. 51+06.00 TO LT. STA. 53+00.00		0.40
LT. STA. 53+00.00 TO LT. STA. 60+81.00		2.02
LT. STA. 63+00.00 TO LT. STA. 65+00.00		0.17
LT. STA. 65+00.00 TO LT. STA. 72+43.00		0.37
RT. STA. 200+33.86	10	
LT. STA. 200+34.13	15	
LT. STA. 200+64.95	15	
LT. STA. 200+91.89	15	
LT. STA. 201+22.25	10	
SUBTOTAL	65	5.89
42ND STREET		
LT. STA. 194+23.00 TO LT. STA. 198+00.00		1.78
RT. STA. 200+74.00 TO RT. STA. 204+18.00		0.17
LT. STA. 202+96.00 TO LT. STA. 204+10.00		0.16
LT. STA. 202+64.96	15	
SUBTOTAL	15	2.11
GRAND TOTAL	80	8.00
USE TOTAL	80	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
 SCALE: NO SCALE DRAWN BY RLT
 DATE 3-22-07 CHECKED BY MTM