

TRAFFIC CONTROL - RAMPS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	065
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

LOCATION STATION TO STATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY PAINT PAVEMENT MARKING, 4" WHITE	TEMPORARY PAINT PAVEMENT MARKING, 4" YELLOW	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	EACH	EACH
STAGE 2									
I-57/I-64 SOUTHBOUND									
747+00 TO 753+00 (REM EXIST PERMANENT)			2304	1152	450				
747+00 TO 758+52						34			
747+00 TO 760+55							33		
747+00 TO 773+55	887.5								
749+63 TO 758+52									
753+00 TO 759+50 (REM EXIST PERMANENT)					271				
758+52 TO 758+15			1926						
759+50 TO 758+15 (REM EXIST PERMANENT)					649				
762+48								1	
768+15 TO 773+55			540						
IL 15 RAMP SOUTHBOUND (I-57/I-64 STATIONING)									
758+52 TO 762+48 (OUTSIDE RAMP LINE)	400		396						
759+50 TO 762+48 (INSIDE RAMP LINE)(REM EXIST PERM)					99				
760+55 TO 762+48 (INSIDE RAMP LINE)				193					
761+20 TO 762+48 (OUTSIDE RAMP LINE)(REM EXIST PERM)					43				
STAGE 3									
I-57/I-64 SOUTHBOUND									
693+85 TO 713+30 (REMOVE EXIST PERMANENT)			3890	1945	1459	49	24		
696+50 TO 749+63	5312.5								
718+95.07 TO 726+42	750							1	
726+42									
729+35 TO 747+00 (REMOVE EXIST PERMANENT)					1324	44	22		
729+35 TO 749+63			4056	2028					
747+00 TO 749+63 (REM TEMP FROM STAGE 2)					263		7		
750+39 TO 758+52 (REM TEMP FROM STAGE 2)					271				
758+39 TO 763+55			516						
760+55 TO 772+15						29			
763+55 TO 768+15 (REM TEMP FROM STAGE 2)					307				
763+55 TO 772+15			1720	860					
768+15 TO 773+55 (REM TEMP FROM STAGE 2)					180				
772+15 TO 774+35			220						
IL 15 RAMP SOUTHBOUND (I-57/I-64 STATIONING)									
780+39 TO 752+89		262.5							
750+39 TO 761+20 (OUTSIDE RAMP LINE)			1081						
752+89									1
758+39 TO 761+20 (INSIDE RAMP LINE)				281					
758+52 TO 761+20 (OUTSIDE LINE REM TEMP FROM STAGE 2)					89				
760+55 TO 761+20 (INSIDE LINE REM TEMP FROM STAGE 2)					22				
I-57/I-64 NORTHBOUND									
697+35								1	
690+30 TO 692+50			220						
692+50 TO 711+65 (REM EXIST PERMANENT)			3830	1915	1436	48	24		
697+35 TO 753+81	5650								
718+20.25								1	
718+20.25 TO 725+62	750								
731+35 TO 753+81 (REM EXIST PERMANENT)			4492	2246	1685				
731+35 TO 759+15						70	35		
753+81 TO 756+88 (REM EXIST PERMANENT)			307	307	128				
756+88 TO 759+15 (REM EXIST PERMANENT)			454	227	170				
IL 15 RAMP NORTHBOUND (I-57/I-64 STATIONING)									
753+81 TO 756+52	275								
753+81 TO 760+54 (OUTSIDE RAMP LINE REM EXIST PERM)			673		224				
756+88 TO 760+54 (INSIDE RAMP LINE REM EXIST PERM)				366	122				
STAGE 4									
I-57/I-64 SOUTHBOUND									
693+85 TO 713+30					1943	24	49		
729+35 TO 747+00						22	44		
729+35 TO 750+39					2104				
747+00 TO 760+55						33	34		
747+00 TO 773+55									
750+39 TO 758+39					533				
758+39 TO 772+15					1376				
760+55 TO 772+15							29		
772+15 TO 774+35					73				
IL 15 RAMP SOUTHBOUND (I-57/I-64 STATIONING)									
750+39 TO 762+48 (OUTSIDE RAMP LINE)					403				
758+39 TO 762+48 (INSIDE RAMP LINE)					136				
I-57/I-64 NORTHBOUND									
690+30 TO 692+50					73				
692+50 TO 711+65					1277	24	48		
731+35 TO 753+81					1497				
731+35 TO 759+15						35	70		
753+81 TO 756+88					205				
756+88 TO 759+15					227				
IL 15 RAMP NORTHBOUND (I-57/I-64 STATIONING)									
753+81 TO 760+54 (OUTSIDE RAMP LINE)					224				
756+88 TO 760+54 (INSIDE RAMP LINE)					122				
STAGE 5									
718+20.25 RT								1	
718+20.25 TO 718+57.75 RT		37.5							
725+87.50 TO 726+25 LT		37.5							
726+25 LT									
TOTALS	14025	337.5	26625	11520	19385	412	419	6	1

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/22/2007 05:15 PM
 A:\98\003\98\20\98\road\sheet\c-607-sch.dgn

LAYOUT	RLT	02/26/04
DRAWN	SEO	04/12/04
REVIEWED	MTM	03/22/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 VETERANS MEMORIAL DRIVE
 INTERCHANGE
 SECTION (41-3)HBK
 SCALE: NO SCALE DRAWN BY RLT
 DATE 3-22-07 CHECKED BY MTM