

| | | | | |
|---------------------|-----------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 57/64 | (41-3)HBK | JEFFERSON | 518 | 068 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| CONTRACT NO. 98963 | | | | |

THERMOPLASTIC PAVEMENT MARKING SCHEDULE - RAMPS

| LOCATION STATION TO STATION | THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE) | THERMOPLASTIC PAVEMENT MARKING LINE 4" (YELLOW) | THERMOPLASTIC PAVEMENT MARKING LINE 6" (WHITE) | THERMOPLASTIC PAVEMENT MARKING LINE 12" (WHITE) | THERMOPLASTIC PAVEMENT MARKING LINE 24" (WHITE) |
|--|--|---|--|---|---|
| | FOOT | FOOT | FOOT | FOOT | FOOT |
| RAMP A | | | | | |
| 300+33.9 RT 32.8 (STOP BAR) | | | | | 15.0 |
| 300+99.3 LT 20.8' TO 315+56.3 LT 16' (SOLID) | | 1457.0 | | | |
| 301+19 RT 3.1' TO 322+77.0 RT 0' (SOLID) | 2158.0 | | | | |
| RAMP B | | | | | |
| 400+00 RT 0' TO 420+67.4 RT 2.7' (SOLID) | 2067.4 | | | | |
| 406+59.6 LT 16' TO 421+07.9 LT 17.1' (SOLID) | | 1448.3 | | | |
| 421+03.7 RT 11.5' (STOP BAR) | | | | | 18.0 |
| 421+10.9 RT 8.7' (STOP BAR) | | | | | 18.0 |
| 421+26.2 (CROSS WALK) | | | 115.8 | | |
| 421+33.5 (ISLAND) | | 154.8 | | 65.9 | |
| RAMP C | | | | | |
| 500+35.3 RT 29.4' (STOP BAR) | | | | | 18.0 |
| 500+61.7 (CROSS WALK) | | | 115.7 | | |
| 500+99.7 LT 20.8' TO 515+51.1 LT 16' (SOLID) | | 1451.4 | | | |
| 501+19.0 RT 3.2' TO 528+08.8 RT 0' (SOLID) | 2689.8 | | | | |
| RAMP D | | | | | |
| 600+00 RT 0' TO 616+74.0 RT 2.7' (SOLID) | 1674.0 | | | | |
| 604+54.8 LT 16' TO 617+13.1 LT 17.2' (SOLID) | | 1258.3 | | | |
| 617+29.2 RT 33.5' (STOP BAR) | | | | | 18.0 |
| 617+33.4 RT 13.4' (STOP BAR) | | | | | 18.0 |
| 617+39.1 (ISLAND) | | 153.0 | | 65.9 | |
| RAMP IL-15 NB | | | | | |
| 756+01 TO 760+48 (SOLID) | 447.0 | | | | |
| 756+88 TO 760+48 (SOLID) | | 360.0 | | | |
| RAMP IL-15 SB | | | | | |
| 752+62.5 TO 762+15 (SOLID) | 985.5 | | | | |
| 760+55 TO 762+48 (SOLID) | | 193.0 | | | |
| SUBTOTAL | 10021.7 | 6475.8 | 231.5 | 131.8 | 105.0 |
| TOTALS | | 16,498 | 232 | 132 | 105 |

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/22/2007, 05:55 PM
 I:\98\jobs\98s20\96\road\sheet\c-610-sch.dgn

| | | |
|----------|-----|----------|
| LAYOUT | RLT | 02/26/04 |
| DRAWN | BEJ | 04/12/04 |
| REVIEWED | MTM | 03/22/07 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VETERANS MEMORIAL DRIVE
 INTERCHANGE
 SECTION (41-3)HBK
 SCALE: NO SCALE
 DATE 3-22-07

DRAWN BY RLT
 CHECKED BY MTM