F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	363
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 98963

PREFORMED PAVEMENT MARKING SCHEDULE - RAMPS

LOCATION STATION TO STATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B INLAID LINE 4" (WHITE)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B INLAID LINE 4" (YELLOW)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B INLAID LINE 8" (WHITE)	PREFORMED PLASTIC PAVEMENT MARKING TYPE B INLAID LINE 12" (WHITE)	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	EACH
I-57/I-64 NORTHBOUND					
692+50 TO 711+65 RT 47' (SOLID)		1915			24
692+50 TO 711+65 RT 59' (SKIP DASH)	478.8				
692+50 TO 699+66.3 RT 59' (SOLID)	716.3				
702+66.3 TO 706+26.3 RT 71' (SOLID)			360		
706+26.3 TO 711+65 RT 71' (SOLID)	538.7				
731+35 TO 759+15 RT 47' (SOLID)		2780			35
731+35 TO 759+15 RT 59' (SKIP DASH)	695				
731+35 TO 735+17.2 RT 71' (SOLID)	382.2				
735+17.2 TO 739+90.3 RT 71' (SOLID)			473.1		
739+90.3 TO 756+74.8 RT 71' (SKIP DASH)	421.1				22
742+40.4 TO 756+01.1 RT 83' (SOLID)	1360.8				
756+74.8 TO 759+15 RT 71' (SOLID)	240.2				
I-57/I-64 SOUTHBOUND					
693+85 TO 713+30 LT 47' (SOLID)		1945			25
693+85 TO 713+30 LT 59' (SKIP DASH)	486.3				
693+85 TO 696+87.3 LT 71' (SOLID)	302.3				
707+41 TO 709+47.5 LT 71' (SOLID)			206.5		
709+47.5 TO 713+30 LT 71' (SOLID)	382.5				
729+35 TO 772+15 LT 47' (SOLID)		4280			54
729+35 TO 772+15 LT 59' (SKIP DASH)	1070				
729+35 TO 732+33.8 LT 71' (SOLID)	298.8				
732+33.8 TO 740+26.9 LT 71' (SOLID)			793		
732+33.8 LT 72' TO 737+83.8 LT 83' (NEUTRAL ZONE)			550	281	
740+26.9 TO 759+02.2 LT 71' (SKIP DASH)	468.8				24
740+99.0 TO 758+51.8 LT 83' (SOLID)	1752.5				
759+02.2 TO 772+15 71' LT (SOLID)	1312.8				
RAMP A					
315+56.3 TO 320+27.2 LT 16' (SOLID)			470.9		
RAMP B					
400+00 TO 410+07.8					61
402+99.5 TO 406+59.6 LT 16' (SOLID)			360.1		
RAMP C					
515+51.1 TO 519+59.8 LT 16' (SOLID)			408.7		
RAMP D					
600+00 TO 606+57.4					38
600+71.1 TO 604+54.8 LT 16' (SOLID)			383.7		
SUBTOTAL	10907.1	10920.0	4006	281.0	283
TOTALS	21,827		4,006	281	283

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK

SCALE: NO SCALE — DRAWN BY RLT

DATE 3-22-07 — CHECKED BY MTM

©Copyright Hanson Professional Services Inc. 2007

HANSON
Hanson Professional Services Inc.

03/22/2007 05:35 PM
I:\98jobs\98209\road\sheets-fill-schdgn

LAYOUT	RLT	02/26/04
DRAWN	JEO	04/12/04
REVIEWED	MTM	03/22/07

11