

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	071
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 98963				

SEEDING AND EROSION CONTROL SCHEDULE - RAMPS

LOCATION STATION TO STATION	SEEDING CLASS 2 (MODIFIED)	SEEDING CLASS 4	SEEDING CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	STONE DUMPED RIPRAP, CLASS A4	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION
	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	SQ YD	POUND	SQ YD	FOOT	EACH
I-57/I-64													
691+75 (RT 13')													1
691+98 (LT 106')													1
703+00 TO 713+00 (MEDIAN)	1.8		1.8	288	216	216	3.6	3.6	355.6	540			
706+26 TO 721+55 RT	3.4		3.4	544	408	408	6.8	6.8	955.6	1020			
711+09 TO 722+59 LT		5.4	5.4	216				10.8		1620			
711+47 TO 723+24 LT	3.0		3.0	480	360	360	6	6.0	1111.1	900			
721+19 TO 735+17 RT	3.6		3.6	576	432	432	7.2	7.2	1211.1	1080			
722+96 TO 73644 LT	3.0		3.0	480	360	360	6	6.0		900			
723+69 TO 734+77 LT		3.1	3.1	124				6.2	1045.0	930			
742+12 TO 756+00 RT	2.3		2.3	368	276	276	4.6	4.6	622.2	690			
741+00 TO 75800 LT	2.5		2.5	400	300	300	5	5.0	755.6	750			
749+00 (LT 27')													1
RAMP A													
301+00 TO 322+50 RT	2.9		2.9	464	348	348	5.8	5.8	950.2	870			
301+50 (56') TO 306+50 (36') LT												480	
301+50 (45') TO 306+50 (21') RT												516	
RAMP B													
400+00 420+50 RT	3.4		3.4	544	408	408	6.8	6.8	911.1	1020	48.83		1
411+00 (LT 30')												601	
414+50 (23') TO 420+50 (42') RT												601	
414+50 (40') TO 420+50 (57') LT												601	
RAMP C													
501+00 TO 528+00 RT	4.2		4.2	672	504	504	8.4	8.4	1200.0	1260			1
503+50 (LT 84')											13.33		
501+00 (56') TO 508+50 (39') LT												728	
501+00 (45') TO 508+50 (23') RT												770	
RAMP D													
600+00 TO 616+75 RT	2.6		2.6	416	312	312	5.2	5.2	755.6	780			
611+50 (57') TO 616+50 (37') LT												501	
612+00 (23') TO 616+50 (39.5') RT												451	
VETERANS DRIVE													
43+42 (LT 78')											13.85		1
TOTALS	32.7	8.5	41.2	5572	3924	3924	66.0	82.4	9873	12360	76.0	4648	6

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

6/3/22/2007, 05:35 PM
 P:\98700s\98s2019p\road\hse\ac-613.sched.rpt

LAYOUT	RLT	02/26/04
DRAWN	JED	04/17/04
REVIEWED	MTM	03/22/07

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK SCALE: NO SCALE DATE 3-22-07
DRAWN BY RLT		CHECKED BY MTM