F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	376
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 98963

STORM SEWER SCHEDULES (A) – STRUCTURES

STR. NO.	STATION	OFFSET (FT) (SEE NOTE 2)	SIDE (LT / RT)	REFERENCE ELEVATION (FT) (SEE NOTE 2)	STRUCTURE TYPE: INLETS: TYPE A: T3 F&G (EACH)	INLETS: TYPE A: T3V F&G (EACH)	INLETS: TYPE B: T3 F&G (EACH)	INLETS: TYPE B: T3V F&G (EACH)	MANHOLES: 4' DIA T3V F&G (EACH)	MANHOLES: 5' DIA T3 F&G (EACH)	MANHOLES: 5' DIA T1 F&CL (EACH)	MANHOLES: 6' DIA T1 F&CL (EACH)	CONC. THRUST BLOCK (EACH)	PRECAST CONCRETE FLARED END SECTIONS: 12 IN (EACH)	18 IN (EACH)	24 IN (EACH)	30 IN (EACH)	36 IN (EACH)	48 IN (EACH)	BOX CULVERT END SECTIONS (EACH)	METAL END SECTION 12 IN (EACH)	INLETS TO BE ADJ. W NEW TY 3 F & G (EACH)		MANHOLE TO BE ADJ. W NEW TY1 CL (EACH)	FLUSH INLET BOX FOR MED. STD. 542546 (EACH)	NOTES REMARKS
VETERANS MEMORIAL DRIVE																										
S1	75+79.38	15.05	LT.	518.13		1																				
S2	61+00.00	80.83	LT.	491.60														1								
S3	75+79.44	16.61	RT.	518.01						1																
S4	73+29.39	18.24	LT.	513.90		1																				
S5	73+29.45	15.04	RT.	513.96		1																				
S6	72+65.57	16.98	RT.	513.38																			1			
S7	70+65.00	26.87	LT.	509.32		1																				
S8	70+64.88	17.13	RT.	509.59																			1			
S9	70+65.03	22.19	RT.	509.42		1																				
S10	68+63.00	35.05	LT.	505.94		1																				
S11	68+61.92	17.42	RT.	506.41																			1			
S12	68+63.00	32.86	RT.	505.99		1																				
S13	65+65.00	37.00	LT.	501.05		1																				
S14	65+65.55	17.43	RT.	501.53																			1			
S15	65+65.00	37.00	RT.	501.05		1																				
S16	64+55.00	37.00	LT.	500.25		1																				
S17	64+44.47	37.00	LT.	500.24	1																					
S18	64+44.47	49.96	LT.	497.48										1												
S19	64+55.00	37.00	RT.	500.25		1																				
S20	64+44.47	37.00	RT.	500.24	1																					
S21	64+44.47	66.32	RT.	496.69										1												
S22	63+15.00	37.00	LT.	501.07		1																				
S23	63+14.68	17.70	RT.	501.54																			1			
S24	63+15.00	37.00	RT.	501.07		1																				
S25	62+60.00	74.73	LT.	494.14														1								
S26	62+60.00	77.83	RT.	493.99														1								
S64	60+90.00	85.13	LT.	492.16									2								1					
S65	60+90.00	37.00	LT.	506.68		1																				
S66	60+75.00	37.00	RT.	507.21		1																				
S67	60+75.00	103.34	RT.	491.32									2								1					
S68	58+75.00	37.00	LT.	514.13		1																				
S69	58+75.00	83.67	LT.	493.25									2								1					
S70	58+75.00	37.00	RT.	514.13		1																				
S71	58+74.90	99.86	RT.	494.26									2								1					
S72	56+75.00	37.00	LT.	518.74		1																				
S73	56+75.00	91.87	LT.	494.52									2								1					
S74	56+75.00	37.00	RT.	518.74		1																				
S75	56+75.00	107.06	RT.	493.26									2								1					
S76	54+00.00	121.78	LT.	495.15													1									
S77	54+00.00	136.34	RT.	494.94													1									
S78	54+25.00	37.00	LT.	523.74		1																				
S79	54+06.00	121.93	LT.	495.53									2								1					
S80	54+25.00	37.00	RT.	523.74		1																				
S81	54+06.00	136.64	RT.	494.48									2								1					
S82	51+75.00	37.00	LT.	528.74		1																				
S83	51+75.00	128.87	LT.	499.43									2								1					
S84	51+75.00	37.00	RT.	528.74		1																				
S85	51+75.00	146.69	RT.	498.56									2								1					
S86	48+21.10	104.75	LT.	501.54												1										
S87	50+67.23	104.75	LT.	500.76												1										
S88	47+40.00	37.00	LT.	529.87		1																				
S89	47+40.00	131.06	LT.	500.53									2								1					
S90	47+40.00	37.00	RT.	529.87		1																				
S91	47+40.00	146.69	RT.	500.19									2								1					
S92	46+00.00	125.55	LT.	499.25													1									
S93	46+00.00	142.46	RT.	499.04													1									
S94	44+90.00	37.00	RT.	525.04		1																				
S95	45+45.31	141.50	RT.	498.93									2								1					
S96	44+90.00	37.00	LT.	525.04		1																				

CONTINUED ON NEXT SHEET

NOTE: 1. EXISTING STRUCTURE TO BE REMOVED. EXISTING PIPE TO BE REMOVED TO NEAREST JOINT TO ALLOW CONNECTION OF NEW PIPE. (SEE STRUCTURE REMOVAL SCHEDULE)

2. REFERENCE OFFSET/ELEVATION TO STRUCTURES W/ TYPE 3 F&G ARE TO FLOWLINE OF GUTTER.
REFERENCE OFFSET/ELEVATION TO STRUCTURES W/ TYPE 1 F & CL ARE TO CENTER OF LID.
SEE DETAILS STORM SEWER SCHEDULE (C).

3. EXISTING STRUCTURE TO REMAIN IN PLACE.

4. THE REFERNCE ELEVATION FOR END SECTIONS IS THE MIDDLE OF THE DOWNSTREAM END.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE SCHEDULE

VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK

SCALE: NO SCALE — DRAWN BY RLT

DATE 3-22-07 — CHECKED BY MTM

© Copyright Hanson Professional Services Inc. 2007
HANSON
Hanson Professional Services Inc.

03/26/2007, 07:41 AM
I:\98 jobs\98s20\9yr road\sheets\c-601-dsc.dgn

LAYOUT	RLT	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MTM	03/22/07

1