

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	079
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 98963				

STORM SEWER SCHEDULES - PIPES

PIPE/CULVERT NUMBER (P# / C#)	FROM STRUCTURE (S#)	INVERT ELEV. (FT)	TO STRUCTURE (S#)	INVERT ELEV. (FT)	PIPE SLOPE %	STORM SEWERS, CLASS A, TYPE 1					PIPE CULVERTS					PIPE CULVERTS CL A 24" (JACKED) (FT)	PIPE DRAINS 12" (FT)	CONCRETE COLLAR (CU YDS)	REINF. BARS (POUND)	PRE. CONC. BOX CULV. 4' X 2' (FT)	PRE. CONC. BOX CULV. 6' X 3' (FT)	TRENCH BACKFILL (CU YDS)	NOTES/REMARKS					
						TYPE 2 RCCP					TYPE 3 RCCP													TYPE 6 RCCP				
						12" DIA (FT)	15" DIA (FT)	18" DIA (FT)	24" DIA (FT)	30" DIA (FT)	36" DIA (FT)	48" DIA (FT)	48" DIA (FT)	24" DIA (FT)	36" DIA (FT)									36" DIA (FT)	48" DIA (FT)	48" DIA (FT)	24" DIA (FT)	36" DIA (FT)
VETERANS MEMORIAL DRIVE																												
C1	S500	500.73	S501	498.00	1.46											183.0						25.6						
C2	S110	497.99	S111	497.87	0.10						115.0											42.1						
C4	S92	499.25	S93	498.31	0.38																	42.1						
C5	S76	497.50	S77	497.30	0.09																	42.1						
C6	S2	491.60	S124	491.43	0.10																	63.7						
P1	S1	515.42	S3	515.10	1.00	28.2																18.3						
P2	S3	514.46	S138	511.51	2.12																		NOTE 1					
P3	S4	510.27	S5	510.00	0.80	30.4																4.0						
P4	S5	509.28	S6	509.00	0.44	61.9																8.2						
P5	S7	505.63	S136	505.53	0.80		9.7															1.3						
P6	S136	505.53	S8	504.76	2.40																		NOTE 1					
P7	S10	502.22	S131	502.05	0.80		18.4															5.7						
P8	S131	502.05	S11	501.08	3.03																	2.7	NOTE 1					
P9	S13	498.39	S130	498.29	0.44		20.5																NOTE 1					
P10	S130	498.29	S14	497.06	3.87																							
P11	S16	497.58	S17	497.54	0.80	8.5																2.0						
P12	S17	497.54	S18	497.48	0.47	6.2																0.7						
P13	S19	497.59	S20	497.50	0.80	8.6																1.1						
P14	S20	497.50	S21	496.69	0.48	22.7																2.4						
P15	S22	498.24	S23	498.00	0.44	51.2																6.8						
P16	S24	498.59	S23	498.50	0.44	15.8																2.1						
P39	S68	511.13	S69	493.25	50.00												48.5	0.9	84			0.4						
P40	S70	511.13	S71	492.29	50.00												64.9	0.9	84			4.1						
P41	S72	515.74	S73	494.26	50.00												58.2	1.2	112			0.4						
P42	S74	515.74	S75	493.51	50.00												74.6	1.2	112			2.3						
P43	S78	520.74	S79	498.00	33.33												90.1	1.5	140			0.4						
P44	S80	520.74	S81	497.80	33.33												105.0	1.5	140			2.4						
P45	S82	525.74	S83	500.12	33.33												96.3	1.5	140			0.4						
P46	S84	525.74	S85	498.88	33.33												113.8	1.5	140			2.2						
P47	S88	526.87	S89	500.53	33.33												97.0	1.5	140			0.4						
P48	S90	526.87	S91	499.89	33.33												113.0	1.5	140			2.2						
P49	S94	522.04	S95	500.23	33.33												122.1	1.5	140			2.2						
P50	S96	522.04	S97	500.38	33.33												96.7	1.5	140			0.3						
P51	S98	518.04	S99	499.88	50.00												63.2	0.9	84			2.3						
P52	S100	518.04	S101	501.69	50.00												45.1	0.9	84			0.3						
P53	S102	511.92	S103	501.03	33.33												59.7	0.3	28			2.3						
P54	S104	511.92	S105	501.16	33.33												45.2	0.3	28			0.3						
P55	S106	503.62	S107	499.09	33.33												39.6					2.2						
P56	S108	503.62	S109	499.45	33.33												24.4					0.4						
P57	S112	500.09	S113	500.05	0.44	7.9																1.0						
P58	S126	499.46	S114	499.25	0.44	45.9																9.9						
P59	S114	498.41	S115	498.20	0.26		73.7															26.4						
P60	S115	497.92	S116	497.84	0.21			36.0														17.6						
P100	S123	500.24	S115	500.00	0.44	51.6																8.9						
P101	S125	501.04	S114	500.84	0.40	45.8																6.0						
P102	S113	499.74	S126	499.70	0.44	8.1																0.9						
P104	S66	504.21	S67	491.32	33.33																	2.2						
P105	S65	503.68	S64	492.16	33.33												66.0	0.6	56			0.3						
P106	S128	497.77	S16	497.68	0.80	18.0											47.6	0.3	28			2.9						
P107	S129	498.16	S19	498.00	0.80	18.0																2.4						
P108	S15	498.34	S14	498.25	0.44	16.0																2.1						

CONTINUED ON NEXT SHEET
 NOTE 1 - EXISTING PIPE TO REMAIN IN PLACE, CONTRACTOR SHALL CLEAN PIPE IF NECESSARY.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION DRAINAGE SCHEDULE VETERANS MEMORIAL DRIVE INTERCHANGE SECTION (41-3)HBK SCALE: NO SCALE DATE 3-22-07
NAME	DATE	
		DRAWN BY RL CHECKED BY MTM



Copyright Hanson Professional Services Inc. 2007
 Hanson Professional Services Inc.
 03/21/2007 07:41 AM
 I:\987\060520\98963\road\sheet\c-604-disc.dgn

DATE	BY
02/26/04	RLT
04/12/04	RLT
02/22/01	MTM