

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	225
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LIGHTING BILL OF MATERIALS

PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITIES
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81021550	CONDUIT, AUGURED, 2" DIA., PVC	FOOT	755
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10,915
81603035	UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 6 GROUND, (XLP TYPE-USE) 1" DIA. POLYETHYLENE	FOOT	12,035
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 400 WATT	EACH	41
82500540	LIGHTING CONTROLLER TYPE CB-RCS 100 AMP - 480 VOLT	EACH	1
83010600	LIGHT POLE, ALUMINUM, 50 FT. M.H. 15 FT. MAST ARM	EACH	41
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	287
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	41

PLOT DATE = 01/11/2007 09:05 AM
 FILE NAME = I:\SIB\982019\T001 RAMPS\98050605.mxd
 PLOT SCALE = 50.0000 / IN.
 USER NAME = KAY

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION LIGHTING BILL OF MATERIALS SCALE: VERT. NONE HORIZ. DATE DRAWN BY CHECKED BY
NAME	DATE	