

**SUMMARY OF QUANTITIES**

CONTRACT NO. 99300

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9550	07-00083-00-RP	SALINE	21	3
CITY OF HARRISBURG		SLOAN STREET		

CODE NO.	PAY ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	700
20800150	TRENCH BACKFILL	CU YD	65
*25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.6
25100630	EROSION CONTROL BLANKET	SQ YD	2900
*28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
28000300	TEMPORARY DITCH CHECKS	EACH	3
28000400	PERIMETER EROSION BARRIER	FOOT	300
28000500	INLET AND PIPE PROTECTION	EACH	13
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	125
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	400
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	910
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	200
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	300
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	300
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	232
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2980
*44000080	HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILLING)	SQ YD	2050
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	85
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1540
44000600	SIDEWALK REMOVAL	SQ FT	2980
54001000	BOX CULVERT END SECTIONS	EACH	2
54010805	PRECAST CONCRETE BOX CULVERT 8'X5'	FOOT	34
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	115
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	25
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	78
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	26
55100500	STORM SEWER REMOVAL 12"	FOOT	35
55101200	STORM SEWER REMOVAL 24"	FOOT	63
*56108710 Δ	TAPPING VALVES AND SLEEVES 4"	EACH	1
*56108800 Δ	TAPPING VALVES AND SLEEVES 6"	EACH	1
*56108900 Δ	TAPPING VALVES AND SLEEVES 8"	EACH	2
*56200200 Δ	WATER SERVICE LINE 3/4"	FOOT	240
*56400820 Δ	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1
*60240200	INLETS, TYPE A, SPECIAL	EACH	1
*60243300	INLETS, SPECIAL, TYPE 3, 5'	EACH	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	164
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1387
67100100	MOBILIZATION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	6

CODE NO.	PAY ITEM	UNIT	QUANTITY
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	26
78000100 Δ	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	1600
78000200 Δ	THERMOPLASTIC PAVEMENT MARKING LINE - 4"	FOOT	1900
78000600 Δ	THERMOPLASTIC PAVEMENT MARKING LINE - 12"	FOOT	140
*XX000679 Δ	CUT AND CAP EXISTING WATERMAIN	EACH	4
*XX002809 Δ	WATERMAIN, 8" PVC	FOOT	1170
*XX005890 Δ	DETECTION WIRE	FOOT	1210
*XX006035 Δ	CASING PIPE 16"	FOOT	30
*XX006960 Δ	WATER MAIN, 8" YELOMINE PVC DIRECTIONAL BORING	FOOT	40

Δ SPECIALTY ITEMS

**SURVEY CONTROL**

POINT DESCRIPTION	NORTHING	EASTING	ELEV
STA 13+10.12 CL	387,623.301	925,799.935	
STA 17+92.02 CL POT	387,609.148	926,281.622	
STA 25+00.00 CL	387,587.575	926,989.273	
STL PIN W/IDOT CAP	387,671.084	925,869.873	362.14
STA 25+00.00 CL	387,591.190	926,074.682	362.08
STA 25+00.00 CL	387,722.218	926,544.015	362.86

12 Apr 2007 - 10:14am X:\2007\07016\AC\plans\3-5summary and schedules.dwg