

TRANSPORTATION BULLETIN



Illinois Department of Transportation

ADDENDUM NO. 1

Dated: June 8, 2007

For: Transportation Bulletin

Letting Date: June 15, 2007

Volume 10 No. 19r Dated: May 11, 2007, Revised June 5, 2007

Item No. 15A – Entrance Road Relocation and Parking Lot Expansion.

Quad City International Airport

Moline, Illinois

Rock Island County

IL Project No.: MLI-3673

Federal Project No.: 3-17-0068-XX

Contract No.: QU004

REASON FOR ADDENDUM:

An incorrect pay item (Item AR110202 – 2" PVC Duct, Direct Bury) was shown in the Summary of Quantities on Sheet 2 of the Plans, on page 20 of the Special Provisions, and on the Schedule of Prices in the Proposal. All have been revised to show the correct pay item (AR110200 1-1/4" PVC Duct, Direct Bury).

The method of measurement for cable has been revised on Page 19 of the Special Provisions.

TO ALL PLAN HOLDERS:

Replace Sheet 2 of the Plans with Attached Sheet 2.

Replace the Schedule of Prices with the Attached Schedule of Prices.

Revise Page 19, Section 108-4.1 and 4.2 of The Special Provisions to Read:

108-4.1

108-4.2

Delete: Entire Sections.

Add: The Footage of cable to be paid for shall be the number of linear feet of cable installed in conduit, measured in place, complete, ready for operation and accepted as satisfactory.

Revise Page 20, Section 110-5.1 to Read:

110-5.1

Add: Payment will be made under:

Item AR110200	1-1/4" PVC Duct, Direct Bury – per linear foot
Item AR110201	1" PVC Duct, Direct Bury – per linear foot
Item AR110610	Electrical Handhole – per each
Item AR110906	Remove Electrical Handhole – per each

STATE JOB #- - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 1
 RUN DATE - 06/07/07
 RUN TIME - 214506

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
ROCK ISLAND	161	02	QUAD-CITY INTERNATIONAL	3-17-0068-XX	ML-I -3673

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR106512	TYPE A AREA LGT POLE W/2 FIXTURES	EACH	3.000 X		=		
AR106521	TYPE B AREA LGT POLE W/1 FIXTURE	EACH	8.000 X		=		
AR106531	TYPE C AREA LGT POLE W/1 FIXTURE	EACH	2.000 X		=		
AR106641	TYPE D ASSEMBLY-1 FIXTURE	EACH	6.000 X		=		
AR106965	RELOCATE LIGHT POLE & FIXTURE	EACH	9.000 X		=		
AR108406	1/C #6 600 V UG CABLE	L.F.	6,480.000 X		=		
AR108410	1/C #10 600 V UG CABLE	L.F.	12,000.000 X		=		
AR108800	CONTROL CABLE	L.F.	450.000 X		=		
AR110200	1-1/4" PVC DUCT, DIRECT BURY	L.F.	1,000.000 X		=		
AR110201	1" PVC DUCT, DIRECT BURY	L.F.	3,350.000 X		=		
AR110610	ELECTRICAL HANDHOLE	EACH	10.000 X		=		
AR110906	REMOVE ELECTRICAL HANDHOLE	EACH	2.000 X		=		
AR150530	TRAFFIC MAINTENANCE	L.S.	1.000 X		=		
AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EACH	38.000 X		=		
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	764.000 X		=		

QUAD-CITY INTERNATIONAL
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 06/07/07
 RUN TIME - 214506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR152440	BORROW EXCAVATION	C.Y.	30,137.000	X	=		
AR156500	TEMPORARY EROSION CONTROL	L.S.	1.000	X	=		
AR156513	SEPARATION FABRIC	S.Y.	23,570.000	X	=		
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	5,789.000	X	=		
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	570.000	X	=		
AR501506	6" PCC PAVEMENT	S.Y.	15,925.000	X	=		
AR501508	8" PCC PAVEMENT	S.Y.	6,574.000	X	=		
AR501530	PCC TEST BATCH	EACH	1.000	X	=		
AR501604	4" PCC SIDEWALK	S.F.	6,482.000	X	=		
AR501690	PCC SIDEWALK REMOVAL	S.F.	2,526.000	X	=		
AR501900	REMOVE PCC PAVEMENT	S.Y.	8,348.000	X	=		
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	4,562.000	X	=		
AR620900	PAVEMENT MARKING REMOVAL	S.F.	438.000	X	=		
AR701200	SLOTTED DRAIN	L.F.	1,047.000	X	=		
AR701206	6" CMP	L.F.	20.000	X	=		

QUAD-CITY INTERNATIONAL
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 06/07/07
 RUN TIME - 214506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR701224	24" CMP	L.F.	58.000	X		=	
AR701412	12" RCP, CLASS III	L.F.	345.000	X		=	
AR701415	15" RCP, CLASS III	L.F.	113.000	X		=	
AR701418	18" RCP, CLASS III	L.F.	20.000	X		=	
AR701424	24" RCP, CLASS III	L.F.	628.000	X		=	
AR701430	30" RCP, CLASS III	L.F.	186.000	X		=	
AR701436	36" RCP, CLASS III	L.F.	136.000	X		=	
AR701900	REMOVE PIPE	L.F.	1,543.000	X		=	
AR705504	4" PERFORATED UNDERDRAIN	L.F.	3,850.000	X		=	
AR751411	INLET-TYPE A	EACH	11.000	X		=	
AR751412	INLET-TYPE B	EACH	4.000	X		=	
AR751415	INLET-SPECIAL	EACH	1.000	X		=	
AR751540	MANHOLE 4'	EACH	3.000	X		=	
AR751550	MANHOLE 5'	EACH	3.000	X		=	
AR751900	REMOVE INLET	EACH	21.000	X		=	

QUAD-CITY INTERNATIONAL
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 4
 RUN DATE - 06/07/07
 RUN TIME - 214506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR751903	REMOVE MANHOLE	EACH	8.000 X		=		
AR751983	RECONSTRUCT MANHOLE	EACH	3.000 X		=		
AR752206	METAL END SECTION 6"	EACH	1.000 X		=		
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	1.000 X		=		
AR760506	6" DUCTILE IRON WATER MAIN	L.F.	87.000 X		=		
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	80.000 X		=		
AR760516	16" DUCTILE IRON WATER MAIN	L.F.	185.000 X		=		
AR760800	FIRE HYDRANT	EACH	1.000 X		=		
AR760905	REMOVE FIRE HYDRANT	EACH	2.000 X		=		
AR801552	6" WATER VALVE	EACH	1.000 X		=		
AR801553	8" WATER VALVE	EACH	1.000 X		=		
AR801554	16" WATER VALVE	EACH	1.000 X		=		
AR801555	ABANDON WATERMAIN	L.S.	1.000 X		=		
AR801556	REMOVE GUARD RAIL	L.F.	1,253.000 X		=		
AR801557	REMOVE AND REERECT STEEL PLATE BE	L.F.	748.000 X		=		

QUAD-CITY INTERNATIONAL
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 5
 RUN DATE - 06/07/07
 RUN TIME - 214506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR801558	SIGN BRIDGE	EACH	1.000 X		=		
AR801559	REMOVE SIGN BRIDGE	EACH	1.000 X		=		
AR801560	SITE SIGNS	EACH	31.000 X		=		
AR801561	RETAINING WALL SIGN	EACH	3.000 X		=		
AR801562	RETAINING WALL	L.F.	437.000 X		=		
AR801563	RECONSTRUCT TELEPHONE VAULT	EACH	1.000 X		=		
AR801564	RELOCATE TICKET DISPENSER & GATE	EACH	1.000 X		=		
AR801565	DETECTOR LOOP, TYPE 1	L.F.	122.000 X		=		
AR801566	RELOCATE SIGN BRIDGE LIGHTING	L.S.	1.000 X		=		
AR801567	ABANDON STORM SEWER	L.S.	1.000 X		=		
AR901510	SEEDING	ACRE	1.840 X		=		
AR908510	MULCHING	ACRE	1.840 X		=		
AR910400	GUARD RAIL	L.F.	960.000 X		=		
AR910410	PARKING BLOCK	EACH	12.000 X		=		
AR910420	BOLLARD	EACH	3.000 X		=		

QUAD-CITY INTERNATIONAL
ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - QU004

ECMS002 DTGECM03 ECMR003 PAGE 6
RUN DATE - 06/07/07
RUN TIME - 214506

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR910976	RELOCATE ROADWAY SIGNS	L.S.	1.000 X			=	
				TOTAL \$			

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.