

SD047

DATE	REVISION	BY

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION- BASE BID	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5KV UG CABLE IN UD	L.F.	1880	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	66	
AR125415	MITL - BASE MOUNTED	EA.	15	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EA.	1	
AR125449	TAXI GUIDANCE SIGN, 9 CHARACTER	EA.	1	
AR125510	MIRL, BASE MOUNTED	EA.	4	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA.	11	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EA.	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150535	RUNWAY CLOSURE MARKING	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	259	
AR152440	BORROW EXCAVATION	C.Y.	1,933	
AR152480	SHOULDER ADJUSTMENT	S.Y.	59	
AR155540	BY - PRODUCT LIME	TON	89	
AR155612	SOIL PROCESSING - 12"	S.Y.	3,202	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	966	
AR401611	BIT. SURFACE COURSE-METHOD I	TON	32	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	263	
AR401910	REMOVE & REPLACE BITUMINOUS PAVEMENT	S.Y.	63	
AR501506	6" PCC PAVEMENT	S.Y.	1,009	
AR501510	10" PCC PAVEMENT	S.Y.	328	
AR501512	12" PCC PAVEMENT	S.Y.	2,736	
AR501530	PCC TEST BATCH	EA.	1	
AR501655	PCC PAVEMENT SAWING	L.F.	192	
AR501900	REMOVE PCC PAVEMENT	S.Y.	1,626	
AR603510	BITUMINOUS TACK COAT	GAL.	40	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	5,262	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	4,706	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	555	
AR701530	30" RCP, CLASS IV	L.F.	152	
AR705411	POROUS BACKFILL NO. 1	C.Y.	74	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	678	
AR705630	UNDERDRAIN INSPECTION HOLE	EA.	4	
AR752430	PRECAST REINFORCED CONC. FES 30"	EA.	2	
AR800409	RELOCATE EXISTING 2 MODULE SIGN	EA.	1	
AR901510	SEEDING	AC.	0.47	
AR908510	MULCHING	AC.	0.47	

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION- ALTERNATE 1	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR800430	LIGHTED RUNWAY CLOSURE MARKER	L.S.	1	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT PREPARATION PLAN
5	PROPOSED CONSTRUCTION PLAN
6	PROPOSED TYPICAL SECTIONS
7	PROPOSED GEOMETRICS PLAN
8	PROPOSED STAKING PLAN
9	PROPOSED STAKING PLAN NOTES
10	PROPOSED JOINTING PLAN
11	PROPOSED JOINTING DETAILS
12	PROPOSED TAXIWAY "B4" PLAN AND PROFILE STA. 901+00 TO STA. 906+00
13	PROPOSED TAXIWAY "A4" PLAN AND PROFILE STA. 906+00 TO STA. 911+00
14	PROPOSED DRAINAGE PLAN
15	EXISTING ELECTRICAL PLAN
16	PROPOSED ELECTRICAL PLAN
17	PROPOSED ELECTRICAL DETAILS AND NOTES
18	PROPOSED ELECTRICAL DETAILS AND NOTES
19	PROPOSED ELECTRICAL DETAILS
20	PROPOSED ELECTRICAL DETAILS
21	PROPOSED ELECTRICAL NOTES
22	PROPOSED ELECTRICAL NOTES
23	PROPOSED MARKING PLAN
24	PROPOSED MARKING PLAN
25	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A4" STA. 906+25 TO STA. 906+50
26	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A4" STA. 906+75 TO STA. 907+25
27	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A4" STA. 907+50 TO STA. 907+86.75
28	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A4" STA. 908+00 TO STA. 908+50
29	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A4" STA. 908+75 TO STA. 909+25
30	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A" STA. 303+50 TO STA. 304+00
31	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A" STA. 304+25 TO STA. 304+75
32	PROPOSED CROSS-SECTIONS FOR TAXIWAY "A" STA. 305+00 TO STA. 305+25

SAINT LOUIS DOWNTOWN AIRPORT  
A Division of Bi-State Development Agency



FILE PROJECT NO. 84507TXD_0800	DATE 1/11/07
FILE NAME R-002FLP.DWG	DATE 1/11/07
SCALE NOT TO SCALE	DATE 01/26/07
DATE 1/11/07	
LAYOUT J.A.C.	
DRAWN B.A.K.	
REVIEWED C.A.H.	

**HANSON**  
Hanson Professional Services Inc.  
4227 Earth City Expressway, Suite 130  
St. Louis, MO 63046-1308  
Officers Nationwide

CONSTRUCT TAXIWAY "A4"  
SUMMARY OF QUANTITIES AND INDEX TO SHEETS

APR 18, 2007 11:56 AM BAK  
I:\AIRPORTS\ST. LOUIS DOWNTOWN\84507TXD\AIRPORT\SHEETS\R-002FLP.DWG - FLAP