


Sheet List Table	
Sheet Number	Sheet Title
01	COVER SHEET
02	INDEX TO SHEETS & SUMMARY OF QUANTITIES
03	SITE PLAN
04	GENERAL NOTES & DETAILS
05	HORIZONTAL & VERTICAL CONTROLS
06	CONSTRUCTION ACTIVITY PLAN PHASE 1
07	CONSTRUCTION ACTIVITY PLAN PHASE 2
08	CONSTRUCTION ACTIVITY PLAN PHASE 3 OVERVIEW
09	CONSTRUCTION ACTIVITY PLAN PHASE 3 DETAILED VIEW
10	CONSTRUCTION ACTIVITY GENERAL NOTES & DETAILS
11	EXISTING CONDITIONS & REMOVALS - APRON
12	EXISTING CONDITIONS & REMOVALS - TAXIWAYS
13	PAVEMENT REMOVAL DETAILS SHEET 1
14	PAVEMENT REMOVAL DETAILS SHEET 2
15	PAVEMENT REMOVAL DETAILS SHEET 3
16	PROJECT IMPROVEMENTS - APRON
17	PROJECT IMPROVEMENTS - TAXIWAYS
18	PROJECT IMPROVEMENTS - TAXI AND LIMO
19	NEW TYPICAL SECTIONS - APRON
20	NEW TYPICAL SECTIONS - TAXIWAYS
21	JOINTING PLAN - APRON
22	JOINTING PLAN - TAXIWAYS
23	NEW JOINTING DETAILS
24	PAVING & MISCELLANEOUS DETAILS
25	PAVING AND MISCELLANEOUS DETAILS SHEET 2
26	PAVING AT STRUCTURES
27	SIDEWALK AND CURB DETAILS
28	STAKING PLAN 1 - APRON
29	STAKING PLAN 2 - TAXIWAYS
30	SIDEWALK AND CURB PLAN
31	UNDERDRAIN PLAN
32	UNDERDRAIN DETAILS
33	MARKING AND GROUND ROD PLAN
34	TERMINAL AREA MARKING PLAN
35	FENCING PLAN
36	FENCE DETAILS
37	ELECTRICAL GATE DETAILS SHEET 1
38	ELECTRICAL GATE DETAILS SHEET 2
39	ELECTRICAL GATE DETAILS SHEET 3
40	ELECTRICAL ADJUSTMENTS & DETAILS 1
41	ELECTRICAL ADJUSTMENTS & DETAILS 2
42	GRADING - TURFING & EROSION CONTROL PLAN
43	EROSION CONTROL DETAILS
44	INDEX TO CROSS SECTIONS
45	CROSS SECTIONS - APRON - 1
46	CROSS SECTIONS - APRON - 2
47	CROSS SECTIONS - TXY A6 - 1
48	CROSS SECTIONS - TXY A6 - 2
49	CROSS SECTIONS - TXY A7 - 1

Summary of Quantities

Item Number	Description	UNIT	QUANTITY
AR110949	Adjust Cable Marker	EA	12
AR125941	Adjust Stake Mounted Light	EA	12
AR125942	Adjust Base Mounted Light	EA	8
AR125944	Adjust Taxi Guidance Sign	EA	2
AR150510	Engineer's Field Office	LS	1
AR152410	Unclassified Excavation	CY	800
AR152480	Shoulder Adjustment	SY	5,370
AR156510	Silt Fence	LF	1,925
AR156513	Separation Fabric	SY	6,740
AR156520	Inlet Protection	EA	6
AR162408	Class E Fence, Vinyl-8'	LF	835
AR162720	Electric Gate - 20'	EA	1
AR162900	Remove Class E Fence	LF	830
AR162908	Remove Electric Gate	EA	1
AR163000	Temporary Construction Fence	LF	360
AR201661	Clean and Seal Bituminous Cracks	LF	600
AR209608	Crushed Aggregate Base Course - 8"	SY	6,740
AR302900	Remove 4" ATPS	SY	6,105
AR401610	Bituminous Surface Course	TON	740
AR401655	Butt Joint Construction	SY	1,110
AR401900	Remove Bituminous Pavement	SY	2,390
AR501508	8" PCC Pavement	SY	6,105
AR501509	9" PCC Pavement	SY	6,250
AR501515	15" PCC Pavement	SY	170
AR501530	PCC Test Batch	EA	1
AR501550	PCC Pavement Milling	SY	6,250
AR501604	4" PCC Sidewalk	SF	900
AR501690	PCC Sidewalk Removal	SF	900
AR501908	8" PCC Pavement Removal	SY	6,105
AR501915	15" PCC Pavement Removal	SY	170
AR510515	Ground Rod	EA	5
AR510905	Remove Ground Rod	EA	5
AR602510	Bituminous Prime Coat	GAL	180
AR603510	Bituminous Tack Coat	GAL	890
AR620510	Pavement Marking	SF	5,425
AR705524	4" Perforated Underdrain w/Sock	LF	480
AR705944	Adjust Underdrain Cleanout	EA	1
AR751944	Adjust Manhole - Pavement	EA	2
AR754210	Concrete Curb	LF	170
AR754410	Comb. Concrete Curb & Gutter	LF	115
AR754900	Remove Concrete Curb	LF	240
AR754904	Remove Comb. Concrete Curb & Gutter	LF	115
AR800215	Remove Bollard	EA	5
AR800281	Liquid Bond Breaker	SY	6,250
AR800283	Clean and Repaint Bollard	EA	12
AR800284	Remove, Repaint and Reinstall Guardrail	LF	150
AR800285	Remove Parking Block	EA	15
AR901510	Seeding	AC	1.5
AR904510	Sodding	SY	970
AR908510	Mulching	AC	1.5
AR910410	Parking Block	EA	15
AR910420	Bollard	EA	5

REVISIONS		
NUMBER	BY	DATE



UNIVERSITY OF ILLINOIS
 WILLARD AIRPORT

REHABILITATE AIR CARRIER RAMP, PHASE 2
 INDEX TO SHEETS
 &
 SUMMARY OF QUANTITIES

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 984-000613



DESIGN BY: SMS
 DRAWN BY: CMT
 CHECKED BY: *SMS*
 APPROVED BY: *SMS*
 DATE: 4/27/2007
 JOB No: 0305903

CMI-3663
 3-17-0016-XX