	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT		STATE URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 7.5% STATE 2.5% VILLAGE 0021	TRAFFIC EVP 100% VILLAGE 0021	BIKE PATH 90% FEDERAL 10% VILLAGE 0028	FIRE HYDRANT 100% VILLAGE 0043	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	42	42					
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	734		734				
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	32		32				
*	81028230	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA.	FOOT	68		68				
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	363		363				
*	81400100	HANDHOLE	EACH	4		4				
*	81400200	HEAVY-DUTY HANDHOLE	EACH	5		5				
*	81400300	DOUBLE HANDHOLE	EACH	1		1				
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	197		197				
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	528		528				
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1089		1089				
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1923		1923				
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1823		1823				
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	33		33				

	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT		STATE URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 7.5% STATE 2.5% VILLAGE 0021	TRAFFIC EVP 100% VILLAGE 0021	BIKE PATH 90% FEDERAL 10% VILLAGE 0028	FIRE HYDRANT 100% VILLAGE 0043	
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	616		616				
*	87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	2		2				
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1				
*	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1				
*	87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1		1				
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	53		53				
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5		5				
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3				
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7		7				
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2				
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12		12				
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8				
*	88600100	DETECTOR LOOP, TYPE I	FOOT	937		937				
*	88700200	LIGHT DETECTOR	EACH	2			2			

FILE NAME = c:\pw_work\pwidot\mlayja\dms92836\P156809-Design.dgn	USER NAME = mlayja	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/29/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US RTE 30 (LINCOLN HWY) AT CENTRAL AVE.
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 4 OF 5 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	23-N-4	COOK	68	7
		CONTRACT NO. 60L21		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

* SPECIALTY ITEMS