

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITIES	SAFETY						CODE NO	ITEM	UNIT	90% FED. 10% STATE TOTAL QUANTITIES	SAFETY						
				0021										0021						
81603051	UNIT DUCT, 600V. WITH 3-1/2 NO. 6, 1/2 NO. 8 GROUND, (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	2692	2692						* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	208	208						
20200100	EARTH EXCAVATION	CU YD	150	150						* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	11	11						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	214	214						* 83007500	LIGHT POLE, ALUMINUM, 35 FT. M.H., 12 FT. MAST ARM	EACH	11	11						
20400800	FURNISHED EXCAVATION	CU YD	128	128						* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	207	207						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	90	90						* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	108	108						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2						* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2	2						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2						* 84200804	REMOVAL OF POLE FOUNDATION	EACH	23	23						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2						* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	16	16						
25200110	SODDING, SALT TOLERANT	SO YD	90	90						* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1						
28000400	PERIMETER EROSION BARRIER	FOOT	360	360						* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	250	250						
28000510	INLET FILTERS	EACH	35	35						* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	254	254						
42001300	PROTECTIVE COAT	SO YD	4800	4800						* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	60	60						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	42400	42400						* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	60	60						
42400800	DETECTABLE WARNINGS	SO FT	200	200						* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	194	194						
44000100	PAVEMENT REMOVAL	SO YD	2565	2565						* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1	1						
44000600	SIDEWALK REMOVAL	SO FT	7485	7485						* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	1						
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1000	1000						* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8						
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2						
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	9	9						* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1	1						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1						
67100100	MOBILIZATION	L SUM	1	1						* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1						
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	3	3						
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1						* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						* 89502376	REBUILD EXISTING HANDHOLE	EACH	4	4						
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1						
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	395	395						* X0325924	CLEAN, RELAMP AND MAINTENANCE OF EXISTING LUMINAIRE	EACH	50	50						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	345	345						Δ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1750	1750						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	521	521						* X8100863	INTERCEPT EXISTING CONDUIT	EACH	3	3						
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	205	205																
78300100	PAVEMENT MARKING REMOVAL	SO FT	1140	1140																
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	37	37																

* SPECIALTY ITEMS
Δ NON-PARTICIPATING ITEMS
(100% STATE)

Rev.