

SUMMARY OF QUANTITIES

Specialty Item	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0014
					SN 016-0963
					100% STATE
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	28	28
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3488	3488
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36.4	36.4
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1979	1979
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	60	60
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	84	84
*	78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	20	20
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	29	29
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	76.7	76.7
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	33	33
	Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	22	22
	Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	124	124
	Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	130	130
	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	92	92
	Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	4	4
	Z0021922	SILICONE JOINT SEALER	FOOT	22	22
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	70.2	70.2
	Z0041895	POLYMER CONCRETE	CU FT	10.4	10.4
	Z0062456	TEMPORARY PAVEMENT	SQ YD	151.1	151.1
*	A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2
*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
	X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	10463	10463
*	Specialty Item				

3/27/2012 1:39:12 PM G:\ENR\B6-5329-02 01 Various Structure TASK ORDERS\TK-11.NorJan\CA0\Structure\Shd\DI60M71-Sht-500.Z.dgn



USER NAME =	DESIGNED - KAC	REVISED -
	CHECKED - BRT	REVISED -
PLOT SCALE =	DRAWN - CEY	REVISED -
PLOT DATE = 3/27/2012	CHECKED - BJM	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 43 (HARLEM AVE)**

SHEET NO. 2 OF 2 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	3127-2-SB-I	COOK	19	4
			CONTRACT NO. 60M71	
ILLINOIS FED. AID PROJECT				